Isometric Standard Project Verification Report

For

Charm Industrial

Client	**Isometric**
Company / GHG Removal Supplier	**Charm Industrial**
Facility or Project Name	**Charm Bio-oil Geologic Storage**
Facility Address	**Bio-oil Production:** **AE Cote-Nord Canada Bioenergy Inc (AECN)** Port Cartier, Quebec, Canada **Bio-oil Injection:** **Charm Industrial** Evangeline Parish, LA, USA
Greenhouse Gas Statement ID/Gas Statement Version ID	**ggs_1KP1ZN1581S0ACDA** **gss_1KPBFB5XW1S0A5PP**
Net Greenhouse Gas Removals	**612.99 tonnes CO_{2e}**
Removal Method	**Bio-oil Geological Storage**
Removal Period	**03MAR – 31MAR2026**
Verification Opinion	**Positive (fully meets criteria)**
Verifier/Validation and Verification Body	**Tim Hansen** **Bill Chatterton** **350Solutions, Inc.**

ISSUED:

APRIL 17, 2026

CONTENTS

1. Key Project Data 3
1.1. Verification Summary 4
2. Verification & Storage Site Validation Details 6
2.1. Verification Objectives 6
2.2. Responsibilities 6
2.3. Level of Assurance & Materiality 6
2.4. Verification Team Details 6
2.5. Audit Process Followed 6
3. Technical Aspects 7
3.1. Project Details 7
3.2. Protocols and Modules Applied 8
3.3. Applicability of Applied Protocol and Modules 8
3.4. Project Boundary 8
3.5. Changes from Previous Verifications 8
3.6. Process & Data Irregularities & Required Exemptions During Reporting Period ... 9
4. Crediting Details 9
4.1. Project Reporting Period 9
4.2. Crediting Period 10
5. GHG Statement Verification & Storage Site Validation 10
5.1. Accuracy of the Statement 10
5.2. Verification Opinion 11
5.3. Verification Results Summary 11
5.4. Verification & Storage Site Validation Findings 13
5.4.1. Critical Findings and Exceptions 13
5.4.2. Forward Action Requests & Recommendations 13
6. Revision History 15
Appendix 1: Documents Submitted for Review 17
Appendix 2: Verification Audit Findings and Responses 18
Appendix 3: Verifier Qualifications 21

ISOMETRIC STANDARD VERIFICATION REPORT

Company: Charm Industrial	Company Contact: *Max Lavine	Validation and Verification Team: *Tim Hansen, PE Bill Chatterton
Removal Method: Bio-oil Geological Storage		
Document No: 350VR-IS.CHA.BO.14		
Rev: v1.2		

** Primary contact/lead author*

1. KEY PROJECT DATA

TABLE 1. VERIFICATION SUMMARY FOR CHARM INDUSTRIAL BIO-OIL STORAGE

Title	Charm Bio-Oil Geologic Storage
Location	Bio-oil Production: AE Cote-Nord Canada Bioenergy Inc (AECN) @ Produits Forestiers Arbec S.E.N.C., 175 Bd du Portage des Mousses Port-Cartier, QC G0W 1X0, Canada 50.025323, -66.818910 Bio-oil Injection & Storage: Charm Industrial (Basco Injection site) Evangeline Parish, LA 30.916251, -92.297908
Reporting Period	March 3 – March 31, 2026
Greenhouse Gas Statement ID	ggs_1KP1ZN1581S0ACDA gss_1KPBFB5XW1S0A5PP
Project Proponents	CDR Supplier: Charm Industrial Feedstock Supplier: Produits Forestiers Arbec S.E.N.C (Quebec mill waste supplier); Altitude Forestry (CO forestry fire prevention waste supplier) Geologic Storage Management: Charm Industrial Salt Cavern Storage Management (Prior Injections): Vaulted Deep Regulatory Agency (Injections / Storage): Louisiana Department of Energy & Natural Resources; Kansas Department of Health & Environment (KDHE) (Prior Injections)
Legal Ownership of the Credits	Charm Industrial
Removals in Reporting Period	612.99 tonnes
Removal Method	Bio-oil Geological Storage
Verification Type & Criteria	Isometric Standard Verification for ongoing deliveries of carbon removal credits by Charm Industrial in accordance with the documents used during project validation: • Isometric Standard v1.8 • Bio-oil Geological Storage Protocol v1.1 • Biomass Feedstock Accounting Module v1.2 • Bio-oil Storage in Permeable Reservoirs v1.1 • Embodied Emissions Accounting v1.0 • Energy Use Accounting v1.2 • Transportation Emissions Accounting v1.1

1.1. VERIFICATION SUMMARY

350Solutions was contracted to perform a project verification of the greenhouse gas (GHG) statement of Charm Industrial's bio-oil geological storage process for the referenced reporting period. The validation report for the Charm Kansas Bio-oil Geologic Storage project was completed on June 25, 2024, by Futurepast, which focused on the use of third-party produced bio-oils and was issued by Isometric for the Crediting Period March 1, 2024 – February 28, 2029. An additional validation of the Charm Bio-oil Geologic Storage project for use of bio-oil produced by Charm was completed on October 18, 2024, for the same crediting period. These validations remain valid for this verification reporting period. Further details and findings can be found in the validation report (https://registry.isometric.com/project/prj_1HZSSWBQM1S08H83#project-documentation). Validation of an additional injection and storage location in Evangeline Parish, Louisiana was completed in September 2025 and is the injection and storage site for all injections during this reporting period. This storage site validation is included in the report located here: https://storage.googleapis.com/isometric--production--eu--public-documents/spl_1H31MW3T81S0R67B/prj_1HZSSWBQM1S08H83/pjd_1K5XPX61T1S0TM0Z/verification_report.pdf.

350Solutions affirms that Charm has the appropriate equipment, procedures, and protocols in place and is documented to quantify GHG removal through the injection of bio-oil into permeable reservoirs via a permitted Class V well in accordance with the requirements of the applicable Isometric standards, protocols and modules.

The carbon removals for the reporting period are provided in Table 2. These values have been verified by 350Solutions.

TABLE 2. VERIFIED TOTAL REMOVALS BY CHARM INDUSTRIAL FOR REPORTING PERIOD ENDING MARCH 31, 2026

Removal ID	Date removal completed	Discounted CO_2e net removed, rounded (kg)
rmv_1KM6CE3M21S0ZQW9	2026-03-12	26640
rmv_1KMGTBJSB1S04X83	2026-03-12	24410
rmv_1KMGTCJM81S0VQ2Q	2026-03-13	28250
rmv_1KMGTDM1W1S0TBD4	2026-03-13	27170
rmv_1KMGTEKM91S0RZQH	2026-03-13	28480
rmv_1KMGTFM7F1S0QM1Y	2026-03-13	26190
rmv_1KMJSCEDH1S0AAVS	2026-03-19	27270
rmv_1KMJSDEZC1S0BK0H	2026-03-19	26620
rmv_1KMJV6SZP1S0EGRK	2026-03-19	25780
rmv_1KMJV7RZM1S0CZTK	2026-03-20	24400
rmv_1KMJV8Q5J1S0BEWK	2026-03-20	26510
rmv_1KMJV9MW91S09XYK	2026-03-19	26520
rmv_1KMR8930Z1S0ZZ6Y	2026-03-20	29250
rmv_1KMR8A1DX1S017BP	2026-03-21	27010

rmv_1KMR8B4941S02FGE	2026-03-21	25950
rmv_1KMR8C6XW1S03QN6	2026-03-21	26450
rmv_1KMR8D9XN1S0EHVH	2026-03-21	25770
rmv_1KMR8E9FQ1S0DHP0	2026-03-21	26530
rmv_1KMR8F8WD1S0CHGF	2026-03-21	25970
rmv_1KMR8G8VC1S0G1ZG	2026-03-22	23520
rmv_1KNMD015E1S0PH5W	2026-03-25	13210
rmv_1KNMGBVGN1S0FBWY	2026-03-25	25850
rmv_1KNMGCH8E1S0PPZN	2026-03-25	25630
rmv_1KNMME8XA1S0MHRB	2026-03-26	19610
TOTAL		612990

The quantity of **612.99 tonnes** of net carbon removals has been verified with a reasonable level of assurance and is eligible for crediting under the referenced Isometric Standard and Protocol.

350Solutions Inc. declares that it is an impartial verification body, approved by Isometric for verifications in the required technical area, free from any conflicts of interest, capable, and qualified to complete this verification for the current reporting period according to the *Isometric Standard v1.8, Bio-oil Geological Storage Protocol v1.1, Biomass Feedstock Accounting Module v1.2.1, Bio-oil Storage in Permeable Reservoirs Module v1.1, Embodied Emissions Accounting v1.0, Transportation Emissions Accounting v1.1,* and *Energy Use Accounting v1.2*.

Verifier Information		
Verification Body	**Verifier**	**Verification ID No.**
350Solutions, Inc.	Tim Hansen	350VR-IS.CHA.BO.14

Timothy A. Hansen

Digitally signed by Timothy A. Hansen
Date: 2026.04.17 08:07:24 -04'00'

Signed: Tim Hansen (Verifier)

Bill Chatterton

Digitally signed by Bill Chatterton
Date: 2026.04.17 08:07:39 -04'00'

Bill Chatterton (QA)

2. VERIFICATION & STORAGE SITE VALIDATION DETAILS

2.1. VERIFICATION OBJECTIVES

A series of verification activities was conducted by 350Solutions to independently verify the claimed removals of the GHG statement submitted by Charm Industrial for operations conducted at the Charm Bio-oil Geologic Storage facility for the referenced Reporting Period. The verification was conducted following the specifications of the standards and protocols cited in Table 1.

2.2. RESPONSIBILITIES

The verification is based on the provision and fair presentation of a complete and accurate GHG Statement submitted by Charm Industrial to the Isometric registry. It is Charm's responsibility to ensure a fair, accurate, and complete presentation of the GHG Statement and Project Design Document are provided. This is confirmed and verified independently by 350Solutions based on supporting evidence in accordance with the Isometric criteria (Table 1, Section 3.2).

2.3. LEVEL OF ASSURANCE & MATERIALITY

The verification was conducted with a reasonable level of assurance. Any discrepancies between the claimed removals of the project and the removals estimated by the verification process for the reporting period are less than the materiality threshold of 5%.

2.4. VERIFICATION TEAM DETAILS

350Solutions is an accredited inspection & verification body by ANAB under ISO 17020:2012 for completion of ISO 14034:2016 Technology Verifications. 350Solutions is headquartered in Raleigh, North Carolina, USA. 350Solutions Technical Lead for the Charm verification is Tim Hansen. Mr. Hansen is a registered Professional Engineer with over 25 years of experience in the evaluation and verification of novel cleantech and carbon technologies. Mr. Hansen has led verifications of carbon removal technologies for multiple registries, including Isometric, and has experience in the development and testing of biomass conversion technologies, including gasification and pyrolysis. The verification report was provided QA by Bill Chatterton, a Carbon Removal Verification Engineer, with experience developing and verifying carbon removal technologies, MRV processes, and LCAs.

2.5. AUDIT PROCESS FOLLOWED

The specific verification and storage site validation activities conducted are summarized in Table 3. The list of all files that were reviewed is provided in Appendix 1. The list of findings from the verification can be found in Appendix 2. Audit results are documented using 350's Compliance Checklist, which includes all requirements from the Isometric standard, Bio-oil Geologic Storage protocol, and referenced modules.

TABLE 3. VERIFICATION ACTIVITIES

Date(s)	Verification Activity	Verification Tasks	Documents Reviewed
April 11, 2026	Review of reporting period modifications and changes	• Review of GHG Statement and report and guidance from Charm	Final V 1.11 Charm Industrial Bio Oil Geologic Storage PDD + Biochar ggs_1KP1ZN1581S0ACDA gss_1KPBFB5XW1S0A5PP Mar3-Apr1_Removals_Isometric_GHG_Statement_Report_v1.7 Mar3-Apr1_2026_VVB_Guidance
April 11-15, 2026	Review of current Validation and GHG Statement Applicability	• Review of Validation Report • Review of prior Verification Report and findings • Identification of major and minor process steps, measurements, and calculations and changes in RP • Review of Standards/Protocols/Modules required for Verification • Generation of a checklist of verification issues and findings and opportunities for improvement	Validation_Report_for_Isometric_Charm_Industrial_Bio-Oil_Project_2024-06-25_r1 Isometric Standard Project Verification & Storage Site Validation Report For Charm Industrial (23Sep2025) Final V 1.11 Charm Industrial Bio Oil Geologic Storage PDD + Biochar ggs_1KP1ZN1581S0ACDA gss_1KPBFB5XW1S0A5PP Mar3-Apr1_Removals_Isometric_GHG_Statement_Report_v1.7 Mar3-Apr1_2026_VVB_Guidance Isometric Standard v1.8, Bio-oil Geological Storage Protocol v1.1, Biomass Feedstock Accounting Module v1.2, Bio-oil Storage in Permeable Reservoirs Module v1.1, Embodied Emissions Accounting v1.0, Transportation Emissions Accounting v1.1, and Energy Use Accounting v1.2
April 14-16, 2026	Verification of Removals	• Verify changes to the system • Review of measurements and calculations • Review of durability/permit requirement monitoring data • Review of GHG statement • Identification of initial findings and follow-up request for information • Write verification report • Internal Quality Assurance	File List provided in Appendix 1. Initial Findings in Appendix 2. Primary verification performed using Isometric Certify and supporting documentation

3. TECHNICAL ASPECTS

3.1. PROJECT DETAILS

Charm obtained bio-oil from a single source during this reporting period. Charm obtains bio-oil from a producer in Quebec, Canada (AECN) who uses an Ensyn/Honeywell UOP pyrolysis system to generate bio-oil from waste biomass produced at a neighboring mill.

Bio-oil from AECN is shipped by tanker truck or rail car to Charm's underground injection and storage facility located in Evangeline Parish, Louisiana for storage into a geologic reservoir. At this facility, Charm pretreats the bio-oil via air sparging and any other required adjustments to ensure bio-oil and aqueous products meet the requirements of the injection facility permit for storage in permeable reservoirs as specified by the Louisiana Department of Energy & Natural Resources (LDENR).

The bio-oil products are blended in on site storage tanks through recirculating pumps and injected as soon as practicable. Samples of the blended bio-oil are collected prior to injection and analyzed for bio-

oil characteristics to ensure compliance with permit requirements. Charm also monitors all injection parameters as required by the Underground Injection Control (UIC) permit.

3.2. PROTOCOLS AND MODULES APPLIED

The verification was conducted following the specifications of the following standards, protocols, and modules:

- Isometric Standard v1.8 [1]
- Bio-oil Geological Storage Protocol v1.1 [2]
- Biomass Feedstock Accounting Module v1.2 [3]
- Bio-oil Storage in Permeable Reservoirs v1.1 [4]
- Embodied Emissions Accounting v1.0 [5]
- Energy Use Accounting v1.2 [6]
- Transportation Emissions Accounting v1.1 [7]

Charm utilizes Book and Claim Units (BCUs) to substitute for some, or all, of project diesel fuel usage and purchases Renewable Energy Certificates (RECs) for some, or all, of its electricity consumption in accordance with the Isometric Energy Use and Transportation Modules.

3.3. APPLICABILITY OF APPLIED PROTOCOL AND MODULES

The Charm project takes mixed woody waste or forestry thinnings from wildfire prevention activities, converts it to bio-oil, which they pretreat and inject into geologic storage formations. The biomass feedstocks were assessed previously under the eligibility criteria of the Isometric Biomass Feedstock Module and were found to be eligible. As the biomass feedstocks have been validated as eligible biomass feedstocks, the storage of biomass conversion products (bio-oil) in a geologic formation makes both the Bio-oil Geological Storage Protocol and Bio-oil Storage in Permeable Reservoirs Module applicable to this project. All other modules for energy, transportation, and embodied emissions accounting are generally applicable to this project.

3.4. PROJECT BOUNDARY

The boundaries of the project include the supply of wood waste to the biomass processing site, the conversion of the biomass to bio-oil via AECN's pyrolysis process, transport of the bio-oil to Charm, completion of pretreatment, and injection of the bio-oil in the geologic reservoir. Monitoring and required analysis of the bio-oil and the storage formation are also included in the project boundary as are all embodied emissions, including end-of-life stage, associated with equipment and consumables.

3.5. CHANGES FROM PREVIOUS VERIFICATIONS

Compared to the prior verification, only minor modifications were made to the Charm Industrial processes, data collection, and calculation procedures which have been specified in the GHG statement and supporting documentation. The following modifications and notes have been provided for clarity. All were reviewed and deemed acceptable under the Isometric requirements:

- Batch 2-155 exhibits a higher-than-typical difference between origin mass and mass of bio-oil injected, attributable to a minor operational spill during handling. The unrecovered oil has been contained in an on-site roll-off container and is scheduled for disposal in April 2026 by a certified third-party environmental remediation vendor. Emissions associated with disposal will be

accounted for when final disposition is known and documentation is available, likely in the next reporting period (noted as a FAR)

- Transport emissions associated with the usage and cleaning of vacuum trailers used for railcar bio-oil transfer operations have been quantified as a single aggregated component. The underlying activity spans January through March 2026, reflecting the full lifecycle of the trailer cleanout process from initiation through completion at Timberlane Landfill.
- BCUs were utilized to offset some of the new emissions associated with site construction, and equipment shipping, in addition to the typical usage for offsetting transportation diesel use.
- There are no emissions associated with Charm production of bio-oil this period, as no Charm oil was injected this period.
- Requirements for monitoring records for prior injections at the Vaulted facility and the required monitoring frequency and submission timing are under discussion with Isometric as operations are moving to a post-injection monitoring plan and approach. Isometric has approved a delay in obtaining and submitting monitoring data for the Vaulted site during this transition period as all parties modify contractual requirements for ongoing monitoring and reporting.
- Note that Charm is continuing to transition additional parts of its reporting to the Isometric Certify platform. As this occurs, certain components may appear partially complete or incomplete in Certify. However, the data has been submitted separately from Certify and verified by 350 as compliant. For this reporting period, Monitoring and Feedstocks requirements are identified in Certify, but entries appear incomplete. However, these items are fully addressed outside of Certify.

3.6. PROCESS & DATA IRREGULARITIES & REQUIRED EXEMPTIONS DURING REPORTING PERIOD

No significant nor critical nonconformities with requirements were identified for this reporting period. Several clarifications and additional data submittals (omissions) were identified and resolved during the audit (See Appendix 2). Minor discrepancies identified were all determined to be non-material to the GHG Statement verification.

It should be noted that the ongoing monitoring required for prior injections at the salt cavern storage site in Kansas (Vaulted Deep) continues to be completed. However, the reporting schedule and verification requirements for such monitoring are under discussion with Isometric and will be completed at a future date. It is also not relevant to the crediting associated with the current reporting period injections. Monitoring report timing and verification requirements for these prior injections are being developed with Isometric.

4. CREDITING DETAILS

4.1. PROJECT REPORTING PERIOD

This verification considers injections of bio-oil (oil and aqueous phases) by Charm during the period March 3 - March 31, 2026. The reporting period is based on the actual injection dates, with bio-oil production, transportation, monitoring, and related activities potentially occurring outside of this reporting period but properly accounted for and allocated to the bio-oil injected within the reporting period.

4.2. CREDITING PERIOD

The 5-year crediting period for the Charm Kansas Bio-oil Geologic Sequestration Project began March 1, 2024, and continues for five years, ending February 28, 2029. All claimed removals in this reporting period fall within the current crediting period.

5. GHG STATEMENT VERIFICATION & STORAGE SITE VALIDATION

5.1. ACCURACY OF THE STATEMENT

Confirmation of the GHG statement has been based on the following efforts:

- Review and confirmation of calculations of total bio-oil and CO_2 equivalent injected and all process, operational, and embodied emissions, as well as all supporting evidence for the following removals:

Removal ID	Date Removal Started
rmv_1KMGTBJSB1S04X83	3/12/2026
rmv_1KNMD015E1S0PH5W	3/25/2026
rmv_1KMR8930Z1S0ZZ6Y	3/20/2026

- This includes for these removals:
  - Re-calculation of mass of bio-oil delivered and injected including tracing to raw data (weigh scale tickets, carbon content lab results, addition of consumables)
  - Confirmation of transportation distances for tanker and rail car deliveries from AECN to Basco site, LA, emission factors, and calculation of transportation emissions
  - Confirmation of weigh scale raw data for deliveries of bio-oil and injectate
  - Confirmation of raw data for and recalculation of total fuel usage at Charm injection facilities
  - Confirmation and recalculation of total electricity usage at Charm and injection facilities
  - Confirmation and recalculation of proper use and accounting of BCUs and RECs to offset diesel and electricity usage emissions, respectively
  - Confirmation and verification of updated embodied emissions for added equipment during the reporting period
- Review of annually updated emissions factors
- Review of monitoring data as required for Basco site injection (preliminary monitoring data and permit requirements) and post injection monitoring to ensure compliance with Class V permit for Basco site
- Review of updated stakeholder engagement activities and grievance log

5.2. VERIFICATION OPINION

350Solutions has reviewed the documentation of the technology, the instrumentation, the procedures, performance and collected data and has found that the data presented in the greenhouse gas removal statement indicates that the claims fall within the 5% materiality threshold for greenhouse gas emissions and removals as required by the Isometric Standard and:

☒ ***Meets the requirements of the Isometric Standard v1.8, Biomass Geological Storage Protocol v1.1, Biomass Feedstock Accounting Module v1.2, and Bio-oil Storage in Permeable Reservoirs Module v1.1 for Verification***

☐ ***Meets the requirements with minor revisions of Isometric Standard v1.8, Biomass Geological Storage Protocol v1.1, Biomass Feedstock Accounting Module v1.2, and Biomass or Bio-oil Storage in Salt Caverns Module v1.1 for Verification***

☐ ***Does Not Meet the requirements of the Isometric Standard v1.8, Biomass Geological Storage Protocol v1.1, Biomass Feedstock Accounting Module v1.2, and Biomass or Bio-oil Storage in Salt Caverns Module v1.1 for Verification***

5.3. VERIFICATION RESULTS SUMMARY

A summary of verification results and compliance with relevant requirements of the *Isometric Standard, Biomass Geological Storage Protocol, Biomass Feedstock Accounting Module*, and *Bio-oil Storage in Permeable Reservoirs Module* are summarized below.

TABLE 4. VERIFICATION RESULTS SUMMARY

Isometric Standard Section Ref.	Verification Topic	Changed since Project Validation? (Y/N)	Final Findings
2.1.	*Validated against approved Protocols*	N	Acceptable – No additional changes since validation
2.5.1	*Boundaries*	N	Acceptable – No additional changes since validation
2.5.2	*Baseline*	N	Acceptable – No change since validation
2.5.3	*Additionality - Financial*	N	Acceptable – No change since validation
2.5.3	*Additionality – Environmental*	N	Acceptable – No change since validation
2.5.3	*Additionality – Regulatory*	N	Acceptable – No change since validation
2.5.4	*Leakage*	N	Acceptable – No change since validation and prior verification.
2.5.5	*Default Emission Factors, Proxies, and Models*	Y	Acceptable – No additional significant changes were made since prior verifications. Emission factors were all updated in March 2026 to reflect any updates from sources in the past year. See Section 3.5 for summary of modifications to any calculation methods, all of which are acceptable.
2.5.11	*Life Cycle Assessment (LCA) Policies*	N	
2.5.6	*Common Calculation Factors*	N	
2.5.7	*Uncertainty*	N	
2.5.8	*Durability and Monitoring*	Y	All updated durability evidence and storage monitoring requirements validated to meet protocol requirements.

Isometric Standard Section Ref.	Verification Topic	Changed since Project Validation? (Y/N)	Final Findings
			Note that ongoing discussions with Isometric and Charm are occurring regarding frequency of Kansas storage site monitoring reports as the prior injections transition into a post-injection / closure monitoring phase with no Charm injections occurring.
2.5.9	*Risk of Reversal*	N	Acceptable – No additional changes since validation
2.5.10 ***3.7***	*Environmental and Socioeconomic Impacts*	N	Acceptable – No additional changes since validation.
3.1	*Ownership*	N	Acceptable – No change since validation
3.2	*Documentation*	Y	Acceptable – No additional changes since prior verification. All documentation properly updated for reporting period
3.3	*Eligibility*	Y (GHG Statement Updated)	Acceptable – Project registered with Isometric and reporting period GHG Statement properly submitted to Isometric dMRV Certify platform.
3.4	*Project Crediting*	Y (GHG Statement Updated)	Acceptable – New reporting period GHG Statement is complete and verified. Reporting period is within current validation crediting period.
3.5	*Stakeholder Input Process*	N	Acceptable – No changes since prior verification
3.6	*Regulatory Compliance*	Y (Required Monitoring Updated)	Required monitoring and reporting completed during reporting period. No additional compliance issues identified for injections during period.
Biomass Feedstock Accounting Module			
2.1	*Eligibility Criteria for Market Leakage*	N	Acceptable – No change since prior feedstock validations
2.2	*Counterfactual Storage Eligibility*	N	Acceptable – No change since prior feedstock validations
2.3	*Dedicated Energy Feedstock Eligibility*	N	Acceptable – No change since prior feedstock validations
3.0	*Counterfactual Definition*	N	Acceptable – No change since prior feedstock validations
3.1	*Counterfactual Energy Definition*	N	Acceptable – No change since prior feedstock validations
3.2	*Counterfactual Replacement Definition*	N	Acceptable – No change since prior feedstock validations

TABLE 5. BASCO STORAGE SITE VERIFICATION SUMMARY

Isometric Standard Section Ref.	Verification Topic	Changed since Project Validation? (Y/N)	Final Findings
Bio-oil Storage in Permeable Reservoirs Module			
1.0	*Storage System Eligibility*	N	Acceptable – No change since validation
2.1	*Storage Reservoir – Permitting*	N	Acceptable – No change since validation
2.2	*Storage Reservoir – Capacity*	N	Acceptable – No change since validation
2.2	*Storage Reservoir – Integrity*	N	Acceptable – No change since validation
2.2	*Storage Reservoir – Integrity: Characterization*	N	Acceptable – No change since validation.

2.2	*Storage Reservoir Characterization – Temperature, pH, conductivity, density*	N	Acceptable – No change since validation
2.2	*Storage Reservoir Characterization – $d^{13}C$ analysis (where applicable)*	NA	Acceptable – Not required
2.3	*Storage Reservoir Integrity – Well Construction*	N	Acceptable – No change since validation
3.1.1	*Storage Reservoir Integrity – Injection operations*	Y	Acceptable – Updated monitoring data provided indicating no exceedances of permit limits
3.1.1	*Storage Reservoir Integrity – Injection operations – Sampling & Analysis*	Y	Acceptable – Updated sampling and analytical data provided indicating no exceedances of permit limits
1.0, 3.2	*Well Closure and Post Closure Requirements*	N	Acceptable – No change since validation
3.1.3	*Injection Pressure*	Y	Acceptable – Pressure is continuously monitored and reported quarterly (monitoring reports indicate full compliance)
3.1.2	*Mechanical Integrity*	N	Acceptable – No change since prior verification
3.1.3	*Volatile Gas Monitoring*	Y	Acceptable – No change to processes since validation. Additional required gas monitoring was completed in February and March and all requirements met
3.1.3	*Reversal Risk & Monitoring*	N	Acceptable – No change since validation
3.3.1	*Attribution of Reversals*	N	Acceptable – No change since validation

5.4. VERIFICATION & STORAGE SITE VALIDATION FINDINGS

5.4.1. CRITICAL FINDINGS AND EXCEPTIONS

Assessment of the greenhouse gas removal statement identified a few minor findings and non-material data issues (see Appendix 2). No significant findings that materially impacted the verified net carbon removals nor compliance with protocol standard were identified. All findings, primarily clarifications and minor data errors, have been addressed and closed.

5.4.2. FORWARD ACTION REQUESTS & RECOMMENDATIONS

Forward action requests (FAR) and recommendations are also provided in Appendix 2 for consideration for improvement of future operations and GHG Removal Credit calculations and to ensure tracking of potential issues to be monitored by verifiers in future verifications. Open FARs and opportunities for improvement are summarized below for future verification reference:

TABLE 6. FORWARD ACTION REQUESTS AND RECOMMENDATIONS

ID No	Type	Finding / Issue	Supplier Response	Conclusion / Resolution
ISS-11 (Prior)	FAR	Charm engaged Guardian Plug and Abandonment to conduct wellhead gas testing as required every 6 months by the Isometric Protocol. The contractor performed the test and found no fugitive leaks at the wellhead. However, as acknowledged by Charm the Isometric protocol also requires testing for CO2 and VOC, which was not completed within the 6 month test period. Charm notes that an additional contractor was hired to complete the CO2 and VOC testing and results will be included in the next Reporting Period.	[Isometric response] Isometric confirm making this request a FAR. There's clear intention and a timeline to obtain the data, and the outcome of the data being 'bad' would be indicative of a reversal which signifies an issue with *all* credits stored in that storage site, not just the credits from the latest verification activity.	Resolved. Required testing completed and testing report and results provided this RP.
ISS-30	FAR	The monitoring data was provided for March, but the monthly report copy to LDENR was not provided. Please upload the LDENR report as well as the email confirmation of receipt.	As with the quarterly reporting requirement, monthly reporting is due within 30 days after the close of the month. So, March reporting would be due at the end of April. When reporting is completed sooner (as was the case with the reporting package submitted in February) we will provide it in the reporting package for the same month. When it is not, it will be included with the subsequent reporting package.	Converted to FAR for next RP
ISS-18	FAR	VVB Guidance document (Google drive) indicates a spill of bio-oil occurred during the reporting period that will be properly disposed of in April. Noting this as a FAR to ensure disposal emissions are accounted for in for the next verification	NA	Review next RP
ISS-14	FAR	Although the air permit may not require monitoring of thermal oxidizer during operation, we would prefer to see evidence that the oxidizer is being operated properly in the future. Can you clarify if oxidizer operational monitoring is done (i.e. temperature logging)	That should not be a problem. This request has been submitted to injection ops for review so we can identify how best to pull and report on this data going forward.	Acceptable. Review in next reporting period

NA	FAR (prior)	With injections no longer occurring at Vaulted, we would like to know how Charm will be notified of closure of the cavern where Charm oil was last injected, and to ensure that Charm will now be obtaining and submitting any post closure monitoring data to Isometric as part of the continued monitoring requirements. Please clarify that plans are in place for this and will be ongoing.	Charm has reached out to Vaulted on multiple occasions to get clarity regarding their future plans for the AR-09 injection well. The well still has considerable capacity and is the property of Vaulted, so it is up to them whether they plug and abandon the well or use it for their own emplacements. This decision on their part will affect the nature of the post-closure monitoring plan. We will continue to request clarity regarding these plans and, once received, we will define and submit a monitoring plan in light of the information we receive.	Verifier to review guidance and requirements from Isometric as ongoing discussions and post-closure monitoring plan requirements are evaluated with Isometric and Charm. Provide post-closure monitoring plan in near future as injections have now transitioned from Vaulted to the Basco facility. (April 2026: guidance provided by Isometric for review and implementation with verification of monitoring proposed in upcoming RPs)
NA	FAR (prior)	With injections no longer occurring at Vaulted, please provide updated contract for post-emplacement / post-closure management and monitoring and post-closure monitoring plan that documents how Charm will be notified of closure of the cavern where Charm oil was last injected, and to ensure that Charm will now be obtaining and submitting any post closure monitoring data to Isometric as part of the continued monitoring requirements or this storage location		See above

6. REVISION HISTORY

Version	Date Issued	Noted Changes
v1.0 (Draft – Internal)	April 16, 2026	N/A Initial Version
v1.1 (Draft – External)	April 16, 2026	Minor edits from QA and Supplier
v1.2 (FINAL)	April 17, 2026	Final Version

References

[1] Isometric, “Isometric Standard v1.8.” [Online]. Available: https://registry.isometric.com/standard/1.8

[2] Isometric, “Bio-oil Geological Storage v.1.1.” [Online]. Available: https://registry.isometric.com/protocol/bio-oil-geological-storage/1.1

[3] Isometric, “Biomass Feedstock Accounting v.1.2.” [Online]. Available: https://registry.isometric.com/protocol/biomass-feedstock-accounting/1.2

[4] Isometric, “Biomass or Bio-oil Storage in Permeable Reservoirs v1.1.” https://registry.isometric.com/module/bio-oil-storage-in-permeable-reservoirs/1.1

[5] Isometric, “Embodied Emissions Accounting v1.0.” [Online]. Available: https://registry.isometric.com/protocol/embodied-emissions/1.0

[6] Isometric, “Energy Use Accounting v1.2.” [Online]. Available: https://registry.isometric.com/protocol/energy-use-accounting/1.2

[7] Isometric, “Transportation Emissions Accounting v1.1.” [Online]. Available: https://registry.isometric.com/protocol/transportation

See Appendix 1 and Table 3 for list of specific files reviewed during the verification.

APPENDIX 1: DOCUMENTS SUBMITTED FOR REVIEW

See source data files available with full Certify access at https://registry.isometric.com/account/certify/project/prj_1HZSSWBQM1S08H83/ghg-statement/ggs_1KP1ZN1581S0ACDA

APPENDIX 2: VERIFICATION AUDIT FINDINGS AND RESPONSES

Code	Type	Title	Body	Status / Resolution	Supplier Response
ISS-30	Omission (converted to FAR)	Basco monthly LDENR report	The monitoring data was provided for March, but the monthly report copy to LDENR was not provided Please upload the LDENR report as well as the email confirmation of receipt.	Open (converted to FAR. Review next RP.	Charm Industrial User (04-15-2026 18:59): As with the quarterly reporting requirement, monthly reporting is due within 30 days after the close of the month. So, March reporting would be due at the end of April. When reporting is completed sooner (as was the case with the reporting package submitted in February) we will provide it in the reporting package for the same month. When it is not, it will be included with the subsequent reporting package.
ISS-29	Clarification Request	Bio-oil mass inquiry	The bio-oil mass on the purchase order and supporting evidence shows 19690kg as reported. However, the weigh scale tickets for deliveries to Basco show 19768 kg. In this case, we are wondering whether the discrepancy should result in the larger value being used here to ensure a conservative estimate is calculated. The total impact will be non-material.	Resolved	Charm Industrial User (04-15-2026 18:47): That is correct -- Per the mass management policy approved by Isometric, in cases where the near-site scale ticket mass is greater than the BOL mass, the BOL mass will be used to determine the Mass of Bio Oil Injected to ensure a conservative estimate of removals. The lower value results in a lower gross removal and thus is more conservative than the higher value.
ISS-28	Clarification Request	Bio-oil Mass Inquiry	The bio-oil mass on the purchase order and supporting evidence shows 19690kg as reported. However, the weigh scale tickets for deliveries to Basco show 19768 kg. In this case, we are wondering whether the discrepancy should result in the larger value being used here to ensure a conservative estimate is calculated. The total impact will be non-material.	Resolved	Charm Industrial User (04-15-2026 18:47): That is correct -- Per the mass management policy approved by Isometric, in cases where the near-site scale ticket mass is greater than the BOL mass, the BOL mass will be used to determine the Mass of Bio Oil Injected to ensure a conservative estimate of removals. The lower value results in a lower gross removal and thus is more conservative than the higher value.
ISS-27	Error	Value mismatch vs evidence & EF incorrect	473.84 kg does not match the value reported in the source file (307.78kg). In addition, it appears that the embodied emissions factor for the railcars was not updated or updated incorrectly. The emission factor provided in Google Drive for the 2026 railcar emissions (embodied) is 0.0000311307. Use of this factor results in a non-material impact, but should be corrected for traceability and accuracy.	Resolved	Charm Industrial User (04-15-2026 16:18): A deprecated version of the calc sheet with the historical EF was attached. Corrected calc sheet with updated data has been attached.
ISS-26	Omission	No Invoice or Delivery evidence	For the quoted use of 1100 gal of methanol in the calculation file, no delivery or invoice evidence is attached. Please upload invoices or similar evidence of amount delivered and/or used	Resolved	Charm Industrial User (04-15-2026 15:58): Invoice for 1100 gallons of methanol has been attached
ISS-25	Omission	Source file is corrupted / blank	Source file on Certify is corrupted or blank. Value checks with Google Drive file provided. Please re-upload source file to Certify	Resolved	Charm Industrial User (04-15-2026 15:53): Non-corrupted file has been attached.

ISS-24	Error	Mismatch between reported value and source file	The listed source shows a slightly lower emissions level than reported here (0.415 vs 0.4306 t). Non-material issue, but should be addressed for traceability and consistency	Resolved	Charm Industrial User (04-15-2026 16:09): A deprecated version of the evidence was attached which had a historical emission factor. The correct evidence has been attached.
ISS-23	Omission	Calculations not fully provided	Please upload the 3_3_26-3_31_26 Gasoline Tracker LA file here as well to ensure all data is in Certify	Resolved	Charm Industrial User (04-15-2026 16:00): Calc sheet has been attached
ISS-22	Error	Mismatch in BCU kg CO2 value	The value provided here (4845.03 kgCO2e) does not match the value for Batch 2-155 provided in the Mar 3-Apr 1 RP BCU Quant spreadsheet (4917 kg CO2e). please clarify and update if needed	Resolved	Tim Hansen (04-15-2026 16:58): Thank you for the clarification. Correct that this is non-material, but identification and fixing of issues helps in traceability and eliminating any confusion for the verifier. Much appreciated. Resolved
ISS-21	Omission	BCU Tracking Spreadsheet should be uploaded here	The BCU tracking spreadsheet that accounts for all usage for the RP should be uploaded along with the corresponding certificate so quantities can be verified in Certify (as opposed to Google Drive)	Resolved	Charm Industrial User (04-15-2026 14:24): Sure thing, sources have been updated
ISS-20	Clarification Request	AECN CI mismatch	The attached AECN H12026 data shows an LCA with a 0.0997 TCO2/Tliquid emission factor. The 010402 factor appears to come from the 'Standard Emission Factors...' file on google drive, with the uncertainty added to result in 0.1038+0.0021 \= 0.10402 emission factor provided here. Can you please clarify which factor is applicable and update as needed?	Resolved	This is a result of a standard methodological practice that is discussed in the PDD: AECN provides an input-output LCA which accounts for conversion energy, but not tailgas emissions.
ISS-19	Clarification Request	Injection timing clarification	Can you please clarify the injection timing? It appears the oil for this injection was delivered 3/6, the sample was collected 3/8, and the injection was completed 3/12. Prior injections seem to have occurred over shorter timeframes (1-2 days), so confirming this is correct.	Resolved	The extended timeline for Batch 2-155 is correct and is directly attributable to the operational spill event referenced in the reporting package guidance. At the start of unloading, a minor spill occurred that required on-site containment before injection operations could proceed. The additional time between delivery (3/6), sampling (3/8), and injection completion (3/12) reflects the operational response to that event â€” Specifically, injection was paused so site staff could focus on containment of the bio-oil contaminated turf an on-site roll-off container and root-cause the issue to prevent any re-occurrence before resuming processing and then injection. The reported mass of bio-oil injected for this batch reflects only the mass confirmed as injected into the subsurface formation. The spilled mass was excluded from the gross removal calculation by having the driver scale in for a new ticket after the spill. The extended timeline does not indicate any change to the injection process itself, but rather the pause required to manage and document the spill responsibly. We have also added a

					transport component accounting for the extra induced round trip to/from the truck scale after the spill.
ISS-18	Omission (converted to FAR)	Pending April bio-oil spill disposal	VVB Guidance document (Google drive) indicates a spill of bio-oil occurred during the reporting period that will be properly disposed of in April. Noting this as a FAR to ensure disposal emissions are accounted for in for the next verification	Open	NA
ISS-17	Clarification Request	Clarification on deadhead emissions for transport	With the noted information in last few verifications related to tanker cleaning, is there any concern regarding increasing deadhead percentage above the default 43.8%? For example, because of cleaning requirements, are tankers in any case being 'dedicated' to Charm and returned empty to source for continued use for bio-oil deliveries (a 100% deadhead rate)?	Resolved	That isn't necessarily the case -- The vendor we use for local short haul engagements is an oil field services vendor who works with many clients in the area. That is why, for example, they are able to supply us with produced water that they have to remove as a waste from their oil and gas clients. As a result, the post-job fate of the truck is not known to us. In some scenarios 100% deadhead may be the fact of the matter, and in others the truck may be used extensively for other purposes between Charm engagements with negligible additional mileage as a result of those engagements. By applying the deadhead to all trips, we can ensure the embodied emissions estimate is conservative in aggregate despite uncertainties with individual deliveries. In any case, if there is a delta would be well below materiality as these are all quite short-haul engagements.
ISS-16	Clarification Request	Clarification of data source	Spreadsheet header says 'GREET 2024 Values', but tanker embodied emissions value listed is the updated 2025 GLEC value from the 'Standard Emission Factors...' spreadsheet. Please clarify and relabel attachment for future verifications to avoid confusion	Resolved	Charm Industrial User (04-14-2026 17:03): That's just a carryover that was not caught -- When we have templated methodologies like this we usually update by copying the sheet and populating with new values. We're usually paying most of our attention to the math, so occasionally a label or heading can slip through the cracks. This has been updated in the source document on our side to avoid future confusion.

APPENDIX 3: VERIFIER QUALIFICATIONS

Supporting documentation, including verifier resumes, and verifier or corporate accreditations are also included in this appendix.

Verifier Qualifications	**Criteria Met?**	**Evidence / Notes** *(note how the criteria was met, specific documents - resume/CV, publications, certifications, etc.).*
Verifier has relevant technical knowledge of the type of technology being evaluated and carbon removal processes in general		
A) Does Verifier have:		
1. An in-depth technical knowledge of the technology type under verification;	☑	350Solutions is accredited to ISO/IEC 17020:2012 and ISO 14034 Environmental Technology Verification (ETV) as a Type A (third party) Inspection Body (ANAB Certificate Number: AI-2618). The technical scope of 350's accreditation includes verification of performance and environmental impact as it relates to design, materials, equipment, installation and operations of technologies in the categories of Energy, Clean Production and Process, and Air Pollution Monitoring and Abatement. As documented in 350Solutions' ETV Standard Operating Procedure (ETV QPM 350-223-03), and Quality Systems Procedures for verifier qualifications (QSP-350-005-02), 350Solutions conforms to the requirements of ISO 17020 Annex A with respect to verifier qualifications and procedures. These procedures and quality management programs are generally relevant to verification under the Isometric Standard. Note that verifications completed for Isometric are not equivalent to ISO 14034 verifications. 350 staff have participated in the evaluation and verification of novel technologies that sequester carbon via various methods, including biomass conversion to liquids, solids, and other products which are then permanantly stored in ways such as land application or geologic storage, conversion of captured CO2 into building materials and co-products, and the production of chemicals, fuels, and products via biomass pyrolysis and gasification. 350 also served as lead verifier for the Carbon XPrize competition and contributed to the development of procedures and processes for verification of relevant calculations, modeling, and statistical methods in order to assess team results and calculations of performance metrics and uncertainty. 350 has demonstrated knowledge of data quality and data validation approaches and execution in supporting verification of performance claims and results.
2. Knowledge of specific risk areas associated with performance of such technologies (i.e. common failure points, performance issues, barriers to scaleup);	☑	
3. Knowledge of the environmental implications related to the use of the technology from a life cycle perspective, such as impact of the technology on lifecycle CO2 emissions and carbon removal;	☑	
4. Knowledge of relevant applicable test methods and standards for evaluating performance or impact of the technology;	☑	
5. Knowledge of relevant calculation, modeling, and statistical methods in order to assess test results and calculations of performance metrics and uncertainty, as applicable;	☑	
6. Knowledge of data quality and data validation approaches, including QA/QC procedures, for example.	☑	
Verifier is a credible independent 3rd party		
B) Is Verifier:		
1. third-party body independent of the team registered for the Isometric Registry	☑	350Solutions is accredited to ISO/IEC 17020:2012 and ISO 14034 ETV as a Type A (third party) Inspection Body. As documented in 350Solutions ETV Policy Manual (ETV QPM 350-200-03), 350Solutions conforms to the requirements of ISO 17020 Annex A with respect to impartiality for Type A inspections, pursuant to ISO 14034 activities.
2. Not directly involved in the design, manufacture or construction, marketing, installation, use or maintenance of the specific technologies submitted to Isometric for verification, or represent the parties engaged in those activities.	☑	
3. Not part of a legal entity that is engaged in design, manufacture, supply, installation, purchase, ownership, use or maintenance of the items inspected.	☑	

Tim Hansen, P.E.
Founder and CEO, 350Solutions

EDUCATION:
B.S., Chemical Engineering, University of Virginia, 1993
M.S., Engineering Science, Thayer School of Engineering, Dartmouth College, 1995

EXPERIENCE SUMMARY:
Mr. Hansen has 26 years of experience in management of energy and environmental technology development and demonstration projects and programs, as well as multimedia environmental engineering efforts. The majority of his recent work has focused on the evaluation of innovative carbon capture, utilization, and removal technologies. Mr. Hansen has led the development and management of large technology evaluation programs in the advanced energy, transportation, and climate change areas.

RESEARCH AND PROFESSIONAL EXPERIENCE:
2019-Present Founder – CEO, 350Solutions, Inc.
Owns and operates a small cleantech engineering consulting business focused on the independent evaluation of new cleantech innovations and their impact on the environment and carbon emissions. Provides engineering consulting, testing and evaluation, techno-economic assessment, and other support to companies developing, using, or investing in new clean technology innovations. Manages administrative, business development, and project activities for 350Solutions.

2012-2019: Director - Energy and Environment, Southern Research
Manages scientific and technical staff performing research, development, and evaluation of innovative clean energy technologies. Projects range from $25,000 to $6million in size, and are funded by the US Department of Energy, Department of Defense, and commercial partners. Technical focus areas are conversion of biomass to fuels and chemicals, carbon capture and utilization, energy efficient building technologies and renewable energy generation.

2009-2012: Program Manager – Transportation & Climate Change Technology, Southern Research
2003-2009 Sr. Project Leader, Environmental Engineer, Southern Research
1996-2003 Environmental Engineer, Bensinger & Garrison Environmental

PROJECT EXPERIENCE:
Mr. Hansen has executed several independent technology performance verifications of emerging carbon, energy and transportation technologies, as CEO of 350Solutions, Director of Energy & Environment at Southern Research, and Director of the U.S. EPA's Greenhouse Gas Technology Center. Mr. Hansen has completed clean technology evaluations for the Department of Defense, state energy agencies, commercial clients, investors, and technology developers, involving evaluation of commercial feasibility, economic and environmental impacts, and technology performance. Mr. Hansen served as the Measurement and Verification Program Lead for the NRG COSIA Carbon XPrize – a $20M prize competition for technologies that capture and beneficially utilize CO_2. Mr. Hansen also served as U.S. Technical Expert for the development and implementation of ISO 14034 – Environmental Technology Verification, an international standard, issued in 2016

Bill Chatterton
Senior Verification Scientist, 350Solutions

EDUCATION:
B.S. Environmental Science, SUNY at Plattsburgh, 1982
A.A.S. Environmental Technology, Paul Smith College, 1979
Certified Measurement and Verification Professional (CMVP), 2019

EXPERIENCE SUMMARY:
Mr. Chatterton has over 30 years of experience in management of energy and environmental technology development and demonstration projects and programs, as well as multimedia environmental engineering efforts. The majority of his recent work has focused on the evaluation of innovative carbon capture, utilization, and removal technologies. Mr. Chatterton has supported the development and management of large technology evaluation programs in the advanced energy, transportation, and climate change areas.

RESEARCH AND PROFESSIONAL EXPERIENCE:
2019-Present Sr Verification Scientist – 350Solutions, Inc.
Owns and operates a small cleantech engineering consulting business focused on the independent evaluation of new cleantech innovations and their impact on the environment and carbon emissions. Provides engineering consulting, testing and evaluation, techno-economic assessment, and other support to companies developing, using, or investing in new clean technology innovations. Manages administrative, business development, and project activities for 350Solutions.

2010-2019: Program Manager - Energy and Environment, Southern Research
Managed scientific and technical staff performing research, development, and evaluation of innovative clean energy technologies. Projects range from $25,000 to $6million in size, and are funded by the US Department of Energy, Department of Defense, and commercial partners. Technical focus areas are conversion of biomass to fuels and chemicals, carbon capture and utilization, energy efficient building technologies and renewable energy generation.

2000-2009 Sr. Project Leader, Environmental Engineer, Southern Research

PROJECT EXPERIENCE:
Mr. Chatterton has executed several independent technology performance verifications of emerging carbon, energy and transportation technologies for 350Solutions and previously at Southern Research Institute. Mr. Chatterton has completed clean technology evaluations for the Department of Defense, state energy agencies, commercial clients, investors, and technology developers, involving evaluation of commercial feasibility, economic and environmental impacts, and technology performance. Mr. Chatterton served as a Lead Verifier for the NRG COSIA Carbon XPrize – a $20M prize competition for technologies that capture and beneficially utilize CO_2. Mr. Chatterton is also a Certified Measurement and Verification Professional, issued in 2019.