Isometric Standard Project Verification Report

For

Charm Industrial

Client	**Isometric**
Company / GHG Removal Supplier	**Charm Industrial**
Facility or Project Name	**Charm Bio-oil Geologic Storage**
Facility Address	**Bio-oil Production:** **AE Cote-Nord Canada Bioenergy Inc (AECN)** Port Cartier, Quebec, Canada **Charm Miniforge** Fort Lupton, CO, USA **Kerry, Inc.** Manitowoc, WI, USA **Bio-oil Injection:** **Charm Industrial** Evangeline Parish, LA, USA
Greenhouse Gas Statement ID/Gas Statement Version ID	**ggs_1KRJ5CK771S0GEYB** **gss_1KRJ5DP7H1S0METE**
Net Greenhouse Gas Removals	**490.82 tonnes CO_{2e}**
Removal Method	**Bio-oil Geological Storage**
Removal Period	**01APR – 30APR2026**
Verification Opinion	**Positive (fully meets criteria)**
Verifier/Validation and Verification Body	**Tim Hansen** **Bill Chatterton** **350Solutions, Inc.**

ISSUED:

MAY 27, 2026

CONTENTS

1. Key Project Data 3
1.1. Verification Summary 4
2. Verification & Storage Site Validation Details 6
2.1. Verification Objectives 6
2.2. Responsibilities 6
2.3. Level of Assurance & Materiality 6
2.4. Verification Team Details 6
2.5. Audit Process Followed 6
3. Technical Aspects 7
3.1. Project Details 7
3.2. Protocols and Modules Applied 8
3.3. Applicability of Applied Protocol and Modules 9
3.4. Project Boundary 9
3.5. Changes from Previous Verifications 9
3.6. Process & Data Irregularities & Required Exemptions During Reporting Period ..10
4. Crediting Details 10
4.1. Project Reporting Period 10
4.2. Crediting Period 11
5. GHG Statement Verification & Storage Site Validation 11
5.1. Accuracy of the Statement 11
5.2. Verification Opinion 12
5.3. Verification Results Summary 12
5.4. Verification & Storage Site Validation Findings 14
5.4.1. Critical Findings and Exceptions 14
5.4.2. Forward Action Requests & Recommendations 14
6. Revision History 16
Appendix 1: Documents Submitted for Review 18
Appendix 2: Verification Audit Findings and Responses 18
Appendix 3: Verifier Qualifications 31

ISOMETRIC STANDARD VERIFICATION REPORT

Company: Charm Industrial	Company Contact: *Max Lavine Garrett Lutz	Validation and Verification Team: *Tim Hansen, PE Bill Chatterton
Removal Method: Bio-oil Geological Storage		
Document No: 350VR-IS.CHA.BO.15		
Rev: v1.2		

** Primary contact/lead author*

1. KEY PROJECT DATA

TABLE 1. VERIFICATION SUMMARY FOR CHARM INDUSTRIAL BIO-OIL STORAGE

Title	Charm Bio-Oil Geologic Storage
Location	Bio-oil Production: AE Cote-Nord Canada Bioenergy Inc (AECN) @ Produits Forestiers Arbec S.E.N.C., 175 Bd du Portage des Mousses Port-Cartier, QC G0W 1X0, Canada 50.025323, -66.818910 Charm Industrial Miniforge 2360 S Rollie Ave Fort Lupton, CO, USA 80621 40.076570, -104.804680 Kerry, Inc. Red Arrow 4343 Expo Drive Manitowoc, WI 54220 44.080613, -87.704757 Bio-oil Injection & Storage: Charm Industrial (Basco Injection site) Evangeline Parish, LA 30.916251, -92.297908
Reporting Period	April 1 – April 30, 2026
Greenhouse Gas Statement ID	ggs_1KRJ5CK771S0GEYB gss_1KRJ5DP7H1S0METE
Project Proponents	CDR Supplier: Charm Industrial Feedstock Supplier: Produits Forestiers Arbec S.E.N.C (Quebec mill waste supplier); Altitude Forestry (CO forestry fire prevention waste supplier); Kerry Inc. Geologic Storage Management: Charm Industrial Salt Cavern Storage Management (Prior Injections): Vaulted Deep Regulatory Agency (Injections / Storage): Louisiana Department of Energy & Natural Resources; Kansas Department of Health & Environment (KDHE) (Prior Injections)
Legal Ownership of the Credits	Charm Industrial
Removals in Reporting Period	490.82 tonnes

Removal Method	Bio-oil Geological Storage
Verification Type & Criteria	Isometric Standard Verification for ongoing deliveries of carbon removal credits by Charm Industrial in accordance with the documents used during project validation: • Isometric Standard v1.8 • Bio-oil Geological Storage Protocol v1.2 (Kerry Bio-oil), v1.1 (AECN and Charm Bio-oil) • Biomass Feedstock Accounting Module v1.3 (Kerry Feedstock), v1.2 (AECN and Charm feedstocks)* • Biomass or Bio-oil Storage in Permeable Reservoirs v1.2 • Embodied Emissions Accounting v1.0 • Energy Use Accounting v1.2 • Transportation Emissions Accounting v1.1

*NOTE THAT CHARM BIO-OIL PRODUCED AFTER DECEMBER, 2025 UTILIZES NEW FEEDSTOCK VALIDATED UNDER BIOMASS FEEDSTOCK ACCOUNTING MODULE V 1.3.

1.1. VERIFICATION SUMMARY

350Solutions was contracted to perform a project verification of the greenhouse gas (GHG) statement of Charm Industrial's bio-oil geological storage process for the referenced reporting period. The validation report for the Charm Kansas Bio-oil Geologic Storage project was completed on June 25, 2024, by Futurepast, which focused on the use of third-party produced bio-oils and was issued by Isometric for the Crediting Period March 1, 2024 – February 28, 2029. An additional validation of the Charm Bio-oil Geologic Storage project for use of bio-oil produced by Charm at the Fort Lupton Miniforge facility was completed on October 18, 2024, for the same crediting period. These validations remain valid for this verification reporting period. Further details and findings can be found in the validation report (https://registry.isometric.com/project/prj_1HZSSWBQM1S08H83#project-documentation). Validation of an additional injection and storage location in Evangeline Parish, Louisiana was completed in September 2025 and is the injection and storage site for all injections during this reporting period. This storage site validation is included in the report located here: https://storage.googleapis.com/isometric--production--eu--public-documents/spl_1H31MW3T81S0R67B/prj_1HZSSWBQM1S08H83/pjd_1K5XPX61T1S0TM0Z/verification_report.pdf. Validation of a new feedstock used by Charm was completed in December, 2025, and a new feedstock for bio-oil produced by Kerry, Inc. for injection was completed on February 12, 2026.

350Solutions affirms that Charm has the appropriate equipment, procedures, and protocols in place and is documented to quantify GHG removal through the injection of bio-oil into permeable reservoirs via a permitted Class V well in accordance with the requirements of the applicable Isometric standards, protocols and modules.

The carbon removals for the reporting period are provided in Table 2. These values have been verified by 350Solutions.

TABLE 2. VERIFIED TOTAL REMOVALS BY CHARM INDUSTRIAL FOR REPORTING PERIOD ENDING APRIL 30, 2026

Removal ID	Date removal completed	Discounted CO_2e net removed, rounded (kg)	Bio-oil Source
rmv_1KQ7XY3Q81S0T52T	2026-04-02	30390	AECN
rmv_1KQ7XZ14K1S09ANA	2026-04-02	32560	AECN
rmv_1KQ7Y019T1S0X0WC	2026-04-02	31340	AECN
rmv_1KQ7Y0Y4S1S023MT	2026-04-02	17080	AECN
rmv_1KQB5HD031S0REDR	2026-04-03	30260	AECN
rmv_1KQB5JF7Q1S0GN9C	2026-04-03	29470	AECN
rmv_1KQB5KCQG1S0JYZ2	2026-04-03	29630	AECN
rmv_1KQB5MBJB1S0N8MR	2026-04-03	21040	AECN
rmv_1KQJFNB7E1S0X8B9	2026-04-01	30770	AECN
rmv_1KQJFP6Q41S0778B	2026-04-01	23230	AECN
rmv_1KQJKPBTM1S0KPEX	2026-04-10	26270	AECN
rmv_1KQJKQCX31S07CNZ	2026-04-11	25700	AECN
rmv_1KQJKRFN61S0EQRP	2026-04-11	36930	AECN
rmv_1KQT5AWP41S0D5MG	2026-04-01	8800	Kerry
rmv_1KQT77FNY1S0J259	2026-04-23	30520	AECN
rmv_1KQYYB3JV1S0RD0R	2026-04-29	6840	AECN
rmv_1KRC7TQXH1S0EZ1X	2026-04-01	1110	Charm
rmv_1KRCH29WH1S0FSR3	2026-04-02	1530	Charm
rmv_1KREBHF111S0DH8N	2026-04-29	4290	Charm
rmv_1KREM359J1S0BC1B	2026-04-11	16650	AECN
rmv_1KREM4CV41S0KXXD	2026-04-11	37430	AECN
rmv_1KRH4CXAP1S0M44D	2026-04-23	18980	AECN
TOTAL		490820	

The quantity of **490.82 tonnes** of net carbon removals has been verified with a reasonable level of assurance and is eligible for crediting under the referenced Isometric Standard and Protocol.

350Solutions Inc. declares that it is an impartial verification body, approved by Isometric for verifications in the required technical area, free from any conflicts of interest, capable, and qualified to complete this verification for the current reporting period according to the standards and protocols identified in Table 1.

Verifier Information		
Verification Body	**Verifier**	**Verification ID No.**
350Solutions, Inc.	Tim Hansen	VR-IS.CHA.BO.15

Timothy A. Hansen
Digitally signed by Timothy A. Hansen
Date: 2026.05.27 11:14:00 -04'00'

Signed: Tim Hansen (Verifier)

Bill Chatterton
Digitally signed by Bill Chatterton
Date: 2026.05.27 11:13:40 -04'00'

Bill Chatterton (QA)

2. VERIFICATION DETAILS

2.1. VERIFICATION OBJECTIVES

A series of verification activities was conducted by 350Solutions to independently verify the claimed removals of the GHG statement submitted by Charm Industrial for operations conducted at the Charm Bio-oil Geologic Storage facility for the referenced Reporting Period. The verification was conducted following the specifications of the standards and protocols cited in Table 1.

2.2. RESPONSIBILITIES

The verification is based on the provision and fair presentation of a complete and accurate GHG Statement submitted by Charm Industrial to the Isometric registry. It is Charm's responsibility to ensure a fair, accurate, and complete presentation of the GHG Statement and Project Design Document are provided. This is confirmed and verified independently by 350Solutions based on supporting evidence in accordance with the Isometric criteria (Table 1, Section 3.2).

2.3. LEVEL OF ASSURANCE & MATERIALITY

The verification was conducted with a reasonable level of assurance. Any discrepancies between the claimed removals of the project and the removals estimated by the verification process for the reporting period are less than the materiality threshold of 5%.

2.4. VERIFICATION TEAM DETAILS

350Solutions is an accredited inspection & verification body by ANAB under ISO 17020:2012 for completion of ISO 14034:2016 Technology Verifications. 350Solutions is headquartered in Raleigh, North Carolina, USA. 350Solutions Technical Lead for the Charm verification is Tim Hansen. Mr. Hansen is a registered Professional Engineer with over 25 years of experience in the evaluation and verification of novel cleantech and carbon technologies. Mr. Hansen has led verifications of carbon removal technologies for multiple registries, including Isometric, and has experience in the development and testing of biomass conversion technologies, including gasification and pyrolysis. The verification report was provided QA by Bill Chatterton, a Carbon Removal Verification Engineer, with experience developing and verifying carbon removal technologies, MRV processes, and LCAs.

2.5. AUDIT PROCESS FOLLOWED

The specific verification and storage site validation activities conducted are summarized in Table 3. The list of all files that were reviewed is provided in Appendix 1. The list of findings from the verification can be found in Appendix 2. Audit results are documented using 350's Compliance Checklist, which includes all requirements from the Isometric standard, Bio-oil Geologic Storage protocol, and referenced modules.

TABLE 3. VERIFICATION ACTIVITIES

Date(s)	Verification Activity	Verification Tasks	Documents Reviewed
May 15, 2026	Review of reporting period modifications and changes	• Review of GHG Statement and report and guidance from Charm	Final V 1.11 Charm Industrial Bio Oil Geologic Storage PDD + Biochar ggs_1KRJ5CK771S0GEYB gss_1KRJ5DP7H1S0METE Apr1-Apr30_Removals_Isometric_GHG_Statement_Report_v1.7 April 1 – April 30 VVB Guidance
May 15-18, 2026	Review of current Validation and GHG Statement Applicability	• Review of Validation Report • Review of prior Verification Report and findings • Identification of major and minor process steps, measurements, and calculations and changes in RP • Review of Standards/Protocols/Modules required for Verification • Generation of a checklist of verification issues and findings and opportunities for improvement	Validation_Report_for_Isometric_Charm_Industrial_Bio-Oil_Project_2024-06-25_r1 Isometric Standard Project Verification & Storage Site Validation Report For Charm Industrial (23Sep2025) Final V 1.11 Charm Industrial Bio Oil Geologic Storage PDD + Biochar ggs_1KRJ5CK771S0GEYB gss_1KRJ5DP7H1S0METE Apr1-Apr30_Removals_Isometric_GHG_Statement_Report_v1.7 April 1 – April 30 VVB Guidance Isometric Standard v1.8, Bio-oil Geological Storage Protocol v1.1, Biomass Feedstock Accounting Module v1.2, Bio-oil Storage in Permeable Reservoirs Module v1.1, Embodied Emissions Accounting v1.0, Transportation Emissions Accounting v1.1, and Energy Use Accounting v1.2
May 15-22, 2026	Verification of Removals	• Verify changes to the system • Review of measurements and calculations • Review of durability/permit requirement monitoring data • Review of GHG statement • Identification of initial findings and follow-up request for information • Write verification report • Internal Quality Assurance	File List provided in Appendix 1. Initial Findings in Appendix 2. Primary verification performed using Isometric Certify and supporting documentation

3. TECHNICAL ASPECTS

3.1. PROJECT DETAILS

Charm obtained bio-oil from three sources during this reporting period. Charm obtains bio-oil from a producer in Quebec, Canada (AECN) who uses an Ensyn/Honeywell UOP pyrolysis system to generate bio-oil from waste wood produced at a neighboring mill.

In addition, Charm produces bio-oil at its pyrolysis facility in Fort Lupton, CO. Production of bio-oil for sequestration and carbon removal credit generation began in August of 2024, with the initial installation of four pyrolyzers, with plans for up to 18 pyrolyzers total to be installed. Charm's pyrolyzers utilize wood chips, placed into a high temperature pressurized reactor in a low oxygen environment to reduce the wood chips into a combination of products, including syngas and light hydrocarbon gases, pyrolysis oils, biochar, and wood vinegar. All hot pyrolysis gases from the reactor are quenched with water to produce the oil and wood vinegar products. Excess gases are routed to a combustion device for emissions control, with the heat produced from the combustion of excess gas utilized for drying the

biomass from 40%-50% moisture content to 10% moisture content before introduction into the pyrolyzer.

Finally, Kerry Inc pyrolyzes woody biomass to produce liquid smoke, a popular flavoring product. This process produces a carbon-rich liquid pyrolysis oil which is intentionally phase separated. The "light ends" of the separated product are refined to produce the primary product of the system. The "heavy ends" are a waste product with high biogenic carbon content. While some of that product is combusted on-site to generate energy, the remainder is typically disposed of by incineration without energy capture. Charm has contracted with Kerry to purchase this waste material for durable carbon removals.

Bio-oil from AECN, Kerry, and Charm, and aqueous fraction product from Charm pyrolyzers are shipped by tanker truck, rail car, or tote tanks on flatbed to the injection facility in Louisiana. At this facility, Charm pretreats the bio-oil via air sparging and any other required adjustments to ensure bio-oil and aqueous product meet the requirements of the injection facility permit for storage in permeable reservoirs as specified by the Louisiana Department of Energy & Natural Resources (LDENR).

The bio-oil products are blended in on site storage tanks through recirculating pumps and injected as soon as practicable. Samples of the blended bio-oil are collected prior to injection and analyzed for bio-oil characteristics to ensure compliance with permit requirements. Charm also monitors all injection parameters as required by the Underground Injection Control (UIC) permit.

3.2. PROTOCOLS AND MODULES APPLIED

The verification was conducted following the specifications of the following standards, protocols, and modules:

- Isometric Standard v1.8 [1]
- Bio-oil Geological Storage Protocol v1.2 (Kerry Bio-oil), v1.1 (AECN and Charm Bio-oil)[2]
- Biomass Feedstock Accounting Module v1.3 (Kerry Feedstock), v1.2 (AECN and Charm feedstocks)[3]
- Biomass or Bio-oil Storage in Permeable Reservoirs v1.2 [4]
- Embodied Emissions Accounting v1.0 [5]
- Energy Use Accounting v1.2 [6]
- Transportation Emissions Accounting v1.1 [7]

Bio-oil supplied by AECN and Charm bio-oil produced prior to December, 2025 were validated under Biomass Feedstock Accounting Module v1.2 and Bio-oil Geologic Storage Protocol v1.1, and remain validated under these modules. Bio-oil provided by Kerry, Inc. and Charm bio-oil produced in December, 2025 and later are validated under updated versions of the feedstock module (v1.3) and storage protocol (v1.2).

Charm utilizes Book and Claim Units (BCUs) to substitute for some, or all, of project diesel fuel usage and purchases Renewable Energy Certificates (RECs) for some, or all, of its electricity consumption in accordance with the Isometric Energy Use and Transportation Modules.

3.3. APPLICABILITY OF APPLIED PROTOCOL AND MODULES

The Charm project takes mixed woody waste or forestry thinnings from wildfire prevention activities, converts it to bio-oil, which they pretreat and inject into geologic storage formations. The biomass feedstocks were assessed previously under the eligibility criteria of the Isometric Biomass Feedstock Module and were found to be eligible. As the biomass feedstocks have been validated as eligible biomass feedstocks, the storage of biomass conversion products (bio-oil) in a geologic formation makes both the Bio-oil Geological Storage Protocol and Biomass or Bio-oil Storage in Permeable Reservoirs Module applicable to this project. All other modules for energy, transportation, and embodied emissions accounting are generally applicable to this project.

3.4. PROJECT BOUNDARY

The boundaries of the project include the supply of wood waste to the biomass processing site, the conversion of the biomass to bio-oil via AECN's pyrolysis process, transport of the bio-oil to Charm, completion of pretreatment, and injection of the bio-oil in the geologic reservoir. Monitoring and required analysis of the bio-oil and the storage formation are also included in the project boundary as are all embodied emissions, including end-of-life stage, associated with equipment and consumables.

3.5. CHANGES FROM PREVIOUS VERIFICATIONS

Several minor changes, updates, or unique scenarios were identified by Charm for the current reporting period regarding the Charm Industrial processes, data collection, and calculation procedures which have been specified in the GHG statement and supporting documentation. The following modifications and notes have been provided for clarity. All were reviewed and deemed acceptable under the Isometric requirements:

- A discrete portion of the biomass processed during November 2025 was diverted for internal Research & Development (R&D) activities and is therefore not eligible for inclusion in the carbon removal accounting for those production periods. The R&D-allocated mass has been quantified, documented in the supporting evidence files, and netted out of the gross biomass throughput totals prior to entry in Certify.
- Kerry oil batches are aggregated from multiple totes prior to injection. Each constituent tote is independently sampled and analyzed for carbon content via CHN laboratory testing. The carbon content value entered into Certify for a given Kerry oil batch represents a mass-weighted average of the individual tote C% values, rather than a single laboratory result.
- Batches 2-194-KS-RC and 2-195-KS-RC account for recovered bio-oil from three (3) railcars that have been held in storage at a railspur in Maize, Kansas. Owing to the age of the oil, only the flowable fraction was extracted for transport and injection; mass quantification is conducted under standard scale-ticket protocols.
- The brine flow sensor required repair on April 29, 2026. For the affected interval, Charm reverts to its prior practice of using delivery invoices as the source of record for brine consumption volumes;
- Excavation site work was completed in March 2026 at the Basco site for expansion. Because this excavation is a discrete component of a larger capital project, the associated embodied and combustion emissions are reported in the Reporting Period in which the tank was commissioned (April 2026).
- For the current Reporting Period, two AECN bio-oil batches (2-192 and 2-199) returned laboratory carbon content values materially above the population mean observed across all calendar year 2026 Reporting Periods to date. To prevent any single laboratory measurement

from exerting disproportionate influence on aggregate removal quantification, Charm applies a 3-sigma winsorization rule consistent with Bio Oil Geological Storage 7.4.1.1.1's program for handling C content outliers.

- The Opelousas→Basco trucking leg is the only route primarily operated by Charm-owned vehicles. Unlike contracted carriers — whose broader operations implicitly amortize backhaul mileage and embodied-asset emissions across many runs — Charm's dedicated trucks haul exclusively for this project, so the empty return trip is a real, project-attributable emission that the current model does not otherwise capture, which is fully accounted for as a deadhead complete trip in emission calculations (2x mileage).
- Charm refreshes its Standard EF table annually in March; production periods that close prior to the March refresh (Nov 2025–Feb 2026) appropriately apply prior-year (2025) EFs, while the March 2026 PP Summary and all subsequent production periods through March of 2027 apply the updated 2026 EFs.
- Batch 5-10 draws Charm bio-oil produced across multiple Production Periods (June 2025 through December 2025). Rather than creating a separate Production Period component in Certify for each source PP, Charm applies a single mass-weighted average of per-PP carbon intensity across the contributing production periods.
- Requirements for monitoring records for prior injections at the Vaulted facility and the required monitoring frequency and submission timing have been under discussion with a plan to review all monitoring records and compliance on a regular basis, with future monitoring compliance verification anticipated within the next two reporting periods as a separate verification process. Isometric has approved the delay in obtaining and submitting monitoring data for the Vaulted site during this transition period as all parties modify contractual requirements for ongoing monitoring and reporting.
- Note that Charm is continuing to transition additional parts of its reporting to the Isometric Certify platform. As this occurs, certain components may appear partially complete or incomplete in Certify. However, the data has been submitted separately from Certify and verified by 350 as compliant. For this reporting period, Monitoring and Feedstocks requirements are identified in Certify, but entries appear incomplete. However, these items are fully addressed outside of Certify.

3.6. PROCESS & DATA IRREGULARITIES & REQUIRED EXEMPTIONS DURING REPORTING PERIOD

No nonconformities were identified for this reporting period. Several clarifications and additional data submittals (omissions) were identified and resolved during the audit (See Appendix 2). No material discrepancies were identified that would impact the GHG Statement verification.

4. CREDITING DETAILS

4.1. PROJECT REPORTING PERIOD

This verification considers injections of bio-oil (oil and aqueous phases) by Charm during the period April 1 – April 30, 2026. The reporting period is based on the actual injection dates, with bio-oil production, transportation, monitoring, and related activities potentially occurring outside of this reporting period but properly accounted for and allocated to the bio-oil injected within the reporting period.

4.2. CREDITING PERIOD

The 5-year crediting period for the Charm Kansas Bio-oil Geologic Sequestration Project began March 1, 2024, and continues for five years, ending February 28, 2029. All claimed removals in this reporting period fall within the current crediting period.

5. GHG STATEMENT VERIFICATION

5.1. ACCURACY OF THE STATEMENT

Confirmation of the GHG statement has been based on the following efforts:

- Review and confirmation of calculations of total bio-oil and CO_2 equivalent injected and all process, operational, and embodied emissions, as well as all supporting evidence for the following removals, representing all injected feedstocks and process emissions:

Removal ID	Feedstock
rmv_1KQJFP6Q41S0778B	AECN
rmv_1KQT5AWP41S0D5MG	Kerry
rmv_1KRC7TQXH1S0EZ1X	Charm (oil)
rmv_1KREBHF111S0DH8N	Charm (wood vinegar)
rmv_1KRH4CXAP1S0M44D	AECN (includes all Basco site emissions)

- This includes for these removals:
    - Re-calculation of mass of bio-oil delivered and injected including tracing to raw data (weigh scale tickets, carbon content lab results, addition of consumables)
    - Confirmation of transportation distances for tanker and rail car deliveries from AECN, Charm, and Kerry to Basco site, LA, emission factors, and calculation of transportation emissions
    - Confirmation of weigh scale raw data for deliveries of bio-oil and injectate
    - Confirmation of Charm oil production emissions for previously unverified production periods, including review of all supporting evidence and data used for production emission calculation
    - Confirmation of raw data for and recalculation of total fuel usage at Charm injection facilities
    - Confirmation and recalculation of total electricity usage at Charm injection facilities
    - Confirmation and recalculation of proper use and accounting of BCUs and RECs to offset diesel and electricity usage emissions, respectively
    - Confirmation and verification of updated embodied emissions totals for added equipment during the reporting period
    - Complete review of embodied emissions allocation and status vs. allocation forecast
- Review of monitoring data as required for Basco site injection (preliminary monitoring data and permit requirements) and post injection monitoring to ensure compliance with Class V permit for Basco site
- Review of updated stakeholder engagement activities and grievance log

5.2. VERIFICATION OPINION

350Solutions has reviewed the documentation of the technology, the instrumentation, the procedures, performance and collected data and has found that the data presented in the greenhouse gas removal statement indicates that the claims fall within the 5% materiality threshold for greenhouse gas emissions and removals as required by the Isometric Standard and:

☒ ***Meets the requirements of the Isometric Standard, Bio-oil Geological Storage Protocol, Biomass Feedstock Accounting Module, and Biomass or Bio-oil Storage in Permeable Reservoirs Module versions specified in Table 1 for Verification***

☐ ***Meets the requirements with minor revisions of Isometric Standard, Bio-oil Geological Storage Protocol, Biomass Feedstock Accounting Module, and Biomass or Bio-oil Storage in Permeable Reservoirs Module versions specified in Table 1 for Verification***

☐ ***Does Not Meet the requirements of the Isometric Standard, Bio-oil Geological Storage Protocol, Biomass Feedstock Accounting Module, and Biomass or Bio-oil Storage in Permeable Reservoirs Module versions specified in Table 1 for Verification***

5.3. VERIFICATION RESULTS SUMMARY

A summary of verification results and compliance with relevant requirements of the *Isometric Standard, Biomass Geological Storage Protocol, Biomass Feedstock Accounting Module*, and *Bio-oil Storage in Permeable Reservoirs Module* are summarized below.

TABLE 4. VERIFICATION RESULTS SUMMARY

Isometric Standard Section Ref.	Verification Topic	Changed since Project Validation? (Y/N)	Final Findings
2.1.	*Validated against approved Protocols*	N	Acceptable – No additional changes since validation
2.5.1	*Boundaries*	N	Acceptable – No additional changes since validation
2.5.2	*Baseline*	N	Acceptable – No change since validation
2.5.3	*Additionality - Financial*	N	Acceptable – No change since validation
2.5.3	*Additionality – Environmental*	N	Acceptable – No change since validation
2.5.3	*Additionality – Regulatory*	N	Acceptable – No change since validation
2.5.4	*Leakage*	N	Acceptable – No change since validation and prior verification.
2.5.5	*Default Emission Factors, Proxies, and Models*	N	Acceptable – No additional significant changes were made since prior verifications.
2.5.11	*Life Cycle Assessment (LCA) Policies*	N	
2.5.6	*Common Calculation Factors*	N	
2.5.7	*Uncertainty*	N	

Isometric Standard Section Ref.	Verification Topic	Changed since Project Validation? (Y/N)	Final Findings
2.5.8	*Durability and Monitoring*	Y	All updated durability evidence and storage monitoring requirements validated to meet protocol requirements. Note that ongoing discussions with Isometric and Charm are occurring regarding frequency of Kansas storage site monitoring reports as the prior injections transition into a post-injection / closure monitoring phase with no Charm injections occurring.
2.5.9	*Risk of Reversal*	N	Acceptable – No additional changes since validation
2.5.10 ***3.7***	*Environmental and Socioeconomic Impacts*	N	Acceptable – No additional changes since validation.
3.1	*Ownership*	N	Acceptable – No change since validation
3.2	*Documentation*	Y	Acceptable – No additional changes since prior verification. All documentation properly updated for reporting period
3.3	*Eligibility*	Y (GHG Statement Updated)	Acceptable – Project registered with Isometric and reporting period GHG Statement properly submitted to Isometric dMRV Certify platform.
3.4	*Project Crediting*	Y (GHG Statement Updated)	Acceptable – New reporting period GHG Statement is complete and verified. Reporting period is within current validation crediting period.
3.5	*Stakeholder Input Process*	N	Acceptable – No changes since prior verification
3.6	*Regulatory Compliance*	Y (Required Monitoring Updated)	Required monitoring and reporting completed during reporting period. No additional compliance issues identified for injections during period.
Biomass Feedstock Accounting Module			
2.1	*Eligibility Criteria for Market Leakage*	N	Acceptable – No change since prior feedstock validations
2.2	*Counterfactual Storage Eligibility*	N	Acceptable – No change since prior feedstock validations
2.3	*Dedicated Energy Feedstock Eligibility*	N	Acceptable – No change since prior feedstock validations
3.0	*Counterfactual Definition*	N	Acceptable – No change since prior feedstock validations
3.1	*Counterfactual Energy Definition*	N	Acceptable – No change since prior feedstock validations
3.2	*Counterfactual Replacement Definition*	N	Acceptable – No change since prior feedstock validations

TABLE 5. BASCO STORAGE SITE VERIFICATION SUMMARY

Isometric Standard Section Ref.	Verification Topic	Changed since Project Validation? (Y/N)	Final Findings
Bio-oil Storage in Permeable Reservoirs Module			
1.0	*Storage System Eligibility*	N	Acceptable – No change since validation
2.1	*Storage Reservoir – Permitting*	N	Acceptable – No change since validation
2.2	*Storage Reservoir – Capacity*	N	Acceptable – No change since validation

2.2	*Storage Reservoir – Integrity*	N	Acceptable – No change since validation
2.2	*Storage Reservoir – Integrity: Characterization*	N	Acceptable – No change since validation.
2.2	*Storage Reservoir Characterization – Temperature, pH, conductivity, density*	N	Acceptable – No change since validation
2.2	*Storage Reservoir Characterization – $d^{13}C$ analysis (where applicable)*	NA	Acceptable – Not required
2.3	*Storage Reservoir Integrity – Well Construction*	N	Acceptable – No change since validation
3.1.1	*Storage Reservoir Integrity – Injection operations*	Y	Acceptable – Updated monitoring data provided indicating no exceedances of permit limits for Basco site
3.1.1	*Storage Reservoir Integrity – Injection operations – Sampling & Analysis*	Y	Acceptable – Updated sampling and analytical data provided indicating no exceedances of permit limits for Basco site
1.0, 3.2	*Well Closure and Post Closure Requirements*	N	Acceptable – No change since validation
3.1.3	*Injection Pressure*	Y	Acceptable – Pressure is continuously monitored and reported quarterly (monitoring reports indicate full compliance) for Basco site
3.1.2	*Mechanical Integrity*	N	Acceptable – No change since prior verification for Basco site
3.1.3	*Volatile Gas Monitoring*	N	Acceptable – No change to processes since prior verifications for Basco site.
3.1.3	*Reversal Risk & Monitoring*	N	Acceptable – No change since validation
3.3.1	*Attribution of Reversals*	N	Acceptable – No change since validation

5.4. VERIFICATION FINDINGS

5.4.1. CRITICAL FINDINGS

Assessment of the greenhouse gas removal statement identified no non-conformities, with only a few minor findings, clarifications, and non-material data issues (see Appendix 2). No significant findings that materially impacted the verified net carbon removals nor compliance with protocol standard were identified. All findings, primarily clarifications and minor data errors, have been addressed and closed.

5.4.2. FORWARD ACTION REQUESTS & RECOMMENDATIONS

Forward action requests (FAR) and recommendations are also provided in Appendix 2 for consideration for improvement of future operations and GHG Removal Credit calculations and to ensure tracking of potential issues to be monitored by verifiers in future verifications. Open FARs and opportunities for improvement are summarized below for future verification reference.

TABLE 6. FORWARD ACTION REQUESTS AND RECOMMENDATIONS

ID No	Type	Finding / Issue	Supplier Response	Conclusion / Resolution
ISS-30	FAR (Prior)	The monitoring data was provided for March, but the monthly report copy to LDENR was not provided. Please upload the LDENR report as well as the email confirmation of receipt.	As with the quarterly reporting requirement, monthly reporting is due within 30 days after the close of the month. So, March reporting would be due at the end of April. When reporting is completed sooner (as was the case with the reporting package submitted in February) we will provide it in the reporting package for the same month. When it is not, it will be included with the subsequent reporting package.	Resolved. Reports provided and confirmed filed on time and with no issues.
ISS-18	FAR (Prior)	VVB Guidance document (Google drive) indicates a spill of bio-oil occurred during the reporting period that will be properly disposed of in April. Noting this as a FAR to ensure disposal emissions are accounted for in for the next verification		Resolved. Charm is properly tracking and accounting for associated disposal emissions.
ISS-14	FAR (Prior)	Although the air permit may not require monitoring of thermal oxidizer during operation, we would prefer to see evidence that the oxidizer is being operated properly in the future. Can you clarify if oxidizer operational monitoring is done (i.e. temperature logging)	That should not be a problem. This request has been submitted to injection ops for review so we can identify how best to pull and report on this data going forward.	Resolved. Oxidizer monitoring data and additional explanation provided.
NA	FAR (prior)	With injections no longer occurring at Vaulted, we would like to know how Charm will be notified of closure of the cavern where Charm oil was last injected, and to ensure that Charm will now be obtaining and submitting any post closure monitoring data to Isometric as part of the continued monitoring requirements. Please clarify that plans are in place for this and will be ongoing.	Charm has reached out to Vaulted on multiple occasions to get clarity regarding their future plans for the AR-09 injection well. The well still has considerable capacity and is the property of Vaulted, so it is up to them whether they plug and abandon the well or use it for their own emplacements. This decision on their part will affect the nature of the post-closure monitoring plan. We will continue to request clarity regarding these plans and, once received, we will define and submit a monitoring plan in light of the information we receive.	April 2026: guidance provided by Isometric for review and implementation with verification of monitoring proposed in upcoming RPs. May 2026: Anticipate compliance verification to occur in June or July RP and FAR to be closed then.

NA	FAR (prior)	With injections no longer occurring at Vaulted, please provide updated contract for post-emplacement / post-closure management and monitoring and post-closure monitoring plan that documents how Charm will be notified of closure of the cavern where Charm oil was last injected, and to ensure that Charm will now be obtaining and submitting any post closure monitoring data to Isometric as part of the continued monitoring requirements or this storage location		See above

6. REVISION HISTORY

Version	Date Issued	Noted Changes
v1.0 (Draft – Internal)	May 22, 2026	N/A Initial Version
v1.1 (Draft – External)	May 26, 2026	Minor edits from QA and Supplier
v1.2 (FINAL)	May 27, 2026	Final Version. Minor edits from QA and client. Clarified bio-oil sources by removal and protocol and module version applicability

References

[1] Isometric, “Isometric Standard v1.8.” [Online]. Available: https://registry.isometric.com/standard/1.8

[2] Isometric, “Bio-oil Geological Storage v.1.2.” [Online]. Available: https://registry.isometric.com/protocol/bio-oil-geological-storage/1.2

[3] Isometric, “Biomass Feedstock Accounting v.1.3.” [Online]. Available: https://registry.isometric.com/protocol/biomass-feedstock-accounting/1.3

[4] Isometric, “Biomass or Bio-oil Storage in Permeable Reservoirs v1.2.” https://registry.isometric.com/module/bio-oil-storage-in-permeable-reservoirs/1.2

[5] Isometric, “Embodied Emissions Accounting v1.0.” [Online]. Available: https://registry.isometric.com/protocol/embodied-emissions/1.0

[6] Isometric, “Energy Use Accounting v1.2.” [Online]. Available: https://registry.isometric.com/protocol/energy-use-accounting/1.2

[7] Isometric, “Transportation Emissions Accounting v1.1.” [Online]. Available: https://registry.isometric.com/protocol/transportation

See Appendix 1 and Table 3 for list of specific files reviewed during the verification.

APPENDIX 1: DOCUMENTS SUBMITTED FOR REVIEW

Name
Apr1-Apr30_Removals_Isometric_GHG_Statement_Report_v1.7.docx
April 1 - April 30 2026 VVB Guidance.docx
April 1 - April 30 2026 VVB Guidance.pdf
Mass Policy Position Statement.docx
Community Engagement Events Lis.xlsx
Grievance Record_All Locations.xlsx
Basco_April_2026_Injection_Report.xlsx
800104 SDS_US EN-US.pdf
LDCE Injection Report_March 2026.xlsx
LDENR Injection Reporting _1Q2026.pdf
December 2025 PP Summary.xlsx
December 2025 PP (12_1-12_31) Biomass Throughput.xlsx
Miniforge Biomass Transport Allocation -- Updated - Biomass Allocation Tracker December .pdf
Diesel Consumption Calc 12_1_25-12_31_25.xlsx
12_10_25.PDF
12_17_25.PDF
12_29_25.PDF
12_7_25.PDF
12_9_25.PDF
December 2025 Miniforge Electricity Consumption Calculator.xlsx
December Electricity Consumption Miniforge.csv
Cap Ex MRV December.xlsx
G2 Construction (Elevation Fabrication LLC) - Quote #4133.pdf
Ryberg Construction Co., Inc. - Helical Pile Supply - Packing List.pdf
South Tent Quantification.xlsx
SP&C December.xlsx
Dec 2025 PP Gasoline Consumption Calculator.xlsx
12_23_25.pdf
December 2025 Production Period Output Summary.xlsx
20260114 CAR-451 QOWV.pdf
20260116 CAR-451 CHAR.pdf
WODO 20260113 CAR-450.pdf
Propane Consumption Calculator 12_1_25-12_31_25.xlsx
Screenshot of Propane Level.PNG
12_12_25.PDF
12_23_25.PDF
12_17_25.pdf
12_3_25.pdf
December Up-Time Screenshot.png
December 2025 PP (12_1-12-31) Vendor Delivery Emissions Calc Sheet.xlsx
Dec PP Waste Disposal Emissions Calc Sheet.xlsx
Manifest_009387162SKS.pdf
Manifest_009513696SKS.pdf
December 2025 PP Water Usage Log.xlsx
November 2025 PP Summary.xlsx
November 2025 PP (11_1-11_30) Biomass Throughput (2).xlsx
Miniforge Biomass Transport Allocation -- Updated - Biomass Allocation Tracker November .pdf
Diesel Consumption Calc 11_1_25-11_30_25.xlsx
11_10_25.PDF
11_17_25.PDF
11_24_2025.PDF

11_6_25.PDF
Nov Electricty Use CO.csv
November 2025 Miniforge Electricity Consumption Calculator.xlsx
Cap Ex MRV November.xlsx
SP&C November.xlsx
Nov 2025 PP Gasoline Consumption Calculator.xlsx
11.14 Gas CO.pdf
November 2025 Production Period Output Summary.xlsx
CHAR 20251215 CAR-444.pdf
QOWV 20251210 CAR-444.pdf
WODO 20251216 CAR-445 (1).pdf
Charm Nov25 Propane Level (Agfinity).xlsx
Propane Consumption Calculator 11_1_25-11_30_25.xlsx
(1) 11_14_25.PDF
11_14_25.PDF
11_18_25.PDF
11_28_2025.PDF
11_3_2025.PDF
11_12_2025.pdf
11_5_25.pdf
November Uptime Data .png
November 2025 PP (11_1-11-30) Vendor Delivery Emissions Calc Sheet.xlsx
Nov PP Waste Disposal Emissions Calc Sheet.xlsx
11.20.2025 SK 009460024.pdf
11.20.2025 SK 009460025.pdf
11.5.2025 SK 009513627.pdf
11.5.2025 SK 009513628.pdf
11.5.2025 SK 009513631.pdf
11.5.2025 SK 009513632.pdf
11.6.2025 SK 0095136235.pdf
11.6.2025 SK 009513629.pdf
11.6.2025 SK 009513637.pdf
November 2025 PP Water Usage Log.xlsx
AECN C Content Outlier Analysis - 2026 YTD.xlsx
2-180 Ops Notes.xlsx
2-180 Empty Ticket (1).jpg
2-180 Full Scale Ticket (1).jpg
SR26-02231_Batch_2-180-185_COA (1).pdf
2-181 Ops Notes.xlsx
2-181 Empty Ticket (1).png
2-181 Full Scale Ticket.jpg
SR26-02231_Batch_2-180-185_COA (1).pdf
2-182 Ops Notes Rail.xlsx
2-182_Empty_Scale_Ticket.jpg
2-182_Full_Scale_Ticket.jpg
SR26-02231_Batch_2-180-185_COA.pdf
2-183 Ops Notes Rail.xlsx
2-183_Empty_Scale_Ticket.jpg
2-183_Full_Scale_Ticket.jpg
SR26-02231_Batch_2-180-185_COA.pdf
2-184 Ops Notes Rail.xlsx
2-184_Empty_Scale_Ticket.jpg
2-184_Full_Scale_Ticket.jpg
SR26-02231_Batch_2-180-185_COA.pdf
2-185 Ops Notes Rail.xlsx
2-185 Empty Scale Ticket.jpg

2-185 Full Scale Ticket.jpg
2-180 - 2-185.pdf
2-186 Ops Notes Rail.xlsx
2-186 Empty Scale Ticket.jpg
2-186 Full Scale Ticket.jpg
2-186 - 2-189.pdf
2-187 Ops Notes Rail.xlsx
2-187 Empty Scale Ticket.jpg
2-187 Full Scale Ticket.jpg
2-186 - 2-189.pdf
2-188 Ops Notes Rail.xlsx
2-188 Empty Scale Ticket.jpg
2-188 Full Scale Ticket.jpg
SR26-02264.pdf
2-189 Ops Notes Rail.xlsx
2-189 Empty Scale Ticket.jpg
2-189 Full Scale Ticket.jpg
2-186 - 2-189.pdf
2-199 Ops Notes.xlsx
2-199 Empty Ticket.png
2-199 Full Scale Ticket.jpg
2-199 - 2-201.pdf
2-201 Ops Notes Rail.xlsx
2-201 Empty Scale Ticket.jpg
2-201 Full Scale Ticket.jpg
2-199 - 2-201.pdf
2-204 Ops Notes Rail.xlsx
2-204 Empty Scale Ticket.pdf
2-204 Full Scale Ticket.jpg
2-202 - 2-204, 5-10.pdf
2-190 Ops Notes Rail.xlsx
2-190 Empty Scale Ticket.jpg
2-190 Full Scale Ticket.jpg
2-190 - 2-191.pdf
2-191 Ops Notes Rail.xlsx
2-191 Empty Scale Ticket.jpg
2-191 Full Scale Ticket.jpg
2-190 - 2-191.pdf
2-192 Ops Notes Rail.xlsx
2-192 Empty Scale Ticket.jpg
2-192 Full Scale Ticket.jpg
CHARM SR26-02553.pdf
2-194-KS-10-1 Ops Notes Rail.xlsx
OPBA10_offload_1_Empty_scale_ticket.jpg
OPBA10_offload_1_Full_scale_ticket.jpg
2-192-2-198+Kc0005-Kc-0008.pdf
2-195-KS-11-1+2 Ops Notes Rail.xlsx
OPBA11_offload_1_Empty_scale_ticket.jpg
OPBA11_offload_1_Full_scale_ticket.jpg
OPBA11_offload_2_Empty_scale_ticket.jpg
OPBA11_offload_2_Full_scale_ticket.jpg
Batch 2-195 Batch 2-196.pdf
2328-R BOL.pdf
2339-R BOL.pdf
2340-R BOL.pdf
Billing Documents 2338-T.pdf

Billing Truck 2314-T Corrections (1).pdf
Billing Truck 2316-R.pdf
BOL 1294.pdf
BOL 1296.pdf
Document Camion 1303.pdf
Document Camion 2345-R corr.pdf
Document Camion 2346-R.pdf
documents 2320-T (1).pdf
documents 2342-T.pdf
documents 2343-T.pdf
documents 2352-T corr.pdf
Documents camion 1304.pdf
Documents Camion 2310-R Charm PO Q42025 (1).pdf
Documents Camion 2312-R Charm PO Q42025.pdf
Documents camion 2317-R.pdf
Documents camion 2344-R corr.pdf
Documents camion charm 1299.pdf
Envoi des documents camion 1300 (1).pdf
Truck documents 2313-R.pdf
3-55 Charm Contents.xlsx
April Bio Oil Shipment Tracker.xlsx
2-186-2-189 + 3-55-3-57.pdf
3-56 Charm Contents.xlsx
April Bio Oil Shipment Tracker.xlsx
Testing 3-56.pdf
5-10 Charm Contents.xlsx
April Bio Oil Shipment Tracker.xlsx
202-204, 5-10.pdf
2-158, 2-159, 2-160, 2-161, K-001, SR26-01913.pdf
2-192-2-198+Kc0005-Kc-0008_src_1KQ0JVPA11S0B47B.pdf
coa_19d2b093a1feb49f_SR26-02012 CHARM BATCH OILS REC 3-24-26.pdf
K-001.xlsx
Apr 1-Apr 30 RP BCU Quant.xlsx
Brine Usage 4_1-4_30.xlsx
20260624_Charm_Basco (1).pdf
Water Transport Calc Sheet (3).xlsx
4-1-_4-30 Diesel Consumption Calcs.xlsx
4.1.26 LA Diesel.pdf
4.17.26 LA Diesel.pdf
4.6.26 LA Diesel.pdf
4.9.26 LA Diesel.pdf
Basco April 26 Electricity (1).xlsx
Basco 6 Capital and Sitework Embodied Emissions Inventory Apr 1 - Apr 30.xlsx
Basco Inj Operations SP+C Inventory Apr 1 - Apr 30.xlsx
3-Panel Triton Shale Shaker.docx
60kW Diesel Generator.docx
65 bbl Catch Tank.docx
AGI Industries Invoice 3278796 Kerr T30M Pump EE.docx
AGI Industries Invoice 3284043 GASO 3364 Pump EE.docx
ERS Invoice ER206885 Generator Shaker Catch Tank Rental.pdf
HDT 60kW Skid Mounted Generator Datasheet.pdf
Kerry 6000 Gal SS Tank.docx
LA-OPS-PRB-251-Rev01 Titan Duplex Strainer PO.pdf
McMaster-Carr Invoice 61320752 SS AODD Pump EE.docx
Metal Shorts ASTM A36 Carbon Steel Plate Weight Chart.pdf
PRM Inv 1000168991 - 70 Mesh 210um SS Basket Strainer.pdf

PRM Inv 1000169627 - 25um Polyester Felt Filter Bags.pdf
PRM Inv 1000169705 - 80 Mesh SS Basket Strainer.pdf
PRM Inv 1000169791 - 37um and 74um Nylon Filter Bags.pdf
PRM Online Order - 25um Polyester Felt Filter Bags.jpg
Titan DS96-0116 Duplex Strainer Datasheet.pdf
Titan Duplex Strainer.docx
4-1-_4-30 Gasoline Tracker LA.xlsx
4.1.26 LA Gas.pdf
4.14.26 LA Gas.pdf
4.27.26 LA Gas.pdf
4.3.26 LA Gas.pdf
4.8.26 LA Gas.pdf
Louisiana Sitework Apr 1 - Apr 30.xlsx
Ag-Con to Basco Distance.png
Douglas Tank to Basco Distance Map.png
JC Construction to Basco.png
Cat Performance Handbook Ed46 Excavator Fuel Tables.pdf
Basco Excavation March 26.pdf
ERS Invoice ER206885 - Generator Shaker Catch Tank Rental Apr 26.pdf
Limestone.pdf
April 2026 Railcar Emissions Calc Sheet.xlsx
Railline Distances.png
Basco Support Travel Calc Sheet Apr 1 - Apr 30.xlsx
Waste Disposal Emissions Calc Sheet - 4_26.xlsx
Basco To Acadania Landfill.png
March Oil Spill Disposal.png
Name
src_1K31MPMV51S0F34N_Standard_Emission_Factors___Calculations__4_.xlsx
src_1K370M1Z51S076JY_GLEC_NA_Fuel_Energy.png
src_1K3729JS71S07WKT_GLEC_NA_Fuel_Energy.png
src_1K7J7C5MZ1S0HNWV_AECN_Process_Emissions_Calculation.xlsx
src_1K7J7C8Q71S0REVP_GLEC_NA_Road_Transport.png
src_1K7J7CFVH1S01G4T_Truck_Embodied_Emissions.png
src_1K7J7CHRD1S0B26D_Truck_Embodied_Emissions.png
src_1KGTC5B2K1S0TZKC_AECN_to_Basco.png
src_1KJGAP1TM1S0M1J4_AECN_to_SOPOR__Baie_Comeau___2_.png
src_1KJGAPM4W1S0H8FC_image__44_.png
src_1KJGAQH311S075NA_Screenshot_2026-01-27_125934.png
src_1KJRJ5XF11S08CER_Supporting_GHG_data_31Dec2025_S.xlsx
src_1KJRJ5YWN1S0W1AD_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KJRJ5ZM61S0FP62_Screenshot_2026-02-23_at_11.29.10_AM.png
src_1KJRJ60FV1S03B1Q_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KJTY2XC31S0XBFE_Charm-A5-2024-10-24-62-1976.pdf
src_1KNHXJ4Q51S0EA6N_2-158__2-159__2-160__2-161__K-001__SR26-01913__1_.pdf
src_1KNHXJ9GT1S047CK_2-166_-_2-174.pdf
src_1KNJ3R6YR1S0N8C8_Kerry_to_Basco_Distance.png
src_1KP1S7FAG1S0R9V2_Standard_Emission_Factors___Calculations_-_2026_SPSO_Electricity_EFs_src_1KNMFRD6N1S0BZQ2.pdf
src_1KP27HK9K1S0BNXF_documents_2343-T.pdf
src_1KP27HTW81S0WHPC_Screenshot_2026-04-10_at_3.19.33_PM.png
src_1KQ0QEC5P1S0AXRR_Standard_Emission_Factors___Calculations_-_Truck_and_Trailer_EE_2025.pdf
src_1KQ7XX03R1S025T8_Truck_documents_2313-R.pdf
src_1KQ7XX1EZ1S0NTNX_Documents_Camion_2312-R_Charm_PO_Q42025.pdf
src_1KQ7XX31H1S09FHJ_Documents_Camion_2310-R_Charm_PO_Q42025__1_.pdf
src_1KQ7XXZ6E1S0XEY1_2-182_Empty_Scale_Ticket__1_.jpg

src_1KQ7XY0VR1S0H3SP_2-182_Full_Scale_Ticket__1_.jpg
src_1KQ7XY2G51S04RNB_SR26-02231_Batch_2-180-185_COA__1_.pdf
src_1KQ7XYWG71S0CMGH_2-183_Full_Scale_Ticket__1_.jpg
src_1KQ7XYXZB1S009C6_2-183_Empty_Scale_Ticket__1_.jpg
src_1KQ7XYZCZ1S0KY7V_SR26-02231_Batch_2-180-185_COA__1_.pdf
src_1KQ7XZWA71S00AQK_2-184_Empty_Scale_Ticket.jpg
src_1KQ7XZXXT1S0KZK8_2-184_Full_Scale_Ticket.jpg
src_1KQ7XZZQF1S07MEX_SR26-02231_Batch_2-180-185_COA__1_.pdf
src_1KQ7Y0R9T1S0HRMC_2-185_Empty_Scale_Ticket__1_.jpg
src_1KQ7Y0T491S05DG1_2-185_Full_Scale_Ticket__1_.jpg
src_1KQ7Y0WT41S0CQ7B_SR26-02231_Batch_2-180-185_COA__1_.pdf
src_1KQ7ZHDBB1S081PH_Standard_Emission_Factors___Calculations_-_2026_Railcar_Embodied_Emissions.pdf
src_1KQ81M0M71S0X7WB_2-182_Ops_Notes_Rail__1_.xlsx
src_1KQ81MQZW1S0R6FA_2-182_Ops_Notes_Rail__1_.xlsx
src_1KQ81NHTA1S0K529_2-182_Ops_Notes_Rail__1_.xlsx
src_1KQ81QZ2K1S01RGX_Standard_Emission_Factors___Calculations__7_.xlsx
src_1KQ86FPTP1S0XQNJ_2-182_Ops_Notes_Rail__2_.xlsx
src_1KQ86J3781S0CB46_2-183_Ops_Notes_Rail__2_.xlsx
src_1KQ86WZWS1S09J1E_2-183_Ops_Notes_Rail__2_.xlsx
src_1KQ86XJ5J1S04GMD_2-183_Ops_Notes_Rail__2_.xlsx
src_1KQ872B3V1S0TDTB_2-184_Ops_Notes_Rail__2_.xlsx
src_1KQ876HW61S0PK6N_2-184_Ops_Notes_Rail__2_.xlsx
src_1KQ8999831S0ZRRY_2-185_Ops_Notes_Rail__3_.xlsx
src_1KQ89A69S1S0EC7J_2-185_Ops_Notes_Rail__3_.xlsx
src_1KQB5G6KG1S0B2QQ_Billing_Truck_2314-T_Corrections__1_.pdf
src_1KQB5G84D1S0YQKC_Billing_Truck_2316-R.pdf
src_1KQB5G9H81S0JCF1_Documents_camion_2317-R.pdf
src_1KQB5H07N1S09NPQ_Standard_Emission_Factors___Calculations_-_2026_Railcar_Embodied_Emissions.pdf
src_1KQB5H78N1S00SP0_2-186_Ops_Notes_Rail.xlsx
src_1KQB5H7WA1S0MEHN_CHN-186-189.pdf
src_1KQB5H8TT1S083DA_2-186_Empty_Scale_Ticket__2_.jpg
src_1KQB5HAFW1S0VR8Z_2-186_Full_Scale_Ticket__2_.jpg
src_1KQB5J92B1S00A8Y_2-187_Ops_Notes_Rail.xlsx
src_1KQB5J9X71S0KZ4K_2-187_Empty_Scale_Ticket__1_.jpg
src_1KQB5JBH51S07M08_2-187_Full_Scale_Ticket__1_.jpg
src_1KQB5JDBX1S0V8VX_CHN-186-189.pdf
src_1KQB5K7361S02KYM_2-189_Ops_Notes_Rail.xlsx
src_1KQB5K7RQ1S0P8T9_2-189_Full_Scale_Ticket__1_.jpg
src_1KQB5K9E21S09XNY_2-189_Empty_Scale_Ticket.jpg
src_1KQB5KB391S0XJHK_CHN-186-189.pdf
src_1KQB5M6071S04XMA_2-188_Ops_Notes_Rail.xlsx
src_1KQB5M6K81S0RJFZ_2-188_Empty_Scale_Ticket__1_.jpg
src_1KQB5M86F1S0C7BM_2-188_Full_Scale_Ticket__1_.jpg
src_1KQB5M9KR1S0ZW79_CHN-186-189.pdf
src_1KQCWR4131S07NSK_2-186_Ops_Notes_Rail.xlsx
src_1KQCWWDTH1S00HAP_2-186_Ops_Notes_Rail.xlsx
src_1KQCWXWEA1S0A3C9_2-186_Ops_Notes_Rail.xlsx
src_1KQCX3GZC1S0XXGB_2-187_Ops_Notes_Rail.xlsx
src_1KQCX4FS01S085JT_Standard_Emission_Factors___Calculations_-_2026_Railcar_Embodied_Emissions.pdf
src_1KQCXA6HA1S0HQMD_2-187_Ops_Notes_Rail.xlsx
src_1KQCXB69M1S0V9P0_2-187_Ops_Notes_Rail.xlsx
src_1KQCXHB6B1S0ZDV8_2-189_Ops_Notes_Rail.xlsx
src_1KQCXM1Z31S0BY80_2-189_Ops_Notes_Rail.xlsx
src_1KQCXMYF51S0NG9K_2-189_Ops_Notes_Rail.xlsx
src_1KQCYCDV71S08YXK_2-188_Ops_Notes_Rail.xlsx
src_1KQCYEMWJ1S0FQWE_2-188_Ops_Notes_Rail.xlsx

src_1KQCZ81E61S002WW_2-188_Ops_Notes_Rail.xlsx
src_1KQJFN5FV1S0W1HY_2-180_Full_Scale_Ticket__1_.jpg
src_1KQJFN8VN1S0Q04X_2-180_Ops_Notes__2_.xlsx
src_1KQJFN9NJ1S0AN0J_SR26-02231_Batch_2-180-185_COA__1_.pdf
src_1KQJFNGRC1S0MEN7_Billing_Documents_2338-T.pdf
src_1KQJFP21Z1S0PW7X_2-181_Ops_Notes.xlsx
src_1KQJFP2Q81S0AH3J_2-181_Full_Scale_Ticket.jpg
src_1KQJFP3RG1S0Y5Z7_2-181_Empty_Ticket__1_.png
src_1KQJFP58W1S0HTTW_SR26-02231_Batch_2-180-185_COA__1_.pdf
src_1KQJGR6E11S0GF59_Supporting_GHG_data_31Dec2025_S.xlsx
src_1KQJGR6QV1S0440Y_Screenshot_2026-02-23_at_11.29.10_AM.png
src_1KQJGR6R31S0QRWK_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KQJGR6RS1S0BDR8_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KQJGZ1NY1S0BR92_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KQJGZ1Z41S0ZD4Q_Supporting_GHG_data_31Dec2025_S.xlsx
src_1KQJGZ1Z91S0K20C_Screenshot_2026-02-23_at_11.29.10_AM.png
src_1KQJGZ1ZF1S06PW1_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KQJKMVR31S0YG93_Correction_Costum_Documents_2328-R.pdf
src_1KQJKMX4Q1S0J54R_Documents_camion_2339-R.pdf
src_1KQJKMYP21S05T0D_Documents_Camion_2340-R_corr__1_.pdf
src_1KQJKP5K21S03BEF_2-190_Ops_Notes_Rail.xlsx
src_1KQJKP6E01S0Q0A4_2-190_Full_Scale_Ticket__1_.jpg
src_1KQJKP7SB1S0AN5S_2-190_Empty_Scale_Ticket__1_.jpg
src_1KQJKP9Y41S0YA1E_2-190-2-191_Tests.pdf
src_1KQJKQ74A1S0Q1NH_2-191_Empty_Scale_Ticket__1_.jpg
src_1KQJKQ8YF1S0APH6_2-191_Full_Scale_Ticket__1_.jpg
src_1KQJKQAQ31S0YBCV_2-191_Ops_Notes_Rail.xlsx
src_1KQJKQBAG1S0J08G_2-190-2-191_Tests.pdf
src_1KQJKR9SP1S0YCR8_2-192_Empty_Scale_Ticket__1_.jpg
src_1KQJKRBDW1S0J1KX_2-192_Full_Scale_Ticket__1_.jpg
src_1KQJKRD371S05PFJ_2-192_Ops_Notes_Rail__2_.xlsx
src_1KQJKRDY51S0SBB7_2-192-2-198_Kc0005-Kc-0008.pdf
src_1KQJM0Q0J1S0W5SC_2-190_Ops_Notes_Rail__1_.xlsx
src_1KQJM1MYW1S0YE3N_2-190_Ops_Notes_Rail__1_.xlsx
src_1KQJM2KDS1S0MB9K_2-190_Ops_Notes_Rail__1_.xlsx
src_1KQJM4DDS1S0KTH4_Standard_Emission_Factors___Calculations_-_2026_Railcar_Embodied_Emissions.pdf
src_1KQJMA0451S0PDC7_2-191_Ops_Notes_Rail__1_.xlsx
src_1KQJMBQKG1S0TY0S_2-191_Ops_Notes_Rail__1_.xlsx
src_1KQJMKKP31S0R4Y1_2-191_Ops_Notes_Rail__1_.xlsx
src_1KQJMR5DD1S0KYT9_2-192_Ops_Notes_Rail__2_.xlsx
src_1KQJMSK9F1S09W07_2-192_Ops_Notes_Rail__2_.xlsx
src_1KQJMTB851S0ZS65_2-192_Ops_Notes_Rail__2_.xlsx
src_1KQT762DK1S0C06J_Documents_camion_2344-R_corr.pdf
src_1KQT763Z91S0ZN27_Document_Camion_2345-R_corr.pdf
src_1KQT765DY1S0K9XW_Document_Camion_2346-R.pdf
src_1KQT77AYA1S01Q4V_2-201_Full_Scale_Ticket.jpg
src_1KQT77C4B1S0NC0G_2-201_Empty_Scale_Ticket.jpg
src_1KQT77E8K1S0WNQT_2-199_-_2-201.pdf
src_1KQT7FQCT1S09K01_2-201_Ops_Notes_Rail__1_.xlsx
src_1KQT7GAJF1S0R6EN_2-201_Ops_Notes_Rail__1_.xlsx
src_1KQT7GVW41S01RG8_2-201_Ops_Notes_Rail__1_.xlsx
src_1KQYTKZ7Z1S0GMFF_K-001__2_.xlsx
src_1KQYTMJHE1S0Z7Y3_K-001__2_.xlsx
src_1KQYTN94M1S0DVCQ_K-001__2_.xlsx

src_1KQYYAZBV1S0MD4N_202-204__5-10.pdf
src_1KQYYB04W1S0820A_2-204_Empty_Ticket.pdf
src_1KQYYB1AK1S0VPVZ_2-204_Full_Scale_Ticket.jpg
src_1KQYYK7S31S07DAV_2-204_Ops_Notes_Rail__1_.xlsx
src_1KQYYP5A21S0V7EX_2-204_Ops_Notes_Rail__1_.xlsx
src_1KQYYPXBZ1S04SGG_2-204_Ops_Notes_Rail__1_.xlsx
src_1KR4MRNRW1S05KTK_AECN_C_Content_Outlier_Analysis_-_2026_YTD.xlsx
src_1KRBRX86M1S08VYQ_RS1-260330-1_Final_CHARM__1_.pdf
src_1KRBRX8FY1S0WGTC_2-204_Ops_Notes_Rail__2_.xlsx
src_1KRBRYY3A1S00GPF_2-201_Ops_Notes_Rail__3_.xlsx
src_1KRBRYY3M1S0M5J4_RS1-260330-1_Final_CHARM__1_.pdf
src_1KRC3GN6T1S09R0A_3-55_Charm_Contents__1_.xlsx
src_1KRC3GP2X1S0XCVZ_2-186-2-189___3-55-3-57.pdf
src_1KRCAYB9P1S04QBK_Documents_camion_charm_1299.pdf
src_1KRCAYD2Q1S0RC78_1296_BOL_Invoice_049T2R3.pdf
src_1KRCAYER31S0C12X_1294_BOL_Invoice_048T2R3.pdf
src_1KRCH27BN1S03ZC7_3-56_Charm_Contents__2_.xlsx
src_1KRCH27YV1S0QM7W_2-186-2-189___3-55-3-57.pdf
src_1KRE9KB3Q1S0VAD8_3-55_Charm_Contents__1_.xlsx
src_1KRE9NR081S0XJQH_3-55_Charm_Contents__1_.xlsx
src_1KRE9NR0C1S09XVW_CO_to_Basco_Routing_Map.png
src_1KRE9QBVV1S0G628_CO_to_Basco_Routing_Map.png
src_1KRE9VBE71S00H2P_November_2025_Production_Period_Summary.xlsx
src_1KREANABZ1S0GBAN_CO_to_Basco_Routing_Map.png
src_1KREAP1KP1S0MB6R_CO_to_Basco_Routing_Map.png
src_1KREAST781S0T2MN_December_2025_Production_Period_Summary.xlsx
src_1KREAVTNT1S0ZT2J_3-56_Charm_Contents__2_.xlsx
src_1KREBGNNX1S0G530_CO_to_Basco_Routing_Map.png
src_1KREBHDCK1S0E214_202-204__5-10.pdf
src_1KREBNJNV1S0D838_5-10_Charm_Contents__2_.xlsx
src_1KREJGA521S0NFTN_2-194-KS-10-1_Ops_Notes_Rail__1_.xlsx
src_1KREJGAWM1S094PA_OPBA10_offload_1_Empty_scale_ticket__2_.jpg
src_1KREJGCE21S0WSHZ_OPBA10_offload_1_Full_scale_ticket__2_.jpg
src_1KREJGEBN1S0GEDM_2-192-2-198_Kc0005-Kc-0008_src_1KQ0JVPA11S0B47B.pdf
src_1KREM3ADA1S061EX_Envoi_des_documents_camion_1300.pdf
src_1KREM3BTK1S0SPAJ_Document_Camion_1303.pdf
src_1KREM3DEQ1S0DB67_Documents_camion_1304.pdf
src_1KREM44151S0GESS_2-195-KS-11-1_2_Ops_Notes_Rail.xlsx
src_1KREM45AE1S043NE_OPBA11_offload_2_Empty_scale_ticket.jpg
src_1KREM46SM1S0QRH3_OPBA11_offload_1_Empty_scale_ticket.jpg
src_1KREM487C1S0BDCR_OPBA11_offload_1_Full_scale_ticket.jpg
src_1KREM49Q01S0Z28D_OPBA11_offload_2_Full_scale_ticket.jpg
src_1KREM49TQ1S0JQ42_April_Bio_Oil_Shipment_Tracker.xlsx
src_1KREM4B5J1S06BZQ_Batch_2-195_Batch_2-196.pdf
src_1KREM6JB61S02RZ3_April_Bio_Oil_Shipment_Tracker.xlsx
src_1KREM9HQB1S0XQJ2_April_Bio_Oil_Shipment_Tracker.xlsx
src_1KREN0ECE1S0YHW3_2-194-KS-10-1_Ops_Notes_Rail__2_.xlsx
src_1KRESK4H51S0NFKQ_December_2025_Production_Period_Summary.xlsx
src_1KREW0JT11S0SZ91_Screenshot_2026-01-27_125934_src_1KJGAQH311S075NA.png
src_1KREW3FRW1S00XG9_2-195-KS-11-1_2_Ops_Notes_Rail.xlsx
src_1KREW41951S0FGYX_Screenshot_2026-01-27_125934_src_1KJGAQH311S075NA.png
src_1KREWDDHD1S03NKS_Screenshot_2026-01-27_125934_src_1KJGAQH311S075NA.png
src_1KREWG0DA1S0TSK2_2-194-KS-10-1_Ops_Notes_Rail__1_.xlsx
src_1KREWGZMS1S0XQY7_Screenshot_2026-01-27_125934_src_1KJGAQH311S075NA.png
src_1KREWPH391S0CGN8_Standard_Emission_Factors___Calculations_-_2026_Railcar_Embodied_Emissions.pdf
src_1KREWQ5B91S07F87_3-56_Charm_Contents__2_.xlsx

src_1KREXBT5B1S0NWF6_Standard_Emission_Factors___Calculations_-_2026_Railcar_Embodied_Emissions.pdf
src_1KREZTJMH1S0DTRG_5-10_Charm_Contents__4_.xlsx
src_1KREZV6HJ1S0WE74_5-10_Charm_Contents__4_.xlsx
src_1KREZW87H1S0B1NR_5-10_Charm_Contents__4_.xlsx
src_1KRGYMEPM1S0QCM7_3-55_Charm_Contents__3_.xlsx
src_1KRGYNB351S0602V_3-55_Charm_Contents__3_.xlsx
src_1KRGYNZVE1S0MKHF_3-55_Charm_Contents__3_.xlsx
src_1KRH4AEZM1S0JDHV_documents_2352-T_corr.pdf
src_1KRH4AREX1S0A29K_Screenshot_2026-04-10_at_3.19.33_PM.png
src_1KRH4ATQA1S0TY2G_Truck_Embodied_Emissions.png
src_1KRH4AX3X1S0GV8E_AECN_to_Basco.png
src_1KRH4B6VV1S0W4VV_Basco_April_26_Electricity__1_.xlsx
src_1KRH4B87G1S05PXE_Charm_Industrial_Delta_Region_FH25_retirement-2026-01-06T13_45_40.pdf
src_1KRH4BBG21S0RV0M_Bourque_Invoice_20260624_-_4.20.26_Brine.pdf
src_1KRH4BCJB1S004QY_Water_Transport_Calc_Sheet.xlsx
src_1KRH4BDSJ1S09PSH_4.1.26_LA_Diesel.pdf
src_1KRH4BET51S0XBN6_4.6.26_LA_Diesel.pdf
src_1KRH4BFHB1S0H0GV_4.17.26_LA_Diesel.pdf
src_1KRH4BG7P1S04NCG_4.9.26_LA_Gas.pdf
src_1KRH4BGZ91S0RA85_4-1-_4-30_Diesel_Consumption_Calcs.xlsx
src_1KRH4BP0V1S0JR2N_4.1.26_LA_Gas__1_.pdf
src_1KRH4BQ8H1S06CYA_4.3.26_LA_Gas__1_.pdf
src_1KRH4BRZ11S0T1SZ_4.8.26_LA_Gas__1_.pdf
src_1KRH4BSXV1S0DPNM_4.14.26_LA_Gas__1_.pdf
src_1KRH4BTQ91S01BH9_4.27.26_LA_Gas__1_.pdf
src_1KRH4BXE21S084G4_Waste_Disposal_Emissions_Calc_Sheet_-_4_26.xlsx
src_1KRH4C3F31S0CN4P_April_2026_Railcar_Emissions_Calc_Sheet.xlsx
src_1KRH4C5161S00A0B_Copy_of_Railline_Distances.png
src_1KRH4CJDK1S01GSP_2-199_Empty_Ticket.png
src_1KRH4CKQA1S0N5NB_2-199_Full_Scale_Ticket.jpg
src_1KRH4CP351S08TH0_2-199_Ops_Notes__1_.xlsx
src_1KRH4CQYK1S0WFCN_RS1-260330-1_Final_CHARM__1_.pdf
src_1KRH4CS9X1S0G48A_2-199_-_2-201.pdf
src_1KRH4NZSJ1S04W0A_AECN_C_Content_Outlier_Analysis_-_2026_YTD.xlsx
src_1KRH4X6JE1S0S6WV_Water_Transport_Calc_Sheet_src_1KRH4BCJB1S004QY.xlsx
src_1KRH52Z641S0M5FT_2-180_Empty_Ticket__1__src_1KQJFN4AM1S08CP9.jpg
src_1KRH5QSPZ1S07ZKW_Basco_Inj_Operations_SP_C_Inventory_Apr_1_-_Apr_30.xlsx
src_1KRH5VZ7X1S0WAGD_Basco_Support_Travel_Calc_Sheet_Apr_1_-_Apr_30.xlsx
src_1KRH67H8K1S04FH0_4-1-_4-30_Gasoline_Tracker_LA.xlsx
src_1KRH6BABJ1S06QV9_March_Oil_Spill_Disposal.png
src_1KRH8YMXT1S08866_Watco_Rail_Distances_Evidence.png
src_1KRH8ZNH01S0PVMT_Watco_Rail_Distances_Evidence.png
src_1KRH90SXD1S05F3E_Watco_Rail_Distances_Evidence.png
src_1KRH91R7T1S0M2J2_Watco_Rail_Distances_Evidence.png
src_1KRHJKTSV1S0QJ1V_Standard_Emission_Factors___Calculations__7_.xlsx
src_1KRHPWW601S0FNKJ_Standard_Emission_Factors___Calculations__7_.xlsx
src_1KRHWBRCS1S0RBCM_Louisiana_Sitework_Apr_1_-_Apr_30__1_.xlsx
src_1KRHWMB6W1S0DQT3_Brine_Usage_4_1-4_30__1_.xlsx
src_1KRHXXAE61S0YRVD_Basco_6_Capital_and_Sitework_Embodied_Emissions_Inventory_Apr_1_-_Apr_30__2_.xlsx
src_1KRHY7MNJ1S0R54Z_Water_Transport_Calc_Sheet_src_1KRH4BCJB1S004QY_src_1KRH4X6JE1S0S6WV.xlsx
src_1KRJ1KXRN1S03ERC_Charm-A5-2024-10-24-62-1976.pdf
src_1KRJ1MDJQ1S0J270_Charm-A5-2024-10-24-62-1976.pdf
src_1KRJ1NASJ1S00NNM_Charm-A5-2024-10-24-62-1976.pdf
src_1KRJ1P5YE1S0F948_Charm-A5-2024-10-24-62-1976.pdf
src_1KRJ1Q01V1S0XWJW_Charm-A5-2024-10-24-62-1976.pdf

src_1KRJ3TEK11S09PYR_Charm_EAC_Verification_Inventory_tracker.xlsx
src_1KRJ41VNY1S0Y1V9_Charm_EAC_Verification_Inventory_tracker.xlsx
src_1KRJ42CHA1S0S0E8_Charm_EAC_Verification_Inventory_tracker.xlsx
src_1KRJ42V7F1S0KZ17_Charm_EAC_Verification_Inventory_tracker.xlsx
src_1KRJ438FA1S0EXM6_Charm_EAC_Verification_Inventory_tracker.xlsx
src_1KRJ43TS31S09W75_Charm_EAC_Verification_Inventory_tracker.xlsx
src_1KRJ48F7X1S0Y73P_Apr_1-Apr_30_RP_BCU_Quant.xlsx
src_1KRJ4H63D1S08ZYM_Apr_1-Apr_30_RP_BCU_Quant.xlsx
src_1KRJ4MT531S0XAV5_Apr_1-Apr_30_RP_BCU_Quant__1_.xlsx
src_1KRJ4NE381S0BY9S_Apr_1-Apr_30_RP_BCU_Quant__1_.xlsx
src_1KRJ4PJ541S0THRD_Apr_1-Apr_30_RP_BCU_Quant__1_.xlsx
src_1KRJ4Q4S31S0NGBC_Apr_1-Apr_30_RP_BCU_Quant__1_.xlsx
src_1KRZ0ZNZ71S0JNM0_Supporting_GHG_data_31Dec2025_S.xlsx
src_1KRZ0ZQH31S06AFN_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KRZ0ZRH11S0SZBA_Screenshot_2026-02-23_at_11.29.10_AM.png
src_1KRZ0ZSJ51S0DM6Z_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KRZ106091S09SK9_AECN_Process_Emissions_Calculation.xlsx
src_1KRZ10P6Q1S0PTRG_AECN_to_SOPOR__Baie_Comeau___2_.png
src_1KRZ10V221S0M1NR_image__44_.png
src_1KRZ112H61S01KKE_Standard_Emission_Factors___Calculations_-_2026_Railcar_Embodied_Emissions.pdf

APPENDIX 2: VERIFICATION AUDIT FINDINGS AND RESPONSES

Code	Type	Title	Body	Status / Resolution	Supplier Response
ISS-37	Clarification Request	Well injection pressure changes	Can you please provide information regarding the significant changes in well injection pressures over the past two months? For injection periods from August through January, the average injection pressures were in the 200-300 psi range, but for March and April, the values are significantly lower (17 in March).	Resolved	The 200-300 psi range experienced from August through January reflected the changing operational conditions at the injection site. More specifically, it was discovered via rig workover in January that an obstruction in the wellbore was preventing bio-oil from travelling into the lower section of the perforated interval. The January 2026 workover removed this wellbore obstruction, allowing bio-oil to contact the entire open perforation set within the well, significantly reducing the required pump pressure.
ISS-36	Clarification Request	Clarification	The Basco site emissions allocation approach will result in a significant back-end emissions allocation based on a massive scaleup of the Charm oil production and storage. This approach should be reviewed annually, along with progress toward forecast injection totals from the three feedstocks, to ensure embodied emissions allocations are allocated properly and not misallocated. Can Charm please clarify the Charm bio-oil scaleup approach and the progress, considering the Charm production is lagging significantly behind the forecast used for the Charm production period embodied emissions? In addition - it doesn't appear that the forecasts used here for Charm oil injection match the forecasts used of Charm production in the Charm embodied emission calcs (off by an order of magnitude for out years?).	Open – Converted to FAR	(350 Comment – based on discussion with Charm): Charm has provided significant additional documentation (containing proprietary forecasts) documenting approach for reconciling this and accounting for reconciliation of embodied emissions allocations. Moving to forward action request based on evidence provided of forward actions, with discussion and approval with Isometric, Charm and 350 to occur.
ISS-35	Clarification Request	Recommendation - Totalize in sheet	Recommend totalizing the Value for the three emissions sources in attached spreadsheet to ease checking (and allow AI to identify also)	Resolved	We will ensure this is totalized going forward for faster/more efficient QA.
ISS-34	Omission	Embodied emissions allocation - Behind Schedule	In reviewing the Nov 2025 PP embodied emissions allocations, it was observed that the embodied emissions allocations are lagging significantly behind due to production levels not hitting forecasts. When reviewing Cap Ex MRV November spreadsheet, the forecast biomass throughput for the production periods completed to date (through Nov 2025) are forecast to have a total biomass throughput of 2749 tDBM, when the actual throughput has been 1019	Open – Converted to FAR	(350 Comment – based on discussion with Charm): Charm has provided significant additional documentation (containing proprietary forecasts) documenting approach for reconciling this and accounting for reconciliation of embodied emissions allocations. Moving to forward action request based on evidence provided of forward actions, with discussion and approval with Isometric, Charm and 350 to occur.

			tDBM, or 37% of forecast. As a result, the embodied emissions will not be fully accounted for in the 5 year allocation period planned without future production significantly exceeding planned capacity. It is suggested that the allocation schedule be revised to reflect actual operations and revised production forecasts (noting max throughput has been 116 (average 81) tonnes per month as opposed to forecast 234 tonnes). This will significantly increase embodied emissions allocation for all periods, (close to double) and would require accounting for prior production periods as well.		
ISS-33	Clarification Request	Biomass Transport Clarification - Nov25 PP	Can you please clarify where the Biomass transport tonnes (cell c13) comes from in the November 2025 PP Summary file? It is identical to the value in Miniforge Biomass Transport Allocation -- Updated tonnes cell, but I dont see supporting data for that value	Resolved	Hello, I have added the delivery log into the folder and linked here ((file link redacted by 350)) Here is the complete xlxs/sheets version, also pushed into the folder. ((file link redacted by 350)) Was attempting to make things less busy, we will ensure this is attached/included going forward. Note: The routing on our delivery log changed slightly because of the completion of a new scale at a Love's close to Charm's Fort Lupton location. This is the scale we will use going forward.
ISS-32	Clarification Request	April 2025 CI not included	The production emissions for April 2025 are not included in the attached spreadsheet (Tote IDs 197929, 200610). Can you please explain? (did not see an explanation in the VVB Guidance specific to this).	Resolved	Charm did not allocate emissions to the QOWV fraction until June 2025 because there were questions about its sequestration method. The months prior (May 2025 and earlier), all production emissions were allocated to WODO and biochar only. Once those questions were answered, we officially added QOWV to our production allocation. For reference to how emissions were allocated, here is April's PP Summary. You can see in columns M-T we did not have the QOWV fraction (should've added this in guidance as a reminder, thank you for double checking) ((file link redacted by 350))
ISS-31	Clarification Request	Removal-Batch-Feedstock-Production Emissions Crosswalk	For future verifications, it would be EXTREMELY helpful if Charm would provide a summary table that identifies the Removal ID in certify, Injection date, Charm Batch ID, Feedstock type for that batch/removal, and if/what production emissions are accounted for in the batch. You could use the GHG Statement spreadsheet downloaded from Certify. With the numbers of removals, feedstocks, and separate production emissions increasing, it is becoming increasingly difficult for the verifier to	Resolved	Heard, and this feedback is also very helpful! We'll put a reference sheet together ASAP for future verifications.

			easily identify batches and production emissions. Although not required, this would be VERY helpful.		
ISS-30	Omission (converted to FAR)	Basco monthly LDENR report	The monitoring data was provided for March, but the monthly report copy to LDENR was not provided Please upload the LDENR report as well as the email confirmation of receipt	Resolved Resolved. Reports provided and confirmed filed on time and with no issues.	Charm Industrial User (04-15-2026 18:59): As with the quarterly reporting requirement, monthly reporting is due within 30 days after the close of the month. So, March reporting would be due at the end of April. When reporting is completed sooner (as was the case with the reporting package submitted in February) we will provide it in the reporting package for the same month. When it is not, it will be included with the subsequent reporting package.
ISS-18	Omission (converted to FAR)	Pending April bio-oil spill disposal	VVB Guidance document (Google drive) indicates a spill of bio-oil occurred during the reporting period that will be properly disposed of in April. Noting this as a FAR to ensure disposal emissions are accounted for in for the next verification	Resolved. Charm is properly tracking and accounting for associated disposal emissions	NA

APPENDIX 3: VERIFIER QUALIFICATIONS

Supporting documentation, including verifier resumes, and verifier or corporate accreditations are also included in this appendix.

Verifier Qualifications	Criteria Met?	Evidence / Notes *(note how the criteria was met, specific documents - resume/CV, publications, certifications, etc.).*
Verifier has relevant technical knowledge of the type of technology being evaluated and carbon removal processes in general		
A) Does Verifier have:		
1. An in-depth technical knowledge of the technology type under verification;	☑	350Solutions is accredited to ISO/IEC 17020:2012 and ISO 14034 Environmental Technology Verification (ETV) as a Type A (third party) Inspection Body (ANAB Certificate Number: AI-2618). The technical scope of 350's accreditation includes verification of performance and environmental impact as it relates to design, materials, equipment, installation and operations of technologies in the categories of Energy, Clean Production and Process, and Air Pollution Monitoring and Abatement. As documented in 350Solutions' ETV Standard Operating Procedure (ETV QPM 350-223-03), and Quality Systems Procedures for verifier qualifications (QSP-350-005-02), 350Solutions conforms to the requirements of ISO 17020 Annex A with respect to verifier qualifications and procedures. These procedures and quality management programs are generally relevant to verification under the Isometric Standard. Note that verifications completed for Isometric are not equivalent to ISO 14034 verifications. 350 staff have participated in the evaluation and verification of novel technologies that sequester carbon via various methods, including biomass conversion to liquids, solids, and other products which are then permanantly stored in ways such as land application or geologic storage, conversion of captured CO2 into building materials and co-products, and the production of chemicals, fuels, and products via biomass pyrolysis and gasification. 350 also served as lead verifier for the Carbon XPrize competition and contributed to the development of procedures and processes for verification of relevant calculations, modeling, and statistical methods in order to assess team results and calculations of performance metrics and uncertainty. 350 has demonstrated knowledge of data quality and data validation approaches and execution in supporting verification of performance claims and results.
2. Knowledge of specific risk areas associated with performance of such technologies (i.e. common failure points, performance issues, barriers to scaleup);	☑	
3. Knowledge of the environmental implications related to the use of the technology from a life cycle perspective, such as impact of the technology on lifecycle CO2 emissions and carbon removal;	☑	
4. Knowledge of relevant applicable test methods and standards for evaluating performance or impact of the technology;	☑	
5. Knowledge of relevant calculation, modeling, and statistical methods in order to assess test results and calculations of performance metrics and uncertainty, as applicable;	☑	
6. Knowledge of data quality and data validation approaches, including QA/QC procedures, for example.	☑	
Verifier is a credible independent 3rd party		
B) Is Verifier:		
1. third-party body independent of the team registered for the Isometric Registry	☑	350Solutions is accredited to ISO/IEC 17020:2012 and ISO 14034 ETV as a Type A (third party) Inspection Body. As documented in 350Solutions ETV Policy Manual (ETV QPM 350-200-03), 350Solutions conforms to the requirements of ISO 17020 Annex A with respect to impartiality for Type A inspections, pursuant to ISO 14034 activities.
2. Not directly involved in the design, manufacture or construction, marketing, installation, use or maintenance of the specific technologies submitted to Isometric for verification, or represent the parties engaged in those activities.	☑	
3. Not part of a legal entity that is engaged in design, manufacture, supply, installation, purchase, ownership, use or maintenance of the items inspected.	☑	

Tim Hansen, P.E.
Founder and CEO, 350Solutions

EDUCATION:
B.S., Chemical Engineering, University of Virginia, 1993
M.S., Engineering Science, Thayer School of Engineering, Dartmouth College, 1995

EXPERIENCE SUMMARY:
Mr. Hansen has 26 years of experience in management of energy and environmental technology development and demonstration projects and programs, as well as multimedia environmental engineering efforts. The majority of his recent work has focused on the evaluation of innovative carbon capture, utilization, and removal technologies. Mr. Hansen has led the development and management of large technology evaluation programs in the advanced energy, transportation, and climate change areas.

RESEARCH AND PROFESSIONAL EXPERIENCE:
2019-Present Founder – CEO, 350Solutions, Inc.
Owns and operates a small cleantech engineering consulting business focused on the independent evaluation of new cleantech innovations and their impact on the environment and carbon emissions. Provides engineering consulting, testing and evaluation, techno-economic assessment, and other support to companies developing, using, or investing in new clean technology innovations. Manages administrative, business development, and project activities for 350Solutions.

2012-2019: Director - Energy and Environment, Southern Research
Manages scientific and technical staff performing research, development, and evaluation of innovative clean energy technologies. Projects range from $25,000 to $6million in size, and are funded by the US Department of Energy, Department of Defense, and commercial partners. Technical focus areas are conversion of biomass to fuels and chemicals, carbon capture and utilization, energy efficient building technologies and renewable energy generation.

2009-2012: Program Manager – Transportation & Climate Change Technology, Southern Research
2003-2009 Sr. Project Leader, Environmental Engineer, Southern Research
1996-2003 Environmental Engineer, Bensinger & Garrison Environmental

PROJECT EXPERIENCE:
Mr. Hansen has executed several independent technology performance verifications of emerging carbon, energy and transportation technologies, as CEO of 350Solutions, Director of Energy & Environment at Southern Research, and Director of the U.S. EPA's Greenhouse Gas Technology Center. Mr. Hansen has completed clean technology evaluations for the Department of Defense, state energy agencies, commercial clients, investors, and technology developers, involving evaluation of commercial feasibility, economic and environmental impacts, and technology performance. Mr. Hansen served as the Measurement and Verification Program Lead for the NRG COSIA Carbon XPrize – a $20M prize competition for technologies that capture and beneficially utilize CO_2. Mr. Hansen also served as U.S. Technical Expert for the development and implementation of ISO 14034 – Environmental Technology Verification, an international standard, issued in 2016

Bill Chatterton
Senior Verification Scientist, 350Solutions

EDUCATION:
B.S. Environmental Science, SUNY at Plattsburgh, 1982
A.A.S. Environmental Technology, Paul Smith College, 1979
Certified Measurement and Verification Professional (CMVP), 2019

EXPERIENCE SUMMARY:
Mr. Chatterton has over 30 years of experience in management of energy and environmental technology development and demonstration projects and programs, as well as multimedia environmental engineering efforts. The majority of his recent work has focused on the evaluation of innovative carbon capture, utilization, and removal technologies. Mr. Chatterton has supported the development and management of large technology evaluation programs in the advanced energy, transportation, and climate change areas.

RESEARCH AND PROFESSIONAL EXPERIENCE:
2019-Present Sr Verification Scientist – 350Solutions, Inc.
Owns and operates a small cleantech engineering consulting business focused on the independent evaluation of new cleantech innovations and their impact on the environment and carbon emissions. Provides engineering consulting, testing and evaluation, techno-economic assessment, and other support to companies developing, using, or investing in new clean technology innovations. Manages administrative, business development, and project activities for 350Solutions.

2010-2019: Program Manager - Energy and Environment, Southern Research
Managed scientific and technical staff performing research, development, and evaluation of innovative clean energy technologies. Projects range from $25,000 to $6million in size, and are funded by the US Department of Energy, Department of Defense, and commercial partners. Technical focus areas are conversion of biomass to fuels and chemicals, carbon capture and utilization, energy efficient building technologies and renewable energy generation.

2000-2009 Sr. Project Leader, Environmental Engineer, Southern Research

PROJECT EXPERIENCE:
Mr. Chatterton has executed several independent technology performance verifications of emerging carbon, energy and transportation technologies for 350Solutions and previously at Southern Research Institute. Mr. Chatterton has completed clean technology evaluations for the Department of Defense, state energy agencies, commercial clients, investors, and technology developers, involving evaluation of commercial feasibility, economic and environmental impacts, and technology performance. Mr. Chatterton served as a Lead Verifier for the NRG COSIA Carbon XPrize – a $20M prize competition for technologies that capture and beneficially utilize CO_2. Mr. Chatterton is also a Certified Measurement and Verification Professional, issued in 2019.