Facilities and Equipment		
Total Cost of Construction and Equipment (CAD)	$110,000,000.00	
CAD --> USD Exchange Rate	$0.75	https://g.co/kgs/fvorfWH
Total Cost of Construction and Equipment (USD)	$82,500,000.00	
Total Cost of Equipment	$36,300,000.00	
Total Cost of Construction	$9,900,000.00	
Total Cost of Installation, Utilities, Other Non-Equipment Costs	$36,300,000.00	
Kg CO2e/USD Emissions Factor Other Industrial Machinery Manufacturing	0.178	NAICS/EPA Supply Chain Emissions Factors
Kg CO2e/USD Emissions Factor Industrial Building Construction	0.310	NAICS/EPA Supply Chain Emissions Factors
Kg CO2/USd Emissions for Wiring, Installation, and Utility Contractors	0.245	NAICS/EPA Supply Chain Emissions Factors
Total Embodied Emissions: Equipment (Kg CO2e)	6,461,400.00	
Total Embodied Emissions: Construction (Kg CO2e)	3,069,000.00	
Toal Embodied Emissions: Installation, Utilities, Other Non-Equipment Costs (Kg CO2e)	8,893,500.00	
Total Embodied Emissions (Kg CO2e)	18,423,900.00	
Total Embodied Emissions (MT CO2e)	18423.9	
Expected Lifetime Production of Facility (Liters)	716,000,000.00	
Expected Lifetime Production of Facility (MT)	873,520.00	
Total Embodied Emissions (MT CO2e/MT Oil)	0.02	
Biomass Transport Embodied Emissions		
MT biomass per liter of Bio Oil	0.002081243072	
MT biomass hauled per trip (dry equivalent)	1.798561151	
Liters Bio Oil per trip	864.176403	
MT Bio Oil per trip	1.054295212	
Round trip distance (km)	1.5	
Round trip distance (mi)	0.932059105	
Embodied Emissions/Trip (TCO2e/mi)	0.00007153461456	
Transport Embodied Emissions/MT Bio Oil	0.0000678506492	
Total Embodied Emissions (T CO2e)/MT Bio Oil	0.02115941123	

	21.15941123	