Validation and Verification Report

For Isometric

CDR Supplier	Vaulted Deep
CDR Pathway	BICRS
Project	TIRE Project
Location	**Terminal Island Water Reclamation Plant** [redacted] United States [redacted]
Verifiers	Kelly Inder-Nesbitt Charlie Skurie Tim Hansen
Crediting Period	January 3rd, 2026 – January 3rd, 2031
Reporting Period	January 3rd, 2026 – February 20th, 2026
Net CO_2e Removed	427.52 tonnes CO_2e
Report Date	June 17, 2026
Version	V1.3

350 SOLUTIONS

Contents

Acronyms and Chemical Definitions 4

List of Figures 4

List of Tables 4

1. Introduction 5

2. Technology Description 6

2.1. Process Overview 6

2.1.1 Feedstock Sourcing and Receipt 7

2.1.2 Slurry Preparation and Pre Injection Handling 7

2.1.3 Injection Operations and Equipment 8

2.2. Monitoring, Measurement and Data Management 9

2.2.1 Operational Monitoring and Control Systems 9

2.2.2 Measurement, Data Collection and Reporting Systems 10

2.3. Technology Boundaries and Integration 10

2.4. Net CDR Calculation 11

2.4.1 Net CDR Calculation Framework 11

2.4.2 Net CO_2e Removal Calculation 11

2.5. Changes since Validation and Previous Verification(s) 12

3. Validation & Verification Process 12

3.1. Objectives and Scope 12

3.2. Responsibilities 12

3.3. Level of Assurance & Materiality 12

3.4. Validation Body Details 12

3.5. Protocols and Modules Applied & Eligibility 12

3.6. Project Boundary 13

3.7. Approach 14

4. Crediting Details 15

4.1 Project Reporting Period 15

4.2 Crediting Period 15

5. Validation and Verification Summary 15

5.1. Accuracy of the Opinion 15

5.2. Validation and Verification Opinion 16

5.3. Summary of Validation and Verification Findings 17

5.4. Validation and Verification Limitations 19
5.5. Exemptions from Isometric 19
6. Revision History 20
7. References 20
Appendix 1: Log of Findings 21
Appendix 2: Copy of Isometric Exemption List 29
Appendix 3: Files Reviewed 30
Appendix 4: Verifier Qualifications 37

Acronyms and Chemical Definitions

ANAB	ANSI National Accreditation Board
AWMS	American Waste Management Services
BICRS	Bio-Intermediary Carbon Removal and Storage
CEQA	California Environmental Quality Act
CDR	Carbon Dioxide Removal
CO_2	Carbon Dioxide
CO_2e	Carbon Dioxide Equivalent
DAS	Distributed Acoustic Sensing
EPA	United States Environmental Protection Agency
FAR	Forward Action Request
GHG	Greenhouse Gas
HPE	High Pressure Effluent
ISO	International Organization for Standardization
LCA	Life Cycle Assessment
MASIP	Maximum Allowable Surface Injection Pressure
MRV	Monitoring, Reporting, and Verification
PDD	Project Design Document
SSR	Sources, Sinks, and Reservoirs
UIC	Underground Injection Control
VVB	Validation and Verification Body
WRTP	Water Reclamation Treatment Plant

List of Figures

Figure 1: TIRE Facility (pit area) 5
Figure 2: Hopper 7
Figure 3: Flow Lines 8
Figure 4: Injection Well 9
Figure 5: Monitoring Wells on site 9

List of Tables

Table 1. Validation & Verification Summary. 6
Table 2. Eligibility Criteria. 13
Table 3. GHG Sources, Sinks, and Reservoirs. 13
Table 4. Audit Activities. 14
Table 5. Net CDR Calculation for the Reporting Period January 3rd, 2026 – February 20th, 2026. 16
Table 6. Requirements from the relevant Isometric standard, protocol, and modules. 17
Table 7. Validation and Verification Forward Action Requests. 19
Table 8. Isometric List of Waivers and Exemptions. 20

ISOMETRIC VALIDATION AND VERIFICATION REPORT		
Company: Vaulted Deep	Company Contact: Hayley Leslie-Bole* Jose Ubillus	VVB: 350Solutions Kelly Inder-Nesbitt* Charlie Skurie Lily Schacht Tim Hansen
Removal Method: BICRS		
Document No: 350VR-ISO2406		

**primary contact/lead author*

1. Introduction

350Solutions was contracted to validate Vaulted Deep's TIRE Project and verify the greenhouse gas (GHG) statement for the first reporting period. The validation and verification process included observation of operations during a remote site visit, collection of files and evidence related to feedstock receipt, handling, and subsurface injection processes, review of sampling and analytical procedures, evaluation of data collection and management systems, as summarized in the TIRE Project Design Document (PDD), to the relevant Isometric Standards and Protocols. The crediting period for this validation is January 3rd, 2026 – January 3rd, 2031 and the reporting period for this verification is January 3rd, 2026 – February 20th, 2026.

The site visit was conducted on November 12th, 2025 (Remote Site Visit) and a desk review of documents provided by Vaulted Deep, including the PDD followed thereafter. 350Solutions affirms that TIRE Project has the appropriate equipment, procedures, and protocols in place to quantify GHG removal through the injection of waste into deep permeable reservoirs in accordance with the requirements of the Isometric standards, protocols, and modules listed in Table 1. The total removals for this reporting period is 427.52 tonnes CO_2e.



Figure 1: TIRE Facility (pit area)

A summary of the project, GHG statement, validation and verification is provided in Table 1.

Table 1. Validation & Verification Summary.

GHG Removal Supplier	Vaulted Deep
Project Name	TIRE Project
Project Code	B9B1
Removal Method	BICRS
Legal Ownership of Removal Credits	Vaulted Deep
Validation and Verification Report Date	June 17, 2026
Site Visit Dates	November 12th, 2025 (Remote Site Visit)
Crediting Period	January 3rd, 2026 – January 3rd, 2031
Reporting Period	January 3rd, 2026 – February 20th, 2026
Net CO_2e Removed	427.52 tonnes CO_2e
Project Location (Address and GPS Coordinates)	[redacted]
Validation Type	Isometric Standard validation and verification, including site visit, project validation, and credit verification in accordance with the following standard, protocol, and modules: - Isometric Standard v1.1 - Biomass Geological Storage Protocol v1.1 - Embodied Emissions Accounting v1.0 - Energy Use Accounting v1.2 - Transportation Emissions Accounting v1.1 - Biomass Feedstock Accounting v1.2 - Biomass Storage in Permeable Reservoirs v1.0

2. Technology Description

2.1. Process Overview

The Vaulted TIRE Project utilizes a biomass slurry injection pathway whereby organic waste materials are permanently sequestered through injection into a deep, permeable geologic formation. The Project is located within the Terminal Island Water Reclamation Plant (WRTP) in San Pedro, California, and operates under a U.S. EPA Class V Underground Injection Control (UIC) permit. Carbon dioxide removal (CDR) is achieved through diversion of additional biosolids from counterfactual disposal pathways—primarily land application—and emplacement of the biogenic carbon within a geologic storage complex intended to provide long-term containment.

The Project does not involve the construction of new injection infrastructure. Instead, it leverages an existing, long-operating biosolids injection facility, with carbon removal credited only for incremental waste volumes above a defined historical baseline. The CDR activity is therefore integrated into existing waste management operations, with project eligibility and crediting constrained to additional volumes accepted under modified economic conditions (i.e., tipping fee waivers).

2.1.1 Feedstock Sourcing and Receipt

Feedstocks processed at the TIRE facility consist primarily of municipal biosolids generated by wastewater treatment operations managed by the City of Los Angeles. Baseline operations include continuous receipt of sludge from the co-located Terminal Island WRTP, supplemented by trucked biosolids deliveries from external facilities, most notably the Hyperion Water Reclamation Plant. Biosolids injection at the TIRE facility has been conducted historically under prior operators as part of the facility's long-standing waste management operations, with the Project representing an extension of these existing activities rather than the introduction of a new process.

Under the Project, carbon removal is attributed exclusively to biosolids volumes exceeding the historical five-year average injection baseline. These incremental volumes are enabled through the waiver of tipping fees, thereby altering the disposal pathway for a subset of biosolids that would otherwise be land applied. Emergency deliveries and Class B biosolids are explicitly excluded from crediting and tracked separately within operational records.

Incoming feedstock mass is determined through external weighbridge measurements at supplier facilities using calibrated equipment. The Project does not employ on-site truck scales; accordingly, mass accounting relies on supplier-provided weigh tickets and associated documentation, which are incorporated into the Project's data management system.



Figure 2: Hopper

2.1.2 Slurry Preparation and Pre Injection Handling

Biosolids received at the TIRE facility undergo minimal pre-treatment prior to injection. Wetcake biosolids are combined with digested sludge, high-pressure effluent (HPE), and/or brine, as available, to produce a pumpable slurry. This process occurs within dedicated mixing infrastructure, including pre-injection tanks and associated piping systems.

A screening stage is applied prior to injection to remove foreign materials, primarily for equipment protection and operational reliability. No thermal, chemical, or biological transformation of the biomass is performed as part of Project operations. As such, the carbon content of the injectate reflects the intrinsic biogenic carbon present in the feedstock at the point of receipt.



Figure 3: Flow Lines

2.1.3 Injection Operations and Equipment

Prepared slurry is injected into a deep geologic formation via two active injection wells at the TIRE facility. Injection is facilitated by surface pumps rated at approximately 600 horsepower. The permitted injection interval spans approximately 3,800 to 7,500 feet below ground surface within a sequence of sand and shale formations, overlain by low permeability confining layers intended to limit vertical migration.

The facility comprises four wells in total: two injection wells and two monitoring wells. Project implementation does not require modification of the permitted injection interval or construction of new wells.

Injection operations are conducted within constraints defined by the Class V UIC permit, including limits on injection pressure and rate. Key operational parameters—including injection rate, cumulative injected volume, and surface injection pressure—are continuously monitored. Automatic shut-off systems are in place to halt injection if predefined thresholds are exceeded, consistent with regulatory requirements.



Figure 4: Injection Well



Figure 5: Monitoring Wells on site

2.2. Monitoring, Measurement and Data Management

2.2.1 Operational Monitoring and Control Systems

Injection operations at the TIRE facility are subject to continuous monitoring and control in accordance with the U.S. EPA Class V UIC permit and applicable Isometric storage module requirements. Monitoring systems are designed to maintain injectate containment, verify well integrity, and identify conditions indicative of potential leakage or reversal risk.

Continuously monitored parameters include surface injection pressure (including compliance with maximum allowable surface injection pressure, MASIP), injection rate, and cumulative injected

volume. These parameters are recorded via automated instrumentation integrated into the facility's monitoring systems, with automatic shut-off triggered where operational thresholds are exceeded.

Annulus pressure monitoring is conducted continuously to assess internal well integrity. Subsurface conditions are monitored using downhole instrumentation, including pressure and temperature measurements, enabling assessment of formation response during injection.

Periodic diagnostic testing, including step-rate and pressure fall-off testing, is performed to evaluate formation characteristics, fracture behavior, and reservoir transmissivity. Results are compared against established reservoir models developed during permitting and updated as required. Material deviations from expected behavior would trigger operational review and corrective actions.

Gas detection systems are installed at the wellhead and facility level to detect emissions of CO_2, methane, or other gases with global warming potential greater than one. These systems are equipped with alarms and automatic shutdown functionality. Additional monitoring, including seismic data from regional networks, supports ongoing evaluation of injection-related impacts.

Monitoring outputs are compiled and reported to the EPA in accordance with permit requirements and are made available to support verification of storage integrity and durability.

2.2.2 Measurement, Data Collection and Reporting Systems

Data relevant to quantification, monitoring, and verification of carbon removal are collected through a combination of third-party measurements, on-site instrumentation, and laboratory analyses, and are managed within Vaulted's internal data platform ("Data Vault").

Feedstock mass is determined using calibrated external weigh systems operated by suppliers. Associated documentation (e.g., weigh tickets) is integrated into Project records. Feedstock classification, including exclusion of emergency and non-eligible volumes, is recorded contemporaneously.

Biomass carbon content is determined through third-party laboratory analysis conducted in accordance with recognized ISO/IEC 17025 standards. Following an initial high-frequency sampling period, periodic sampling methodologies are applied to characterize ongoing feedstock composition in line with protocol requirements.

Operational energy consumption is measured via on-site metering where available, supplemented by equipment specifications for non-metered components. All operational, laboratory, and monitoring data are consolidated within Data Vault, which is used to perform carbon accounting calculations in accordance with applicable Isometric methodologies.

Data Vault also functions as the reporting interface for external stakeholders. Following internal validation, data are transmitted to the Isometric registry system to support periodic verification. Records, including raw data, laboratory reports, and operational logs, are retained for a minimum of five years, with appropriate controls to ensure data integrity and auditability.

2.3. Technology Boundaries and Integration

The TIRE technology is implemented within an existing wastewater and biosolids management system and does not operate as a standalone facility. Carbon removal activities are therefore limited to incremental operational changes—specifically, the acceptance and injection of additional biosolids volumes beyond baseline operations.

The technology boundary for the Project begins at the point of feedstock receipt at the injection facility and includes slurry preparation, injection, and monitoring activities. Upstream wastewater treatment processes remain outside the operational control of the Project but are incorporated within the counterfactual baseline assessment.

No material process modifications, new infrastructure, or distinct operational phases are introduced solely for the purposes of carbon removal. As such, the Project represents an extension of existing injection operations, with additional monitoring, data management, and accounting layers applied to enable quantification and verification of carbon removal outcomes.

2.4. Net CDR Calculation

2.4.1 Net CDR Calculation Framework

The Project quantifies net CO_2e removal as the net outcome of (i) CO_2e stored through injection of eligible biosolids, less (ii) deductions for baseline and counterfactual storage, (iii) project emissions, and (iv) any storage losses.

CO_2e stored is determined from the mass of eligible biosolids injected and the measured carbon content of those materials. Only biosolids volumes exceeding the established facility baseline are considered for crediting.

Adjustments are applied to reflect the counterfactual fate of the incremental biosolids, accounting for the proportion of carbon that would have remained stored or been emitted under alternative disposal pathways.

Project emissions are quantified across relevant activities required to deliver, prepare, and inject the biomass and are deducted from gross removals.

Storage integrity is assessed through operational monitoring and subsurface performance data to identify potential leakage, migration outside the defined storage interval, or reversal. Where identified, such losses are incorporated as deductions to net CDR.

2.4.2 Net CO_2e Removal Calculation

Net CO_2e removal is calculated as:

Net CO_2e Removal = CO_2e Stored – Baseline and Counterfactual Adjustments – Project Emissions – Leakage Deductions

where:

- CO_2e Stored represents the quantity of biogenic carbon injected and stored within the geologic formation;
- Baseline and Counterfactual Adjustments account for non-additional volumes and alternative carbon storage outcomes;
- Project Emissions represent emissions attributable to project activities; and
- Leakage Deductions represent any storage losses identified through monitoring.

The application of this framework and the resulting net CO_2e removals are presented in Section 5.

2.5. Changes since Validation and Previous Verification(s)

This is the initial validation (January 9th, 2026 – January 9th, 2031) and verification (January 3rd, 2026 – February 20th, 2026) for this project.

3. Validation & Verification Process

3.1. Objectives and Scope

A planned series of validation and verification activities, detailed in Table 4, were conducted by 350Solutions to assess the submitted PDD and GHG Statement. These activities were intended to independently validate the eligibility of TIRE Project for registration on the Isometric registry following the guidelines of the Isometric Standard v1.1 and associated modules/protocols. 350Solutions was also tasked with verifying carbon dioxide removals for the project.

3.2. Responsibilities

The project proponent, Vaulted Deep, is responsible for the fair presentation of the PDD and GHG Statement in accordance with Isometric criteria.

It is the responsibility of 350Solutions to express an opinion as to whether the PDD, GHG Statement, and supporting documents support project validation and verification under the relevant Isometric standard, protocol, and modules.

3.3. Level of Assurance & Materiality

This validation and verification were completed with a reasonable level of assurance. The materiality threshold of 5%, considering the totality of all omissions, errors, and misstatements, was applied to this audit.

3.4. Validation Body Details

350Solutions Inc. declares that we are an impartial verifying body, free from any conflicts of interest, capable, and qualified to complete this validation for the current operational period according to the Isometric Standard and applicable protocols and modules utilizing a reasonable level of assurance.

350Solutions is an accredited inspection & verification body by ANAB under ISO 17020 for completion of ISO 14034 Technology Verifications. 350Solutions is based out of Raleigh, North Carolina, USA. The Technical Lead for the TIRE Project validation and verification is Kelly Inder-Nesbitt. Quality assurance was provided by Lily Schacht. Complete validator qualifications are included in Appendix 4.

3.5. Protocols and Modules Applied & Eligibility

The validation was conducted following the specifications of the following standards, protocols, and modules:

- Isometric Standard v1.1
- Biomass Geological Storage Protocol v1.1

- Embodied Emissions Accounting v1.0
- Energy Use Accounting v1.2
- Transportation Emissions Accounting v1.1
- Biomass Feedstock Accounting v1.2
- Biomass Storage in Permeable Reservoirs v1.0

According to the BICRS Protocol, projects are eligible if they meet the criteria listed in Table 2.

Table 2. Eligibility Criteria.

Projects must	Assessment	Result
Utilize eligible biomass feedstocks in accordance with the Biomass Feedstock Accounting Module	The Project utilizes biosolids as feedstocks, consistent with the Biomass Feedstock Accounting Module requirements.	Acceptable
Inject biomass into natural or engineered geologic formations via an underground injection well	The Project injects biosolids into a deep geologic formation via a permitted underground injection well at the TIRE facility.	Acceptable
Provide a net-negative CO_2e impact as calculated in the GHG Statement	The Project demonstrates net negative CO_2e removal through the lifecycle assessment and GHG statement.	Acceptable
Use sustainably sourced biomass feedstocks	Biosolids are sourced from municipal wastewater treatment operations, consistent with sustainable sourcing expectations under the Protocol.	Acceptable
Not cause net environmental or social harm	The Project operates under CEQA review and EPA permitting, with no material environmental or social harms identified. Isometric issued an exemption for stakeholder Engagement. (See section 5.5 and Appendix 2.)	Acceptable with Isometric Exemption and FARs in place
Additionality	The Project demonstrates additionality through diversion of incremental biosolids enabled by tipping fee waiver and reliance on carbon finance.	Acceptable
Provide long duration storage (>1000 years) of carbon in geologic formations	The Project demonstrates durable storage through deep geologic injection, supported by site characterization, operational history, and modeling indicating >1000 year storage.	Acceptable
Operate at a geologic storage site that is properly permitted with a valid UIC injection well permit	The TIRE facility operates under a valid Class V UIC permit and complies with applicable regulatory requirements governing underground injection.	Acceptable

3.6. Project Boundary

The greenhouse gas (GHG) sources, sinks, and reservoirs (SSRs) within the system boundary for TIRE Project are listed in Table 5.

Table 3. GHG Sources, Sinks, and Reservoirs.

Activity	SSR	Quantification Method
	Delivery of biomass to injection site	Emissions associated with transport of biosolids are quantified based on transport activity (distance and

Project Establishment / Operations		vehicle type), using distance-based methods supported by mapped distances and standardized emission factors.
	Injection facility operations (including surface processing, slurry preparation, and injection system)	Energy consumption associated with facility operations is quantified using electricity usage data and applicable grid emission factors. Supporting data include facility operational records and energy allocation assumptions.
	HPE (High Pressure Effluent) pumping emissions	Emissions associated with HPE pumping are quantified using estimated electricity consumption and corresponding emission factors, where direct measurement data are not available.
	Foreign material transport and handling (offsite)	Emissions are quantified based on material quantities, transport distances, and freight emission factors using tonne-kilometre approaches.
	Equipment use and maintenance (e.g., pump maintenance)	Emissions associated with maintenance activities are quantified using material usage (e.g., lubricants, consumables) and proxy emission factors.
	Monitoring, sampling, and laboratory analysis	Emissions associated with monitoring activities are quantified using distance-based methods for sample transport and activity/spend-based methods for laboratory analysis.
Sinks / Storage	CO_2 stored in geologic formation	CO_2 stored is quantified based on the mass of injected biosolids and measured carbon content, converted to CO_2e. This represents the primary removal term.
Counterfactual / Leakage	Counterfactual carbon storage	The counterfactual fate of diverted biosolids is accounted for by quantifying carbon that would have been emitted or stored under alternative disposal pathways (e.g., land application).
	Market leakage	Market leakage is assessed in accordance with feedstock eligibility criteria. The Project satisfies EC1, and the feedstock has negative commercial value; therefore, no leakage emissions are applied.
End-of-Life	End-of-life emissions (equipment and infrastructure)	Emissions associated with end-of-life activities, including equipment and infrastructure, are estimated using equipment inventories, usage assumptions, and supporting emission factors.

3.7. Approach

The validation process activities are described in Table 6. Appendix 1 contains findings identified during the validation and verification process and their resolutions. The files that were reviewed are listed in Appendix 3.

Table 4. Audit Activities.

Date(s)	Activity	Tasks
December 5, 2025 – May 5, 2026	PDD Review	- Assess PDD against applicable Isometric standards, protocols, and modules - Review project description, system boundaries, and technology description

		- Assess baseline definition and additionality approach - Review feedstock eligibility and sourcing approach - Review monitoring, measurement, and data management approach
November 12th, 2025 (Remote Site Visit)	Site Visit	Discussions and a video call was held to discuss the following: - Review facility layout, injection infrastructure, and operational setup - Assess implementation of monitoring and control systems - Review data collection systems and data management platform - Conduct interviews with project personnel - Review operational procedures and records supporting project activities
January 3 – February 28, 2026	GHG Statement and Supporting Document Review	- Review calculations of all terms in net CDR calculation - Review monitoring data used in quantification - Review raw analytical data and laboratory results - Review feedstock mass and carbon content inputs - Review energy, transport, and operational emissions calculations - Review counterfactual assumptions and associated deductions - Review supporting documentation for project emissions (e.g., metering, transport data, equipment assumptions)
April 29 – June 10, 2026	Report Writing	- Draft report
June 12 - 14, 2026	Quality Assurance and Revisions	- Review by internal QA, Isometric, and Vaulted Deep - Edits to address concerns raised

4. Crediting Details

4.1 Project Reporting Period

The reporting period for Vaulted Deep Tire Project is January 3rd, 2026 – February 20th, 2026. This is the first reporting period for this project.

4.2 Crediting Period

The crediting period for this project is January 3rd, 2026 – January 3rd, 2031. This is the first crediting period for this project.

5. Validation and Verification Summary

5.1. Accuracy of the Opinion

The information provided in the PDD and GHG Statement have been evaluated, cross-referenced with the presented evidence, and confirmed. Confirmation of the PDD has been based on the following efforts:

1. Verification of calculation structure and input data for net CO_2e removal

2. Recalculation of CO_2e stored based on biomass mass and carbon content
3. Verification of baseline definition and counterfactual modeling approach
4. Review of project emissions and life cycle assessment inputs
5. Review of feedstock eligibility, characterization, and tracking
6. Assessment of monitoring, measurement, and data management systems
7. Assessment of storage integrity monitoring and reversal risk framework
8. Review of environmental and social safeguarding practices

The net CO_2e removal calculation was independently assessed through recalculation where possible and review of supporting data, assumptions, and methodologies where direct recalculation was not feasible. Given the high volume of individual removals generated by the Project, verification was performed using a representative sample of removal records and underlying data, in addition to assessment of the overall calculation framework and data aggregation processes.

Project emissions include energy consumption, transportation, high-pressure effluent (HPE) operations, foreign material handling, propane use, pump maintenance, laboratory sampling, and counterfactual emissions, as detailed in the GHG Statement. The aggregated results for the reporting period, including claimed and verified values, are presented in Table 5.

Table 5. Net CDR Calculation for the Reporting Period January 3rd, 2026 – February 20th, 2026.

Parameter	Claimed Value	Verified Value	Data Source
CO_2e Stored (Biogenic Carbon Injected)	517.59 tCO_2e	517.59 tCO_2e	gss_1KQAGXZR01S049TKxlsx ggs_1KJGT4M0B1S0ZGZG-sources.zip 01-03-26_02-20-26 Isometric GHG Statement Report 4.10 Revision.pdf
Project Emissions (Total)	97.73 tCO_2e	97.73 tCO_2e	
Net Removal of CO_2e	427.52 tCO_2e	427.52 tCO_2e	

* Values have been rounded and may not add up without error.

5.2. Validation and Verification Opinion

Based on the confirmation described in Section 5.1, 350Solutions has found that the data presented in the TIRE Project PDD, GHG Statement, and supporting documentation, and the site visit:

☐ ***Meets the requirements of the Isometric Standard v1.1 and Biomass Geological Storage Protocol for Validation and Verification***

☒ ***Meets the requirements with Isometric-Approved Exemptions or Deviations from the Isometric Standard v1.1 and Biomass Geological Storage Protocol for Validation and Verification***

☐ ***Meets the requirements of the Isometric Standard v1.1 and Biomass Geological Storage Protocol for Validation and Verification with minor modifications***

☐ ***Does Not Meet the requirements of the Isometric Standard v1.1 and Biomass Geological Storage Protocol for Validation and Verification***

By adhering to the requirements of the Isometric standard, protocols and modules, **Vaulted Deep**'s TIRE Project has been validated as eligible for crediting in accordance with the criteria listed in Section 3.5 with a reasonable level of assurance. The GHG statement submitted has been verified and conforms to the criteria with a reasonable level of assurance.

VVB	Lead Auditor	Report ID No.
350Solutions, Inc.	Kelly Inder-Nesbitt	350VR-ISO2406

Signed: Kelly Inder-Nesbitt (Lead Auditor) — Digitally signed by Kelly Inder-Nesbitt, Date: 2026.06.17 14:39:58 -04'00'

Lily Schacht (Quality Assurance) — Digitally signed by Lily Schacht, Date: 2026.06.17 14:32:12 -04'00'

5.3. Summary of Validation and Verification Findings

Table 6contains a summary of findings and any identified issues associated with each requirement in the applicable Isometric standard, protocol, and modules. See Appendix 1 for a log of all findings identified throughout the validation and verification process.

Table 6. Requirements from the relevant Isometric standard, protocol, and modules.

Reference	Criteria	Finding
	Isometric Standard v1.0	
3.7 / 3.8	Stakeholder Engagement & Grievance Mechanism	**Acceptable with Isometric Exemption**– Isometric granted an exemption from the pre-project stakeholder engagement timing requirement based on the long operating history of the Terminal Island facility, existing regulatory oversight, prior engagement activities by previous operators, and Vaulted's forward stakeholder engagement plan and active grievance mechanism. No material change in community impacts relative to baseline operations was identified.
2.5.2	Baseline	**Acceptable** – The Project establishes a baseline using a five-year historical average of biosolids injected at TIRE, excluding emergency and Class B volumes. Additional biosolids volumes above the baseline are assumed to be diverted from land application and are assessed against a conservatively adjusted baseline to mitigate the risk of over-crediting.
2.5.3	Additionality	**Acceptable** – Historical TIRE operations were funded through City of Los Angeles tipping fees. Additional feedstock volumes are obtained through waiver of tipping fees above the baseline threshold, with carbon finance providing the revenue necessary to support incremental biosolids acceptance and storage activities.
2.5.4	Leakage	**Acceptable** – The Project identified nutrient replacement and market leakage as the primary potential leakage pathways associated with diversion of biosolids from a Farm. Supplementary documentation

		demonstrated compliance with EC1 and concluded any potential market leakage remains below Isometric materiality thresholds.
2.5.1 / 2.5.5	System Boundary & GHG Statement	**Acceptable** – The Project boundary includes feedstock transport, preprocessing, injection, monitoring, decommissioning and well plugging activities, together with project emissions, counterfactual emissions and counterfactual storage calculations.
2.5.7	Uncertainty	**Acceptable** – Carbon content is determined using project-specific laboratory testing and Isometric-approved sampling methodologies. Conservative assumptions are applied where direct measurement is not feasible.
Biomass Geological v1.1		
6.3	Ownership	**Acceptable** – Ownership of environmental attributes and carbon credit rights is established through agreements between GeoEnvironment, AWMS, Vaulted Deep and the City of Los Angeles. The contractual framework reviewed provides clear ownership of removals generated by the Project.
6.4	Additionality	**Acceptable** – The Project demonstrated that additional biosolids volumes are enabled through waived tipping fees and carbon finance. Deep geologic injection of biosolids for carbon removal is not considered common practice within the United States.
7.2	Counterfactual Baseline	**Acceptable** – The Project identifies land application at [redacted] Farm as the most likely counterfactual fate of additional biosolids. Counterfactual emissions and storage are quantified using a two-pool biosolids decay model.
7.3	Net CO_2e Removal Calculation	**Acceptable** – Net removals are calculated using measured feedstock carbon content, project emissions, counterfactual emissions and counterfactual storage. Project accounting includes transportation, operational energy use, maintenance and end-of-life emissions.
7.3.5.6	Leakage	**Acceptable** – Leakage was assessed through feedstock eligibility screening and a project-specific market leakage analysis. The assessment concluded that diversion of biosolids from [redacted] does not create material market leakage.
Biomass Storage in Permeable Reservoirs Module v1.0		
3.3	Physical Characterization	**Acceptable** – The Project provided reservoir characterization information supporting the suitability of the storage formation for long-term biosolids emplacement. The TIRE facility has an established operational history of biosolids injection.
3.4	Geochemical Characterization	**Acceptable** – Available geologic and geochemical information supports long-term storage of injected biomass within the target formation and is consistent with the permanence objectives of the Project.
4.1	Injection and Monitoring	**Acceptable** – Operational monitoring procedures are in place for feedstock receipt, injection activities and storage accounting. Monitoring requirements are consistent with the Project monitoring plan and protocol requirements. The Projects environmental permits and licenses are all current and no non-compliance was observed with local legislation.
4.5	Closure and Post-Closure	**Acceptable** – Decommissioning and well-plugging activities are included within the Project boundary and associated emissions are incorporated into the project accounting framework.
OVERALL ELIGIBILITY		ELIGIBLE
Eligible Period		January 9th, 2026 – January 9th, 2031

5.4. Validation and Verification Limitations

While Vaulted Deep has demonstrated compliance with the applicable Isometric standard, protocol, and modules, certain unresolved issues have been identified. Although these issues have been deemed acceptable for the current reporting period, they are required or strongly recommended for resolution in the next verification cycle. The forward action requests (FARs) outlining these requirements are detailed in Table 7.

Table 7. Validation and Verification Forward Action Requests.

ID No	Date Issued	Finding / Issue	Audit Evidence	Protocol Reference	Required Action
ISS – 79 , 81	April 20, 2026	Stakeholder engagement activities have not yet been implemented [redacted] Isometric granted an exemption from the pre-project stakeholder engagement timing requirement based on existing facility engagement records, regulatory oversight, and Vaulted's forward engagement plan.	Stakeholder Engagement Exemption Note (April 2026), Stakeholder Engagement Plan, Grievance Mechanism Documentation	Isometric Standard v1.0 §3.7, §3.8	[redacted] implement the stakeholder engagement plan, including stakeholder outreach, grievance tracking, and maintenance of a stakeholder engagement log. Evidence of implementation shall be reviewed at first verification.
ISS - 106	April 28, 2026	Historical propane purchase records are currently used as a proxy for estimating propane consumption within the LCA.	ISS-106 Log of Issues, TIRE LCA Workbook, Supporting Propane Consumption Documentation	Isometric Standard v1.0 §2.5.5	Replace historical propane consumption estimates with contemporaneous propane purchase and consumption records during the verification period and update emissions calculations accordingly.
FAR-03	April 21, 2026	Historical lubricant purchase records are currently used as a proxy for estimating lubricant consumption associated with facility maintenance activities.	ISS-88 Log of Issues, TIRE LCA Workbook, Maintenance and Consumables Documentation	Isometric Standard v1.0 §2.5.5	Replace historical lubricant consumption estimates with contemporaneous lubricant purchase and usage records during the verification period and update emissions calculations accordingly.

5.5. Exemptions from Isometric

Table 10 states the requirements that have been deemed not applicable to Vaulted Deep's TIRE Project and as a result have received an ad-hoc waiver or exemption from Isometric. These exemptions have resulted from discussions between Isometric and Vaulted Deep and communication to 350Solutions. Copies of Isometric exemptions can be found in Appendix 2.

Table 8. Isometric List of Waivers and Exemptions.

Requirements Waiver Description	Standard	Waiver, Exemption, or Not Applicable

Isometric granted an exemption from the requirement to conduct stakeholder engagement prior to project development [redacted]. The decision was supported by historical [redacted], existing regulatory oversight, Vaulted's forward stakeholder engagement plan, and an active grievance mechanism.	Isometric Standard v1.0 §3.7 Stakeholder Engagement	Exemption

6. Revision History

Version	Date Issued	Noted Changes
Draft Version 1.0 (v1.0)		N/A
Draft Version 1.1 (v1.1)	June 11, 2026	
Version 1.2 (v1.2)	June 15, 2026	Redactions requested
Version 1.2 (v1.3)	June 17, 2026	Final Report

7. References

[1] Isometric, "Isometric Standard v1.1," Accessed: 1 Dec. 2025. [Online]. Available: https://registry.isometric.com/standard/1.6.2

[2] Isometric, "Biomass Geological Storage Protocol v1.1," Accessed: 1 Dec. 2025. [Online]. Available: https://registry.isometric.com/protocol/biomass-geological-storage/1.1

[3] Isometric, "Embodied Emissions Accounting v1.0," Accessed: 1 Dec. 2025. [Online]. Available: https://registry.isometric.com/protocol/embodied-emissions/1.0

[4] Isometric, "Energy Use Accounting v1.2," Accessed: 1 Dec. 2025. [Online]. Available: https://registry.isometric.com/protocol/energy-use-accounting/1.2

[5] Isometric, "Transportation Emissions Accounting v1.1," Accessed: 1 Dec. 2025. [Online]. Available: https://registry.isometric.com/protocol/transportation/1.1

[6] Isometric, "Biomass Feedstock Accounting v1.2," Accessed: 1 Dec. 2025. [Online]. Available: https://registry.isometric.com/module/biomass-feedstock-accounting/1.2

[7] Isometric, "Biomass Storage in Permeable Reservoirs v1.0," Accessed: Dec. 2025. [Online]. Available: https://registry.isometric.com/module/biomass-storage-in-permeable-reservoirs/1.0

Appendix 1: Log of Findings

ID	Date Issued	Type	Finding / Required Action	Audit Evidence	Protocol Reference	Vaulted Response	Date Resolved
ISS-60	2026-02-24T19:17:19.789086+00:00	Clarification Request	Method A (detailed sampling of individual batches) must be completed for the first 30 batches before transitioning to Method B (periodic sampling). However we could begin using method B if you've already sampled at least 30 batches. Actions needed: 1. Clarify your sampling progress: Please confirm whether you have already collected 30 Method A samples. If so, this should be explicitly stated in Section B.3. If not, the PDD should reflect that you will complete Method A sampling before moving to Method B. 2. Update Section E.1 (Monitoring Plan) to include: Your sampling protocol and QA/QC procedures for feedstock characterization Plans for monitoring gas composition at the injection site Carbon content testing methodology for feedstock Mass measurement procedures for feedstock - Currently, Section E.1 states "No samples collected at this time" for carbon content and feedstock mass, which conflicts with the indication that sampling has begun. Please update this to reflect your actual monitoring activities.	Project design	R-TGBM-0	I think we have answered this issue. Yes, we collected 30 method A and then moved to method B.	2026-04-23T15:30:39.553323+00:00
ISS-59	2026-02-24T19:16:38.862449+00:00	Clarification Request	The protocol requires evidence that diverted biosolids will not be replaced with synthetic fertilizer (or	Project design	R-HF2G-0	I've attached Isometric's leakage assessment and	2026-05-05T16:08:15.898988+00:00

			other amendments) that would generate GHG emissions, as this would undermine the emissions reduction claim. While we appreciate the email confirmation you've provided, validation requires more formal documentation to create an auditable record. Actions needed: 1. Add a statement of intent in Section B.5 confirming that no replacement fertilizer will be applied to [redacted] to compensate for the diverted biosolids rather than the current statement that replacement emissions are "not likely". 2. Obtain a formal affidavit or signed attestation from [redacted] farm (if feasible) that confirms: No additional fertilizer is currently being applied due to the biosolids diversion [redacted] they begin purchasing or applying fertilizer in the future We understand that formal documentation from municipal partners can be challenging to obtain. A signed statement from [redacted] would be sufficient and more robust than the email screenshot currently provided.			added text specifying that market leakage emissions are found to be below the materiality threshold when using the most conservative estimates.	
ISS-44	2025-12-23T13:36:25.707200+00:00	Error	Please revise the model to reflect N2O emissions and decay rates for untreated solids.	Feedstock: LACity_Biosolids	R-BTYG-0		2026-02-09T09:46:38.340804+00:00
ISS-43	2025-12-19T18:42:43.585343+00:00	Clarification Request	The attached document is more detailed, but there is value in provide a few more points of clarity in this summary description for comprehension: 1. Please detail the period of time that the historical baseline will be based. Specifically, weekly	Project design	R-PGFH-0		2026-02-16T15:44:15.771603+00:00

			quantities of biosolids injected for the previous 5 years, up to the beginning of the crediting period. 2. Please add that the historical baseline will be a simple average of volumes of biosolids injected over this time frame - exclusive of Emergency Class B volumes - which is appropriate due to the lack of trend in the volumes over the historical 5 year period. 3. Clarify that the cushion will be calculated based on a simulations of annual volumes based on weekly estimates random sampling historical volumes, relative to volumes beginning in the crediting period. Given the cushion is a function of the actual volumes beginning in the crediting period, not strictly historical volumes, the ultimate baseline (historical volumes + cushion) will be evaluated monthly or quarterly for the first year, and additional, creditable volumes will be based on these incremental assessments, ex-post				
ISS-37	2025-11-12T20:04:31.106610+00:00	Omission	Need GeoEnvironment + Hyperion included Also need company numbers for all partners. All fields should be filled.	Project design	R-F6R7-0		
ISS-36	2025-11-12T20:02:13.112172+00:00	Nonconformity	Vaulted is working on: 	Project design	R-M858-0		2026-03-02T13:26:05.985313+00:00
ISS-31	2025-11-12T14:29:18.347552+00:00	Omission	Ideally the submission should outline the specific regulatory framework governing the project operations, including all relevant permits, approvals, and compliance requirements beyond the general mention of EPA regulation and	Project design	R-9MJQ-0		2026-06-10T17:59:51.863954+00:00

			CEQA review. This could be left as a forward action request for now, to be updated in the next 1-2 weeks.				
ISS-27	2025-11-10T20:32:15.049009+00:00	Omission	The description of the volumes of waste that are eligible for crediting implies that volumes will only come from the TIRE facility. I believe Vaulted is also aiming to secure volumes from Hyperion and potential other WWTPs. The description should be updated to reflect this. Additionally, please include a description of the baseline conditions regarding obtaining emergency volumes per the historical contract.	Project design	R-PGFH-0		2026-03-02T13:29:05.609816+00:00
ISS-18	2025-10-28T15:27:17.146504+00:00	Clarification Request	The document attached with CEQA comments is dated 2011. DO you have a more up-to-date evidence available?	Project design	R-X9EC-0	Should be OK for now but would ideally need a more up-to-date documentation	2026-03-02T17:09:28.663292+00:00
ISS-24	2025-10-28T15:34:45.583003+00:00	Clarification Request	Is the TIRE project having any affect on the amount of land-applied biosolids that would have an affect on farm production/yield	Feedstock: LACity_Biosolids	R-CBPZ-0		2025-12-29T11:09:28.569225+00:00
ISS-23	2025-10-28T15:34:37.829745+00:00	Clarification Request	Tied to a similar question within the baseline section of the PDD - Will vaulteds involvement increase the injection volumes and therefore divert the use of biosolids as a soil amendment?	Feedstock: LACity_Biosolids	R-RPVA-0		2025-12-29T11:09:13.929617+00:00
ISS-15	2025-10-28T15:23:15.537512+00:00	Clarification Request	Previous sections refer to the use of fracture simulation models. They must be included here.	Project design	R-NZQ2-0		2025-11-11T18:38:36.575570+00:00
ISS-14	2025-10-28T15:21:25.722228+00:00	Clarification Request	Can you please include some more detail on how the uncertainty analysis around biomass carbon content will be assessed.	Project design	R-2AVD-0		2025-11-12T19:56:08.342159+00:00
ISS-13	2025-10-28T15:19:26.784921+00:00	Nonconformity	This section is missing a few of the monitoring requirements regarding the injectant itself such as the carbon content of the biomass, mass of injectant etc. as per the relevant protocol. These must be included.	Project design	R-ENZR-0		2025-11-12T19:56:49.749112+00:00

ISS-10	2025-10-28T15:09:00.676673+00:00	Clarification Request	Please could you provide a bit more detail around the lack of a leakage consideration here? If there is a complete diversion of biosolids from [redacted] with no replacement fertiliser there could be a significant drop in farm production of feed crops etc. How is this considered? Are enough biosolids still applied to [redacted] to provide a nutrient benefit? Is the crop produced from this acreage deemed unnecessary?	Project design	R-HF2G-0		2025-11-11T18:26:57.282043+00:00
ISS-4	2025-10-28T15:04:30.490818+00:00	Clarification Request	Fuel Use from Feedstock Transport - In section B.3 the transportation method detailed relates to diesel vehicles. Can this section's description be amended to be in line with this?	Project design	R-2VKW-0		2025-11-11T18:24:12.452721+00:00
ISS-5	2025-10-28T15:04:34.765993+00:00	Clarification Request	Counterfactual Emissions: Temporary Carbon Storage from Feedstock - This section refers to the counterfactual of combustion while the established baseline for the feedstock is field spreading. Please amend.	Project design	R-2VKW-0		2025-11-11T18:25:00.787938+00:00
ISS-26	2025-11-06T15:58:34.072626+00:00	Omission	Neither pdf mentioned is linked - please update with relevant links.	Project design	R-QASJ-0		2025-11-12T19:44:44.342605+00:00
ISS-21	2025-10-28T15:32:55.265642+00:00	Clarification Request	Please use the Stakeholder engagemnt plan template provided for the GP site to address this section.	Project design	R-ZHRN-0		2025-11-12T19:45:11.548964+00:00
ISS-20	2025-10-28T15:32:47.014022+00:00	Clarification Request	The detail for well closures is great - thank you for describing this so clearly. Please also describe what happens to the rest of the project (facilities and equipment) after project closure.	Project design	R-6VFZ-0		2025-11-12T19:49:15.292528+00:00
ISS-17	2025-10-28T15:23:55.802518+00:00	Omission	Please clearly identify the specific persons or organizations responsible for each aspect of measurement and data collection, including roles for external facilities, laboratory analysis, and internal data management. The current submission mentions various	Project design	R-GYA1-0		2025-11-11T22:14:47.771698+00:00

			parties but does not clearly assign responsibilities. Please also specify ASWM and GeoEnvironment's roles in data collection and storage.				
ISS-11	2025-10-28T15:11:14.448120+00:00	Clarification Request	Could you please provide additional evidence to substantiate the [redacted] [redacted] [redacted] Any supporting documentation would be very helpful, that or a simple spreadsheet showing Vaulted's finances with and without credits over the next several years. The spreadsheet should contain Vaulted's primary CAPEX + OPEX costs and indicate how carbon financing interacts with the two.	Project design	R-53Y5-0		2025-11-12T19:51:53.927625+00:00
ISS-22	2025-10-28T15:34:27.032362+00:00	Misrepresentation	Please include a quantification of counterfactual storage using the equations within the biomass feedstock accounting module. The use of the 50 year time horizon necessitates the quantification of CO2eEmissions15 to exceed	Feedstock: LACity_Biosolids	R-BTYG-0		2025-12-21T15:37:01.167289+00:00

			CO2eFeedstock - CO2eStorage50 (i.e. the CO2eEmissions15 must have a significant portion of emissions with a GWP100 >1. Full equation here: CO2eCounterfactul = CO2eFeedstock - CO2eCounterfactualEmissions CO2eCounterfactualEmissions = min(CO2eCounterfactualEmissions, CO2eFeedstock - CO2eCounterfactualStorage50) This section would benefit from referenced and representative values based on a typical sample and its associated decay rate and emission profile.				
ISS-25	2025-10-31T15:08:21.464465+00:00	Nonconformity	[redacted]	Project design	R-M858-0	[redacted]	2025-11-12T20:00:20.767008+00:00

			[redacted]				

Appendix 2: Copy of Isometric Exemption List

Exemption Note: Vaulted TIRE Validation

April, 2026

As per Section 3.7 and 3.8 of the Isometric Standard (applied via the Biomass Geological Storage Protocol v1.1), suppliers are required to conduct stakeholder engagement prior to the start of project development, with a documented engagement plan, an active grievance mechanism, and evidence of consultation with affected communities. The requirement exists to ensure that affected stakeholders are informed of project activities, can raise concerns through a formal channel, and are consulted iteratively as the project progresses.

An exemption from the pre-project timing element of this requirement is granted to Vaulted (TIRE) based on the following justifications:

- Vaulted provided prior community engagement records associated with the existing Terminal Island injection facility, which has operated for years under the Terminal Island WWTP permit envelope. Project activities under Vaulted are near-identical to baseline operations from a community-impact perspective, so existing facility-level engagement remains substantively relevant.
- The project adheres to the in-force air and water quality permits held by the Terminal Island WWTP. The regulatory consultation pathway represented by those permits has been continuously in force, providing a documented form of stakeholder oversight throughout the project's existence.
- Vaulted has submitted a robust forward stakeholder engagement plan, mirroring the plan already operating at their existing facility. A grievance mechanism is live, and stakeholder office hours are scoped and ready to execute.
- Vaulted has exhausted what it can reasonably do under current project constraints. [redacted] Engagement will be conducted as soon as practicable [redacted]

Isometric assessed the risk of this decision on the basis of community impact, regulatory oversight, and forward engagement readiness. Risk is minimal because the project does not change baseline community impact at the site, the facility continues to operate under its existing permits, prior engagement records remain materially relevant, and Vaulted's forward plan and live grievance mechanism are sufficient to capture and respond to any community concerns in the interim.

Appendix 3: Files Reviewed

src_1KJ7N64FE1S0CBA5_From_Source_To_Facility_TIRE_Foreign_Materials_Transportation_Distance.png
src_1KJ7N666F1S0KN1F_From_Source_To_Facility_TIRE_Biosolids_.png
src_1KKH8ZPXX1S0GAEB_V3-vaulted-2-2026-01-03-1530-carbon_content-95275.pdf
src_1KKH8ZQZD1S03ZA0_V3-vaulted-2-2026-01-03-1530-not_integrated_feed_organic-95411.pdf
src_1KKH8ZT1W1S0QM5N_V3-vaulted-2-50-final_process_energy_use-97813.jpg
src_1KKH8ZW0Z1S0B91A_V3-vaulted-2-50-initial_process_energy_use-97812.jpg
src_1KKH91AP21S03R33_V3-vaulted-2-2026-01-04-1531-carbon_content-95287.pdf
src_1KKH91BNB1S0QCYR_V3-vaulted-2-2026-01-04-1531-not_integrated_feed_organic-95412.pdf
src_1KKH91RBA1S0NE61_V3-vaulted-2-2026-01-04-1533-carbon_content-95277.pdf
src_1KKH91T571S0931P_V3-vaulted-2-2026-01-04-1533-not_integrated_feed_organic-95413.pdf
src_1KKH9260F1S0G5J3_V3-vaulted-2-2026-01-04-1534-carbon_content-95278.pdf
src_1KKH926X71S03TDR_V3-vaulted-2-2026-01-04-1534-not_integrated_feed_organic-95416.pdf
src_1KKH92JWF1S0DP0X_V3-vaulted-2-2026-01-04-1535-carbon_content-95279.pdf
src_1KKH92NGK1S01AWJ_V3-vaulted-2-2026-01-04-1535-not_integrated_feed_organic-95415.pdf
src_1KKH9309X1S0PG34_V3-vaulted-2-2026-01-04-1538-carbon_content-95281.pdf
src_1KKH9316F1S0A4YS_V3-vaulted-2-2026-01-04-1538-not_integrated_feed_organic-95417.pdf
src_1KKH93E4Z1S0ZTXT_V3-vaulted-2-2026-01-04-1543-carbon_content-95282.pdf
src_1KKH93F111S0KFSF_V3-vaulted-2-2026-01-04-1543-not_integrated_feed_organic-95418.pdf
src_1KKH93X1E1S06CNR_V3-vaulted-2-2026-01-04-1550-carbon_content-95283.pdf
src_1KKH93YMN1S0T1HD_V3-vaulted-2-2026-01-04-1550-not_integrated_feed_organic-95419.pdf
src_1KKH94ADH1S0VHWA_V3-vaulted-2-2026-01-04-1560-carbon_content-95284.pdf
src_1KKH94BAC1S0F6QZ_V3-vaulted-2-2026-01-04-1560-not_integrated_feed_organic-95421.pdf
src_1KKH94N471S06M8T_V3-vaulted-2-2026-01-05-1562-carbon_content-95660.pdf
src_1KKH94PFN1S0T94F_V3-vaulted-2-2026-01-05-1562-not_integrated_feed_organic-95423.pdf
src_1KKH952461S04TRG_V3-vaulted-2-2026-01-05-1561-not_integrated_feed_organic-95422.pdf
src_1KKH95DTJ1S042S4_V3-vaulted-2-2026-01-05-1563-not_integrated_feed_organic-95424.pdf
src_1KKH95PTB1S0B59H_V3-vaulted-2-2026-01-05-1564-not_integrated_feed_organic-95425.pdf
src_1KKH95ZV51S0J7SY_V3-vaulted-2-2026-01-05-1566-not_integrated_feed_organic-95426.pdf
src_1KKH968EJ1S0SAAB_V3-vaulted-2-2026-01-05-1568-not_integrated_feed_organic-95427.pdf
src_1KKH96H8H1S07PJ2_V3-vaulted-2-2026-01-05-1569-not_integrated_feed_organic-95428.pdf
src_1KKH96V5R1S0ES2F_V3-vaulted-2-2026-01-05-1593-not_integrated_feed_organic-95429.pdf
src_1KKH977AC1S0NVJW_V3-vaulted-2-2026-01-06-1595-not_integrated_feed_organic-95430.pdf
src_1KKH97H3R1S0WY39_V3-vaulted-2-2026-01-06-1596-not_integrated_feed_organic-95431.pdf
src_1KKH97XAS1S040KP_V3-vaulted-2-2026-01-06-1597-carbon_content-95286.pdf
src_1KKH97YB51S0QNFB_V3-vaulted-2-2026-01-06-1597-not_integrated_feed_organic-95557.pdf
src_1KKH988861S0TXC2_V3-vaulted-2-2026-01-06-1600-not_integrated_feed_organic-95433.pdf
src_1KKH98JZK1S0BHY2_V3-vaulted-2-2026-01-06-1601-not_integrated_feed_organic-95434.pdf
src_1KKH98X3S1S08HMD_V3-vaulted-2-2026-01-06-1610-not_integrated_feed_organic-95435.pdf
src_1KKH99CDR1S0CV22_V3-vaulted-2-2026-01-06-1611-not_integrated_feed_organic-95436.pdf
src_1KKH99PDB1S0XFM2_V3-vaulted-2-2026-01-06-1626-not_integrated_feed_organic-95437.pdf
src_1KKH99ZJG1S01S1Q_V3-vaulted-2-2026-01-07-1630-not_integrated_feed_organic-95439.pdf

src_1KKH9AMJE1S0FMGZ_V3-vaulted-2-2026-01-07-1629-not_integrated_feed_organic-95438.pdf
src_1KKH9AYKN1S0KXYM_V3-vaulted-2-2026-01-07-1635-not_integrated_feed_organic-95440.pdf
src_1KKH9B8G31S0ZH3K_V3-vaulted-2-2026-01-07-1636-not_integrated_feed_organic-95441.pdf
src_1KKH9BJBF1S0B48J_V3-vaulted-2-2026-01-07-1644-carbon_content-95280.pdf
src_1KKH9BKA21S0YS47_V3-vaulted-2-2026-01-07-1644-not_integrated_feed_organic-95558.pdf
src_1KKH9C3161S01G8F_V3-vaulted-2-2026-01-07-1647-not_integrated_feed_organic-95443.pdf
src_1KKH9CD5G1S030KC_V3-vaulted-2-2026-01-07-1653-not_integrated_feed_organic-95444.pdf
src_1KKH9CPX91S04GY9_V3-vaulted-2-2026-01-10-1756-not_integrated_feed_organic-95445.pdf
src_1KKH9D1XF1S06196_V3-vaulted-2-2026-01-11-1757-not_integrated_feed_organic-95446.pdf
src_1KKH9DB8A1S07HM3_V3-vaulted-2-2026-01-11-1760-not_integrated_feed_organic-95447.pdf
src_1KKH9DMFP1S02Z11_V3-vaulted-2-2026-01-11-1761-not_integrated_feed_organic-95448.pdf
src_1KKH9DXB21S04FBY_V3-vaulted-2-2026-01-11-1763-not_integrated_feed_organic-95559.pdf
src_1KKH9E7PK1S05ZPV_V3-vaulted-2-2026-01-11-1771-not_integrated_feed_organic-95560.pdf
src_1KKH9EJG41S07G1R_V3-vaulted-2-2026-01-11-1772-not_integrated_feed_organic-95561.pdf
src_1KKH9EVMY1S090CN_V3-vaulted-2-2026-01-11-1775-carbon_content-95654.pdf
src_1KKH9EWKS1S0WN8A_V3-vaulted-2-2026-01-11-1775-not_integrated_feed_organic-95562.pdf
src_1KKH9F86Y1S0N9JG_V3-vaulted-2-2026-01-11-1785-not_integrated_feed_organic-95563.pdf
src_1KKH9FHRM1S0CQ3B_V3-vaulted-2-2026-01-12-1786-not_integrated_feed_organic-95565.pdf
src_1KKH9FTT21S01BHE_V3-vaulted-2-2026-01-12-1787-not_integrated_feed_organic-95566.pdf
src_1KKH9G3GS1S0RS29_V3-vaulted-2-2026-01-12-1788-not_integrated_feed_organic-95567.pdf
src_1KKH9GDQE1S0G6K4_V3-vaulted-2-2026-01-12-1791-not_integrated_feed_organic-95568.pdf
src_1KKH9GR0V1S07M3Z_V3-vaulted-2-2026-01-12-1798-not_integrated_feed_organic-95569.pdf
src_1KKH9H1TT1S0Z1MT_V3-vaulted-2-2026-01-12-1802-not_integrated_feed_organic-95570.pdf
src_1KKH9HBN71S0PF5N_V3-vaulted-2-2026-01-12-1803-not_integrated_feed_organic-95571.pdf
src_1KKH9HPQ01S0DWPG_V3-vaulted-2-2026-01-12-1813-not_integrated_feed_organic-95572.pdf
src_1KKH9J0VY1S0CKYN_V3-vaulted-2-2026-01-13-1817-not_integrated_feed_organic-95573.pdf
src_1KKH9JA9E1S041FG_V3-vaulted-2-2026-01-13-1818-carbon_content-95655.pdf
src_1KKH9JB6Z1S0QPB5_V3-vaulted-2-2026-01-13-1818-not_integrated_feed_organic-95574.pdf
src_1KKH9JSFJ1S067V9_V3-vaulted-2-2026-01-13-1823-not_integrated_feed_organic-95575.pdf
src_1KKH9K3CA1S0KJJ2_V3-vaulted-2-2026-01-13-1828-not_integrated_feed_organic-95576.pdf
src_1KKH9KBZ91S00X8V_V3-vaulted-2-2026-01-13-1827-not_integrated_feed_organic-95577.pdf
src_1KKH9KP501S0WVE8_V3-vaulted-2-2026-01-13-1829-not_integrated_feed_organic-95578.pdf
src_1KKH9M1SP1S0XV0P_V3-vaulted-2-2026-01-13-1831-not_integrated_feed_organic-95579.pdf
src_1KKH9MDNE1S0B5QF_V3-vaulted-2-2026-01-13-1836-not_integrated_feed_organic-95580.pdf
src_1KKH9MRHM1S0RGE8_V3-vaulted-2-2026-01-13-1844-not_integrated_feed_organic-95581.pdf
src_1KKH9N2NC1S05V51_V3-vaulted-2-2026-01-14-1847-not_integrated_feed_organic-95582.pdf
src_1KKH9NC401S06TQF_V3-vaulted-2-2026-01-14-1849-not_integrated_feed_organic-95583.pdf
src_1KKH9NQP11S07T9X_V3-vaulted-2-2026-01-14-1850-carbon_content-95657.pdf
src_1KKH9NRK81S0VF5J_V3-vaulted-2-2026-01-14-1850-not_integrated_feed_organic-95584.pdf
src_1KKH9P7YM1S0ZXVM_V3-vaulted-2-2026-01-14-1855-not_integrated_feed_organic-95585.pdf
src_1KKH9PHXQ1S035RB_V3-vaulted-2-2026-01-14-1860-not_integrated_feed_organic-95586.pdf
src_1KKH9PVAH1S06DN2_V3-vaulted-2-2026-01-14-1862-not_integrated_feed_organic-95587.pdf

src_1KKH9Q53X1S09NHS_V3-vaulted-2-2026-01-14-1869-not_integrated_feed_organic-95588.pdf
src_1KKH9QGGY1S0CXEG_V3-vaulted-2-2026-01-17-1937-not_integrated_feed_organic-95615.pdf
src_1KKH9QTRM1S0G5B7_V3-vaulted-2-2026-01-18-1939-not_integrated_feed_organic-95616.pdf
src_1KKH9R5C21S0KD7Y_V3-vaulted-2-2026-01-18-1940-not_integrated_feed_organic-95617.pdf
src_1KKH9RHVR1S0PN4N_V3-vaulted-2-2026-01-18-1941-not_integrated_feed_organic-95619.pdf
src_1KKH9RXVM1S0FT7A_V3-vaulted-2-2026-01-18-1944-carbon_content-95656.pdf
src_1KKH9RYQ31S03F2Z_V3-vaulted-2-2026-01-18-1944-not_integrated_feed_organic-95620.pdf
src_1KKH9SA311S0XTYZ_V3-vaulted-2-2026-01-18-1952-not_integrated_feed_organic-95621.pdf
src_1KKH9SQJC1S0HYMK_V3-vaulted-2-2026-01-18-1956-not_integrated_feed_organic-95622.pdf
src_1KKH9T2AR1S0B3Q8_V3-vaulted-2-2026-01-18-1958-not_integrated_feed_organic-95623.pdf
src_1KKH9TC9T1S048SX_V3-vaulted-2-2026-01-18-1969-not_integrated_feed_organic-95625.pdf
src_1KKH9TNPT1S0XDWJ_V3-vaulted-2-2026-01-19-1971-not_integrated_feed_organic-95626.pdf
src_1KKH9TYX91S0PJZ7_V3-vaulted-2-2026-01-19-1973-not_integrated_feed_organic-95627.pdf
src_1KKH9VGM91S0APMV_V3-vaulted-2-2026-01-19-1974-not_integrated_feed_organic-95628.pdf
src_1KKH9VVBC1S03VQG_V3-vaulted-2-2026-01-19-1980-not_integrated_feed_organic-95629.pdf
src_1KKH9W4941S0X0T5_V3-vaulted-2-2026-01-19-1985-not_integrated_feed_organic-95630.pdf
src_1KKH9WEB11S04SBE_V3-vaulted-2-2026-01-19-1988-carbon_content-95658.pdf
src_1KKH9WFCT1S0RE73_V3-vaulted-2-2026-01-19-1988-not_integrated_feed_organic-95631.pdf
src_1KKH9WTV01S0P96Q_V3-vaulted-2-2026-01-19-1990-not_integrated_feed_organic-95632.pdf
src_1KKH9X5Z81S00A29_V3-vaulted-2-2026-01-19-2001-not_integrated_feed_organic-95633.pdf
src_1KKH9XGXN1S0PP26_V3-vaulted-2-2026-01-20-2002-not_integrated_feed_organic-95634.pdf
src_1KKH9XY681S05RAS_V3-vaulted-2-2026-01-20-2003-not_integrated_feed_organic-95635.pdf
src_1KKH9Y9B11S0FS6B_V3-vaulted-2-2026-01-20-2005-not_integrated_feed_organic-95636.pdf
src_1KKH9YKA11S0YVEY_V3-vaulted-2-2026-01-20-2007-not_integrated_feed_organic-95637.pdf
src_1KKH9YZBK1S0DXQH_V3-vaulted-2-2026-01-20-2008-not_integrated_feed_organic-95638.pdf
src_1KKH9ZA861S0QYK3_V3-vaulted-2-2026-01-20-2022-not_integrated_feed_organic-95639.pdf
src_1KKH9ZQE61S047RY_V3-vaulted-2-2026-01-20-2062-not_integrated_feed_organic-95640.pdf
src_1KKHA03C11S0GG1A_V3-vaulted-2-2026-01-21-2063-carbon_content-95659.pdf
src_1KKHA04GD1S044WZ_V3-vaulted-2-2026-01-21-2063-not_integrated_feed_organic-95641.pdf
src_1KKHA0JRZ1S0WYFJ_V3-vaulted-2-2026-01-21-2065-not_integrated_feed_organic-95642.pdf
src_1KKHA0VQG1S01XY3_V3-vaulted-2-2026-01-21-2066-not_integrated_feed_organic-95643.pdf
src_1KKHA14S91S06XCM_V3-vaulted-2-2026-01-21-2069-not_integrated_feed_organic-95644.pdf
src_1KKHA1E7V1S0ZHPT_V3-vaulted-2-2026-01-21-2078-not_integrated_feed_organic-95645.pdf
src_1KKHA1RZ91S017A4_V3-vaulted-2-2026-01-21-2082-not_integrated_feed_organic-95646.pdf
src_1KKHA25Z71S02WXE_V3-vaulted-2-2026-01-21-2083-not_integrated_feed_organic-95647.pdf
src_1KKHA2HC51S07WBZ_V3-vaulted-2-2026-01-24-2198-not_integrated_feed_organic-95709.pdf
src_1KKHA2YE71S09HZ9_V3-vaulted-2-2026-01-25-2200-not_integrated_feed_organic-95710.pdf
src_1KKHA3A2Q1S0665J_V3-vaulted-2-2026-01-25-2201-not_integrated_feed_organic-95711.pdf
src_1KKHA3M5E1S0B5M3_V3-vaulted-2-2026-01-25-2202-carbon_content-96484.pdf
src_1KKHA3NXY1S0YTFR_V3-vaulted-2-2026-01-25-2202-not_integrated_feed_organic-95712.pdf
src_1KKHA43Y81S0NWGH_V3-vaulted-2-2026-01-25-2205-not_integrated_feed_organic-95713.pdf
src_1KKHA4DNS1S0GS50_V3-vaulted-2-2026-01-25-2213-not_integrated_feed_organic-95714.pdf

src_1KKHA4QFV1S06MCE_V3-vaulted-2-2026-01-25-2214-not_integrated_feed_organic-95715.pdf
src_1KKHA50RX1S01H0X_V3-vaulted-2-2026-01-25-2215-not_integrated_feed_organic-95716.pdf
src_1KKHA5BW11S0WDNC_V3-vaulted-2-2026-01-25-2227-not_integrated_feed_organic-95717.pdf
src_1KKHA5PKG1S0QA9V_V3-vaulted-2-2026-01-26-2228-not_integrated_feed_organic-95718.pdf
src_1KKHA61HC1S0J6YA_V3-vaulted-2-2026-01-26-2230-not_integrated_feed_organic-95719.pdf
src_1KKHA6BFT1S0D3JS_V3-vaulted-2-2026-01-26-2236-not_integrated_feed_organic-95720.pdf
src_1KKHA6NF91S0H1GC_V3-vaulted-2-2026-01-26-2239-not_integrated_feed_organic-95721.pdf
src_1KKHA6Z6E1S0BY4V_V3-vaulted-2-2026-01-26-2241-not_integrated_feed_organic-95722.pdf
src_1KKHA77TG1S06TSA_V3-vaulted-2-2026-01-26-2244-not_integrated_feed_organic-95723.pdf
src_1KKHA7GVT1S01QDS_V3-vaulted-2-2026-01-26-2257-not_integrated_feed_organic-95724.pdf
src_1KKHA7WAJ1S0WM28_V3-vaulted-2-2026-01-27-2258-not_integrated_feed_organic-95725.pdf
src_1KKHA87SF1S0QGPQ_V3-vaulted-2-2026-01-27-2259-not_integrated_feed_organic-95726.pdf
src_1KKHA8HFY1S0JDB6_V3-vaulted-2-2026-01-27-2263-not_integrated_feed_organic-95727.pdf
src_1KKHA8TA81S0D9ZN_V3-vaulted-2-2026-01-27-2264-not_integrated_feed_organic-95728.pdf
src_1KKHA95C61S086M4_V3-vaulted-2-2026-01-27-2269-not_integrated_feed_organic-95729.pdf
src_1KKHA9G601S0ACZX_V3-vaulted-2-2026-01-27-2271-not_integrated_feed_organic-95730.pdf
src_1KKHA9TQK1S059MC_V3-vaulted-2-2026-01-27-2273-carbon_content-96492.pdf
src_1KKHA9VP71S0RYG1_V3-vaulted-2-2026-01-27-2273-not_integrated_feed_organic-95731.pdf
src_1KKHAA83Y1S0AZ3S_V3-vaulted-2-2026-01-27-2282-not_integrated_feed_organic-95732.pdf
src_1KKHAAH621S0VRY6_V3-vaulted-2-2026-01-28-2283-not_integrated_feed_organic-95733.pdf
src_1KKHAATT91S0CJRK_V3-vaulted-2-2026-01-28-2285-not_integrated_feed_organic-95734.pdf
src_1KKHAB50Z1S0XCK0_V3-vaulted-2-2026-01-28-2286-not_integrated_feed_organic-95735.pdf
src_1KKHABGBN1S0E6DD_V3-vaulted-2-2026-01-28-2288-not_integrated_feed_organic-95736.pdf
src_1KKHABSBN1S069Z4_V3-vaulted-2-2026-01-28-2292-not_integrated_feed_organic-95737.pdf
src_1KKHAC3EQ1S07ZJE_V3-vaulted-2-2026-01-28-2299-not_integrated_feed_organic-95738.pdf
src_1KKHACEHN1S00345_V3-vaulted-2-2026-01-28-2300-not_integrated_feed_organic-95739.pdf
src_1KKHACTZ31S04HT7_V3-vaulted-2-2026-01-26-2240-carbon_content-96490.pdf
src_1KKHACWVP1S0R6NW_V3-vaulted-2-2026-01-26-2240-not_integrated_feed_organic-95740.pdf
src_1KKHAD7B31S004FJ_V3-vaulted-2-2026-01-31-2395-not_integrated_feed_organic-97301.pdf
src_1KKHADP3K1S0Z104_V3-vaulted-2-2026-02-01-2398-carbon_content-97356.pdf
src_1KKHADQ1Z1S0JNVS_V3-vaulted-2-2026-02-01-2398-not_integrated_feed_organic-97302.pdf
src_1KKHAE1AG1S0GGVD_V3-vaulted-2-2026-02-01-2400-not_integrated_feed_organic-97303.pdf
src_1KKHAEC6W1S0D51P_V3-vaulted-2-2026-02-01-2401-not_integrated_feed_organic-97304.pdf
src_1KKHAER481S0XRME_V3-vaulted-2-2026-02-01-2403-not_integrated_feed_organic-97305.pdf
src_1KKHAF5XT1S01PJ1_V3-vaulted-2-2026-02-01-2404-not_integrated_feed_organic-97306.pdf
src_1KKHAFFDS1S0HZKZ_V3-vaulted-2-2026-02-01-2415-not_integrated_feed_organic-97307.pdf
src_1KKHAFSSF1S0EKT8_V3-vaulted-2-2026-02-01-2417-not_integrated_feed_organic-97308.pdf
src_1KKHAG3D71S0B80H_V3-vaulted-2-2026-02-01-2426-not_integrated_feed_organic-97309.pdf
src_1KKHAGE791S0VH2F_V3-vaulted-2-2026-02-02-2429-not_integrated_feed_organic-97310.pdf
src_1KKHAGR401S0R58R_V3-vaulted-2-2026-02-02-2430-not_integrated_feed_organic-97311.pdf
src_1KKHAH1TT1S0MSF1_V3-vaulted-2-2026-02-02-2441-carbon_content-97434.pdf
src_1KKHAH2RD1S08EAP_V3-vaulted-2-2026-02-02-2441-not_integrated_feed_organic-97312.pdf

src_1KKHAHE1K1S0W6G8_V3-vaulted-2-2026-02-02-2443-not_integrated_feed_organic-97313.pdf
src_1KKHAHRRC1S02CR4_V3-vaulted-2-2026-02-02-2445-not_integrated_feed_organic-97314.pdf
src_1KKHAJ1X41S0MY4B_V3-vaulted-2-2026-02-02-2458-not_integrated_feed_organic-97315.pdf
src_1KKHAJB6W1S0V4C7_V3-vaulted-2-2026-02-03-2460-not_integrated_feed_organic-97316.pdf
src_1KKHAJP771S0DNRE_V3-vaulted-2-2026-02-03-2461-not_integrated_feed_organic-97317.pdf
src_1KKHAJYXS1S0074N_V3-vaulted-2-2026-02-03-2465-not_integrated_feed_organic-97318.pdf
src_1KKHAK94X1S0JRGW_V3-vaulted-2-2026-02-03-2471-not_integrated_feed_organic-97319.pdf
src_1KKHAKKEG1S0RYRR_V3-vaulted-2-2026-02-03-2474-not_integrated_feed_organic-97320.pdf
src_1KKHAKXJQ1S0BG4Z_V3-vaulted-2-2026-02-03-2477-not_integrated_feed_organic-97321.pdf
src_1KKHAM6H51S0CMZT_V3-vaulted-2-2026-02-03-2479-carbon_content-97432.pdf
src_1KKHAM8HV1S009VF_V3-vaulted-2-2026-02-03-2479-not_integrated_feed_organic-97322.pdf
src_1KKHAMMAN1S0C7H8_V3-vaulted-2-2026-02-03-2490-not_integrated_feed_organic-97323.pdf
src_1KKHAMXVX1S0MP3D_V3-vaulted-2-2026-02-04-2495-not_integrated_feed_organic-97325.pdf
src_1KKHAN89H1S0GSH7_V3-vaulted-2-2026-02-04-2496-not_integrated_feed_organic-97328.pdf
src_1KKHANK8Y1S0CWZ1_V3-vaulted-2-2026-02-04-2500-not_integrated_feed_organic-97333.pdf
src_1KKHANXT61S0GA45_V3-vaulted-2-2026-02-04-2505-not_integrated_feed_organic-97336.pdf
src_1KKHAP6PT1S0RRPA_V3-vaulted-2-2026-02-04-2511-not_integrated_feed_organic-97339.pdf
src_1KKHAPHJK1S0MW44_V3-vaulted-2-2026-02-04-2513-not_integrated_feed_organic-97342.pdf
src_1KKHAPV8F1S0XAP9_V3-vaulted-2-2026-02-04-2516-not_integrated_feed_organic-97345.pdf
src_1KKHAQ42Y1S0SE43_V3-vaulted-2-2026-02-04-2527-not_integrated_feed_organic-97349.pdf
src_1KKHAQFSH1S0JRF5_V3-vaulted-2-2026-02-05-2528-carbon_content-97433.pdf
src_1KKHAQGQM1S0T26F_V3-vaulted-2-2026-02-05-2528-not_integrated_feed_organic-97357.pdf
src_1KKHAQVBM1S0SMQX_V3-vaulted-2-2026-02-05-2529-not_integrated_feed_organic-97358.pdf
src_1KKHAR5E01S0R0G0_V3-vaulted-2-2026-02-05-2532-not_integrated_feed_organic-97359.pdf
src_1KKHARFKZ1S0PC83_V3-vaulted-2-2026-02-05-2535-not_integrated_feed_organic-97360.pdf
src_1KKHARRJF1S0CXGD_V3-vaulted-2-2026-02-07-2615-not_integrated_feed_organic-97361.pdf
src_1KKHAS29D1S0B98G_V3-vaulted-2-2026-02-08-2616-not_integrated_feed_organic-97362.pdf
src_1KKHASCB31S09N0K_V3-vaulted-2-2026-02-08-2620-not_integrated_feed_organic-97363.pdf
src_1KKHASPM41S080RP_V3-vaulted-2-2026-02-08-2626-not_integrated_feed_organic-97364.pdf
src_1KKHAT1901S06CGS_V3-vaulted-2-2026-02-08-2628-not_integrated_feed_organic-97365.pdf
src_1KKHATAMJ1S04R8W_V3-vaulted-2-2026-02-08-2630-not_integrated_feed_organic-97366.pdf
src_1KKHATPJF1S0340Z_V3-vaulted-2-2026-02-08-2643-carbon_content-97740.pdf
src_1KKHATQDQ1S0PRWM_V3-vaulted-2-2026-02-08-2643-not_integrated_feed_organic-97367.pdf
src_1KKHAV3ZV1S0C8M0_V3-vaulted-2-2026-02-09-2646-not_integrated_feed_organic-97369.pdf
src_1KKHAVD881S0HDAY_V3-vaulted-2-2026-02-09-2647-not_integrated_feed_organic-97370.pdf
src_1KKHAVRC41S0D009_V3-vaulted-2-2026-02-09-2650-not_integrated_feed_organic-97371.pdf
src_1KKHAW3331S018YA_V3-vaulted-2-2026-02-09-2656-not_integrated_feed_organic-97372.pdf
src_1KKHAWBXH1S0DQCJ_V3-vaulted-2-2026-02-09-2661-not_integrated_feed_organic-97373.pdf

src_1KKHAWQJX1S09A1X_V3-vaulted-2-2026-02-09-2664-not_integrated_feed_organic-97374.pdf
src_1KKHAX0ZE1S0XJZY_V3-vaulted-2-2026-02-09-2679-not_integrated_feed_organic-97375.pdf
src_1KKHAXAJH1S05GSM_V3-vaulted-2-2026-02-10-2682-not_integrated_feed_organic-97376.pdf
src_1KKHAXK9N1S0SSQN_V3-vaulted-2-2026-02-10-2683-not_integrated_feed_organic-97377.pdf
src_1KKHAXXAJ1S0E2NP_V3-vaulted-2-2026-02-10-2684-carbon_content-97742.pdf
src_1KKHAXY6H1S01QHB_V3-vaulted-2-2026-02-10-2684-not_integrated_feed_organic-97378.pdf
src_1KKHAY8141S0VQX9_V3-vaulted-2-2026-02-10-2686-not_integrated_feed_organic-97379.pdf
src_1KKHAYJ411S0MHFW_V3-vaulted-2-2026-02-10-2693-not_integrated_feed_organic-97380.pdf
src_1KKHAYV8F1S0YQKV_V3-vaulted-2-2026-02-10-2698-not_integrated_feed_organic-97381.pdf
src_1KKHAZ3K71S08XQT_V3-vaulted-2-2026-02-10-2700-not_integrated_feed_organic-97382.pdf
src_1KKHAZCG21S0K3VS_V3-vaulted-2-2026-02-10-2715-not_integrated_feed_organic-97383.pdf
src_1KKHAZPSN1S0BXEC_V3-vaulted-2-2026-02-11-2716-not_integrated_feed_organic-97384.pdf
src_1KKHB01B01S0P3JB_V3-vaulted-2-2026-02-11-2717-not_integrated_feed_organic-97385.pdf
src_1KKHB0ANV1S009PA_V3-vaulted-2-2026-02-11-2718-not_integrated_feed_organic-97386.pdf
src_1KKHB0KEY1S0AFT9_V3-vaulted-2-2026-02-11-2721-not_integrated_feed_organic-97387.pdf
src_1KKHB0X5F1S0MNY8_V3-vaulted-2-2026-02-11-2731-carbon_content-97734.pdf
src_1KKHB0Y011S08ASX_V3-vaulted-2-2026-02-11-2731-not_integrated_feed_organic-97388.pdf
src_1KKHB19GP1S09MX5_V3-vaulted-2-2026-02-11-2732-not_integrated_feed_organic-97389.pdf
src_1KKHB1KB31S09R72_V3-vaulted-2-2026-02-11-2734-not_integrated_feed_organic-97390.pdf
src_1KKHB1X3P1S09VGZ_V3-vaulted-2-2026-02-11-2745-not_integrated_feed_organic-97391.pdf
src_1KKHB2B3S1S09YTW_V3-vaulted-2-2026-02-12-2746-not_integrated_feed_organic-97392.pdf
src_1KKHB2KEA1S0A24S_V3-vaulted-2-2026-02-12-2748-not_integrated_feed_organic-97393.pdf
src_1KKHB2X821S0A5EP_V3-vaulted-2-2026-02-12-2747-not_integrated_feed_organic-97394.pdf
src_1KKHB36GT1S0A8RK_V3-vaulted-2-2026-02-12-2749-not_integrated_feed_organic-97395.pdf
src_1KKHB3H211S0AC2G_V3-vaulted-2-2026-02-12-2757-not_integrated_feed_organic-97396.pdf
src_1KKHB3VW21S0AFCD_V3-vaulted-2-2026-02-12-2760-not_integrated_feed_organic-97397.pdf
src_1KKHB461J1S0AJPA_V3-vaulted-2-2026-02-12-2762-carbon_content-97741.pdf
src_1KKHB46XH1S0Y7HZ_V3-vaulted-2-2026-02-12-2762-not_integrated_feed_organic-97398.pdf
src_1KKHB4HSH1S0NEV5_V3-vaulted-2-2026-02-14-2826-not_integrated_feed_organic-97635.pdf
src_1KKHB4VP61S0BFB0_V3-vaulted-2-2026-02-15-2827-not_integrated_feed_organic-97636.pdf
src_1KKHB55721S01FTV_V3-vaulted-2-2026-02-15-2830-not_integrated_feed_organic-97637.pdf
src_1KKHB5FB41S0QGAP_V3-vaulted-2-2026-02-15-2832-not_integrated_feed_organic-97641.pdf
src_1KKHB5TNP1S0PJ3N_V3-vaulted-2-2026-02-15-2838-not_integrated_feed_organic-97645.pdf
src_1KKHB646Q1S0CJKG_V3-vaulted-2-2026-02-15-2852-not_integrated_feed_organic-97647.pdf
src_1KKHB6F6D1S02K3B_V3-vaulted-2-2026-02-15-2854-not_integrated_feed_organic-97648.pdf
src_1KKHB6RQP1S0RKK6_V3-vaulted-2-2026-02-15-2856-not_integrated_feed_organic-97649.pdf
src_1KKHB72NH1S0EM31_V3-vaulted-2-2026-02-15-2872-not_integrated_feed_organic-97650.pdf
src_1KKHB7C021S04MJW_V3-vaulted-2-2026-02-16-2873-carbon_content-97733.pdf
src_1KKHB7D1P1S0R9EH_V3-vaulted-2-2026-02-16-2873-not_integrated_feed_organic-97651.pdf
src_1KKHB7Q9V1S05DXN_V3-vaulted-2-2026-02-16-2874-not_integrated_feed_organic-97652.pdf
src_1KKHB829C1S0HBKE_V3-vaulted-2-2026-02-16-2875-not_integrated_feed_organic-97653.pdf
src_1KKHB8BS11S0GY4W_V3-vaulted-2-2026-02-16-2879-not_integrated_feed_organic-97654.pdf
src_1KKHB8ND91S0WVTN_V3-vaulted-2-2026-02-16-2886-not_integrated_feed_organic-97655.pdf
src_1KKHB90AF1S0WEC3_V3-vaulted-2-2026-02-16-2887-not_integrated_feed_organic-97656.pdf
src_1KKHB9AGW1S08C1W_V3-vaulted-2-2026-02-16-2888-not_integrated_feed_organic-97657.pdf

src_1KKHB9PF71S0M9QN_V3-vaulted-2-2026-02-16-2900-not_integrated_feed_organic-97658.pdf
src_1KKHBA3341S007DE_V3-vaulted-2-2026-02-17-2905-not_integrated_feed_organic-97659.pdf
src_1KKHBADMS1S0N6CB_V3-vaulted-2-2026-02-17-2907-not_integrated_feed_organic-97666.pdf
src_1KKHBAQJM1S01424_V3-vaulted-2-2026-02-17-2908-carbon_content-97736.pdf
src_1KKHBARCZ1S0MRXS_V3-vaulted-2-2026-02-17-2908-not_integrated_feed_organic-97667.pdf
src_1KKHBB43M1S0QTJV_V3-vaulted-2-2026-02-17-2915-not_integrated_feed_organic-97668.pdf
src_1KKHBBDAB1S0SNEJ_V3-vaulted-2-2026-02-17-2916-not_integrated_feed_organic-97669.pdf
src_1KKHBBSBQ1S02T1K_V3-vaulted-2-2026-02-17-2922-not_integrated_feed_organic-97670.pdf
src_1KKHBC2V81S0BDW5_V3-vaulted-2-2026-02-17-2923-not_integrated_feed_organic-97671.pdf
src_1KKHBCC941S0D8QW_V3-vaulted-2-2026-02-18-2933-not_integrated_feed_organic-97672.pdf
src_1KKHBCQ7R1S0F3KK_V3-vaulted-2-2026-02-18-2934-not_integrated_feed_organic-97673.pdf
src_1KKHBD0051S0GYFA_V3-vaulted-2-2026-02-18-2935-not_integrated_feed_organic-97686.pdf
src_1KKHBDA8C1S0JSB1_V3-vaulted-2-2026-02-18-2939-not_integrated_feed_organic-97687.pdf
src_1KKHBDKTH1S0MM6R_V3-vaulted-2-2026-02-18-2940-not_integrated_feed_organic-97688.pdf
src_1KKHBDWEY1S0PF2F_V3-vaulted-2-2026-02-18-2943-carbon_content-97739.pdf
src_1KKHBDXBR1S0A3Y4_V3-vaulted-2-2026-02-18-2943-not_integrated_feed_organic-97689.pdf
src_1KKHBE87H1S032S4_V3-vaulted-2-2026-02-18-2947-not_integrated_feed_organic-97690.pdf
src_1KKHBEGY91S0TTTS_V3-vaulted-2-2026-02-18-2950-not_integrated_feed_organic-97691.pdf
src_1KKHBETVA1S0JJWE_V3-vaulted-2-2026-02-18-2954-not_integrated_feed_organic-97694.pdf
src_1KKHBF6CR1S0AAY3_V3-vaulted-2-2026-02-18-2955-not_integrated_feed_organic-97699.pdf
src_1KKHBFGCQ1S022ZR_V3-vaulted-2-2026-02-18-2963-not_integrated_feed_organic-97700.pdf
src_1KKHBFSGA1S0SV1D_V3-vaulted-2-2026-02-19-2966-not_integrated_feed_organic-97701.pdf
src_1KKHBG3PH1S0HK32_V3-vaulted-2-2026-02-19-2965-not_integrated_feed_organic-97702.pdf
src_1KKHBGE3Y1S09B4Q_V3-vaulted-2-2026-02-19-2967-not_integrated_feed_organic-97703.pdf
src_1KKHBGQWG1S08CXP_V3-vaulted-2-2026-02-19-2970-not_integrated_feed_organic-97705.pdf
src_1KKHBH49D1S004ZB_V3-vaulted-2-2026-02-19-2978-carbon_content-97823.pdf
src_1KKHBH6ES1S0KSV0_V3-vaulted-2-2026-02-19-2978-not_integrated_feed_organic-97706.pdf
src_1KKHBHKB31S02NVY_V3-vaulted-2-2026-02-19-2980-not_integrated_feed_organic-97707.pdf
src_1KKHBHVTM1S0GB3H_V3-vaulted-2-2026-02-19-2985-not_integrated_feed_organic-97708.pdf
src_1KNA1Q9H51S07CWT_111425_Vaulted_GHG_Statement_TIRE_rev3.xlsx

Appendix 4: Verifier Qualifications

350Solutions, Inc. Corporate Experience

350Solutions serves as an independent expert in cleantech, low carbon, and environmental technologies. We provide an unbiased assessment of innovative technologies. 350Solutions is accredited through ANAB under ISO 17020 as an independent inspection body to provide independent technology evaluation services using the ISO 14034 ETV process. In addition, 350Solutions staff include a Certified Measurement and Verification Professional (CMVP for IPMVP) and a North Carolina Registered Professional Engineer (P.E.).

Kelly Inder-Nesbitt
Senior Carbon Removal Verification Engineer, 350Solutions Inc

Education:

- Master of Science in Geography, Archaeology, and Environmental Studies, University of the Witwatersrand, 2014
- Bachelor of Science with Honors in Geography, University of the Witwatersrand, 2011
- Bachelor of Arts in Geography and Archaeology, University of the Witwatersrand, 2010

Experience Summary:

At 350Solutions, Kelly specializes in verifying carbon removal projects to ensure compliance with ISO 14034 standards and carbon registry requirements. With over a decade of experience in environmental compliance and carbon management, she brings extensive expertise in operational compliance and MRV framework implementation, enhancing accuracy, transparency and integrity in the voluntary carbon market.

Kelly's career spans multiple sectors, including aquaculture, mining, and carbon removal technology, where she has developed and audited environmental management systems that promote sustainable practices and attract investor finance. At 350Solutions, she leads the validation of diverse carbon removal pathways, including biochar, BECCS, DAC and direct ocean capture and biomass burial. Her responsibilities encompass site audits and rigorous evaluation of MRV systems to ensure scientifically validated project claims.

Previously Kelly led the development of Brilliant Planet's carbon dioxide removal methodology protocol for algal biomass burial and contributed as an author. She was also responsible for developing and implementing an ISO 14001 compliant EHSS Management System for the FirstWave Group, who are aquaculture industry leaders in Southern and Eastern Africa. This system is also aligned with IFC World Bank Best Practices and leveraged software tools to streamline compliance monitoring and enhance ESG reporting for investor and regulatory alignment.

Throughout her career, Kelly has consistently collaborated with project developers, communities, regulators, and clients to enhance the credibility of environmental initiatives through rigorous documentation and alignment with international standards. Her approach emphasizes precise data management and actionable reporting, elevating compliance practices into a strategic, value-adding process that drives sustainable business growth.

Kelly's strong communication skills and commitment to fostering collaboration enable her to manage complex compliance initiatives effectively. Her ability to bridge the gap between technical requirements and stakeholder expectations continues to advance science-driven, impactful solutions in the carbon removal industry.

Charlie Skurie

Carbon Removal Verification Engineer, 350Solutions

EDUCATION:

B.S., Chemical Engineering, Washington University in St. Louis, 2021

M.E., Energy, Environmental, and Chemical Engineering, Washington University in St. Louis, 2022

EXPERIENCE SUMMARY:

Charlie is a chemical engineer with over three years of R&D experience focused on evaluating low-carbon technologies. His work spans technical performance analysis, environmental impact assessment, and financial viability studies. Charlie has developed lab-scale test methods, conducted material qualification experiments, led pilot trials, and performed lifecycle assessments to advance sustainable innovation.

RESEARCH AND PROFESSIONAL EXPERIENCE:

2025 – Present Carbon Removal Verification Engineer

Verify CDR technologies across multiple pathways by performing site audits, evaluating feedstock characterizations, and reviewing greenhouse gas statements for methodological rigor and project viability. Assessments span CDR pathways but focus on mineralization-based technologies, supporting durable carbon removals.

2022 – 2025 Sustainability Research Engineer, Saint-Gobain

Served as internal consultant on anticipatory lifecycle assessment (LCA) by conducting 40+ LCAs of R&D stage technologies. Translated LCAs into actionable decarbonization insights at product and process level. This work supported business projects focused on circular economy, biobased materials, product stewardship, and implementation of low-carbon processing.

Managed sustainable innovation program, evaluating Horizon 2 and 3 technologies to identify cutting edge material circularity and energy decarbonization opportunities. Performed bench-to-pilot scale experimentation, analytical chemistry, and techno-economic assessments, accelerating sustainable solutions through the R&D stage-gate process.

2021 – 2022 Carbon Neutrality Intern, Washington University in St. Louis

Reviewed LCAs and technical feasibility of low-carbon technologies such as renewable natural gas and renewable electricity at a campus-scale. Produced written briefs to inform long-term carbon neutrality planning.

Tim Hansen, P.E.

Founder and CEO, 350Solutions

EDUCATION:

B.S., Chemical Engineering, University of Virginia, 1993

M.S., Engineering Science, Thayer School of Engineering, Dartmouth College, 1995

EXPERIENCE SUMMARY:

Mr. Hansen has 26 years of experience in management of energy and environmental technology development and demonstration projects and programs, as well as multimedia environmental engineering efforts. The majority of his recent work has focused on the evaluation of innovative carbon capture, utilization, and removal technologies. Mr. Hansen has led the development and management of large technology evaluation programs in the advanced energy, transportation, and climate change areas.

RESEARCH AND PROFESSIONAL EXPERIENCE:

2019-Present Founder – CEO, 350Solutions, Inc.

Owns and operates a small cleantech engineering consulting business focused on the independent evaluation of new cleantech innovations and their impact on the environment and carbon emissions. Provides engineering consulting, testing and evaluation, techno-economic assessment, and other support to companies developing, using, or investing in new clean technology innovations. Manages administrative, business development, and project activities for 350Solutions.

2012-2019: Director - Energy and Environment, Southern Research

Manages scientific and technical staff performing research, development, and evaluation of innovative clean energy technologies. Projects range from $25,000 to $6million in size, and are funded by the US Department of Energy, Department of Defense, and commercial partners. Technical focus areas are conversion of biomass to fuels and chemicals, carbon capture and utilization, energy efficient building technologies and renewable energy generation.

2009-2012: Program Manager – Transportation & Climate Change Technology, Southern Research

2003-2009 Sr. Project Leader, Environmental Engineer, Southern Research

1996-2003 Environmental Engineer, Bensinger & Garrison Environmental

PROJECT EXPERIENCE:

Mr. Hansen has executed several independent technology performance verifications of emerging carbon, energy and transportation technologies, as CEO of 350Solutions, Director of Energy & Environment at Southern Research, and Director of the U.S. EPA's Greenhouse Gas Technology Center. Mr. Hansen has completed clean technology evaluations for the Department of Defense, state energy agencies, commercial clients, investors, and technology developers, involving evaluation of commercial feasibility, economic and environmental impacts, and technology

performance. Mr. Hansen served as the Measurement and Verification Program Lead for the NRG COSIA Carbon XPrize – a $20M prize competition for technologies that capture and beneficially utilize CO2. Mr. Hansen also served as U.S. Technical Expert for the development and implementation of ISO 14034 – Environmental Technology Verification, an international standard, issued in 2016

Lily Schacht

Carbon Removal Verification Engineer, 350Solutions

EDUCATION:

MS, Environmental Engineering, University of Wisconsin – Madison, 2019

BS, Chemical, Energy, and Environmental Engineering, Washington University in St. Louis, 2017

EXPERIENCE SUMMARY:

Lily Schacht is an Environmental and Chemical Engineer with experience in process engineering, environmental chemistry, analytical methods, and life cycle analysis (LCA). At 350Solutions, Lily works on verifying carbon dioxide removal (CDR) technologies, with a focus on mineralization-based pathways, including enhanced weathering, direct air capture, and ocean alkalinity enhancement. Previously, Lily led agronomic research at an enhanced weathering CDR supplier where she organized field trials across multiple states to quantify carbon removal and crop yield changes after rock application. Before that, Lily developed rapid prototyping instrumentation to optimize a biomineralization process in concrete production and aided in scaling up the process to pilot-scale. Lily also built environmental impact models for process variable sensitivity analysis of demo-scale manufacturing processes. These models were used to drive the direction of research and development to minimize product life cycle impacts. Throughout her career, Lily has developed analytical chemistry methodologies for both liquid- and solid-phase analyses.

RESEARCH AND PROFESSIONAL EXPERIENCE:

March 2024 – Present: Carbon Removal Verification Engineer, 350Solutions

Verify CDR technologies on behalf of registries and the XPRIZE Carbon Removal challenge. Specializes in mineralization pathways, including mineralization kinetics, measurement methods, and open-system modeling.

Nov 2022 – Feb 2024: Researcher, Lithos Carbon

Quantified carbon removal rates and agronomic impacts of enhanced weathering on cropland across six US states; Evaluated chemical analysis methods for precision relative to cost.

Nov 2023 – Jan 2024: Independent Consultant, Keel Labs

Built an environmental impact model to evaluate potential material and process changes; Recommended areas for reducing material usage up to 80%

Dec 2020 – Oct 2022: Research Scientist II, Biomason

Guided experimentation and data analysis throughout all R&D teams to inform techno-economic analysis (TEA) and LCA; built and led the carbonate biomineralization prototyping workstream for rapid iteration; developed real-time measurement techniques for critical process parameters in solid state

SELECTED PUBLICATIONS & PRESENTATIONS:

Schacht, L., Baum, M., Liu, H., & Yap, M. (2023) Scaling Enhanced Rock Weathering: Agronomic Impacts at Field-Scale [Abstract]. ASA, CSSA, SSSA International Annual Meeting, St. Louis, MO.

Schacht, L. and Ginder-Vogel, M. Arsenite Depletion by Manganese Oxides: A Case Study on the Limitations of Observed First Order Rate Constants. Soil Syst. 2018, 2(3), 39. https://doi.org/10.3390/soilsystems2030039