Isometric Standard Project Verification Report

For

Charm Industrial

Client	Isometric
Company / GHG Removal Supplier	Charm Industrial
Facility or Project Name	Charm Bio-oil Geologic Storage
Facility Address	**Bio-oil Production:** AE Cote-Nord Canada Bioenergy Inc (AECN) Port Cartier, Quebec, Canada **Bio-oil Injection:** Charm Industrial Evangeline Parish, LA, USA
Greenhouse Gas Statement ID/Gas Statement Version ID	ggs_1KKD2V7PJ1S0HJ4Q gss_1KKD2XSFW1S0JRY2
Net Greenhouse Gas Removals	764.14 tonnes CO_{2e}
Removal Method	Bio-oil Geological Storage
Removal Period	01FEB – 02MAR2026
Verification Opinion	Positive (fully meets criteria)
Verifier/Validation and Verification Body	Tim Hansen Bill Chatterton 350Solutions, Inc.

ISSUED:

MARCH 18, 2026

CONTENTS

1. Key Project Data 3
1.1. Verification Summary 4
2. Verification & Storage Site Validation Details 6
2.1. Verification Objectives 6
2.2. Responsibilities 6
2.3. Level of Assurance & Materiality 6
2.4. Verification Team Details 6
2.5. Audit Process Followed 6
3. Technical Aspects 7
3.1. Project Details 7
3.2. Protocols and Modules Applied 8
3.3. Applicability of Applied Protocol and Modules 8
3.4. Project Boundary 8
3.5. Changes from Previous Verifications 8
3.6. Process & Data Irregularities & Required Exemptions During Reporting Period ... 9
4. Crediting Details 10
4.1. Project Reporting Period 10
4.2. Crediting Period 10
5. GHG Statement Verification & Storage Site Validation 10
5.1. Accuracy of the Statement 10
5.2. Verification Storage Site Validation Opinion 11
5.3. Verification & Storage Site Validation Results Summary 11
5.4. Verification & Storage Site Validation Findings 13
5.4.1. Critical Findings and Exceptions 13
5.4.2. Forward Action Requests & Recommendations 14
6. Revision History 15
Appendix 1: Documents Submitted for Review 17
Appendix 2: Verification Audit Findings and Responses 27
Appendix 3: Verifier Qualifications 29

ISOMETRIC STANDARD VERIFICATION REPORT		
Company: Charm Industrial	Company Contact: *Max Lavine	Validation and Verification Team: *Tim Hansen, PE Bill Chatterton
Removal Method: Bio-oil Geological Storage		
Report Date: March 17, 2026		
Document No: 350VR-Charm-ISO2606.02		
Rev: v1.1		

** Primary contact/lead author*

1. KEY PROJECT DATA

TABLE 1. VERIFICATION SUMMARY FOR CHARM INDUSTRIAL BIO-OIL STORAGE

Title	Charm Bio-Oil Geologic Storage
Location	Bio-oil Production: AE Cote-Nord Canada Bioenergy Inc (AECN) @ Produits Forestiers Arbec S.E.N.C., 175 Bd du Portage des Mousses Port-Cartier, QC G0W 1X0, Canada 50.025323, -66.818910 Bio-oil Injection & Storage: Charm Industrial (Basco Injection site) Evangeline Parish, LA 30.916251, -92.297908
Reporting Period	February 1 – March 2, 2026
Greenhouse Gas Statement ID	ggs_1KKD2V7PJ1S0HJ4Q gss_1KKD2XSFW1S0JRY2
Project Proponents	CDR Supplier: Charm Industrial Feedstock Supplier: Produits Forestiers Arbec S.E.N.C (Quebec mill waste supplier); Altitude Forestry (CO forestry fire prevention waste supplier) Geologic Storage Management: Charm Industrial Salt Cavern Storage Management (Prior Injections): Vaulted Deep Regulatory Agency (Injections / Storage): Louisiana Department of Energy & Natural Resources; Kansas Department of Health & Environment (KDHE) (Prior Injections)
Legal Ownership of the Credits	Charm Industrial
Removals in Reporting Period	764.14 tonnes
Removal Method	Bio-oil Geological Storage
Verification Report Date	March 17, 2026
Verification Type & Criteria	Isometric Standard Verification for ongoing deliveries of carbon removal credits by Charm Industrial in accordance with the documents used during project validation: • Isometric Standard v1.8 • Bio-oil Geological Storage Protocol v1.1 • Biomass Feedstock Accounting Module v1.2 • Bio-oil Storage in Permeable Reservoirs v1.1 • Embodied Emissions Accounting v1.0

	• Energy Use Accounting v1.2 • Transportation Emissions Accounting v1.1

1.1. VERIFICATION SUMMARY

350Solutions was contracted to perform a project verification of the greenhouse gas (GHG) statement of Charm Industrial's bio-oil geological storage process for the referenced reporting period. The validation report for the Charm Kansas Bio-oil Geologic Storage project was completed on June 25, 2024, by Futurepast, which focused on the use of third-party produced bio-oils and was issued by Isometric for the Crediting Period March 1, 2024 – February 28, 2029. An additional validation of the Charm Bio-oil Geologic Storage project for use of bio-oil produced by Charm was completed on October 18, 2024, for the same crediting period. These validations remain valid for this verification reporting period. Further details and findings can be found in the validation report (https://registry.isometric.com/project/prj_1HZSSWBQM1S08H83#project-documentation). Validation of an additional injection and storage location in Evangeline Parish, Louisiana was completed in September 2025 and is the injection and storage site for all injections during this reporting period. This storage site validation is included in the report located here: https://storage.googleapis.com/isometric--production--eu--public-documents/spl_1H31MW3T81S0R67B/prj_1HZSSWBQM1S08H83/pjd_1K5XPX61T1S0TM0Z/verification_report.pdf.

350Solutions affirms that Charm has the appropriate equipment, procedures, and protocols in place and is documented to quantify GHG removal through the injection of bio-oil into permeable reservoirs via a permitted Class V well in accordance with the requirements of the applicable Isometric standards, protocols and modules.

The carbon removals for the reporting period are provided in Table 2. These values have been verified by 350Solutions.

TABLE 2. VERIFIED TOTAL REMOVALS BY CHARM INDUSTRIAL FOR REPORTING PERIOD ENDING MARCH 2, 2026

Removal ID	Date removal started	Date removal completed	CO_2e net removed (kg)
rmv_1KJTBJZ141S0704B	2026-02-18	2026-02-18	31610
rmv_1KJTYHFB81S03FRT	2026-03-01	2026-03-01	26850
rmv_1KJTAKY7P1S05YTB	2026-02-25	2026-02-25	30320
rmv_1KJDX6DNG1S0A29R	2026-02-24	2026-02-24	27430
rmv_1KJTXHBT21S0GZJS	2026-02-26	2026-02-26	32520
rmv_1KJ66ZQDK1S0Y7F3	2026-02-20	2026-02-20	27560
rmv_1KJTYZ2H41S0HGWM	2026-03-01	2026-03-01	24980
rmv_1KJDWYSQT1S04K20	2026-02-23	2026-02-23	27410
rmv_1KJTY27M71S0JNJ8	2026-03-01	2026-03-01	27340
rmv_1KJDXMBAP1S0N0S8	2026-02-25	2026-02-25	24800
rmv_1KJZC9RK61S0DGH9	2026-02-25	2026-02-25	31110
rmv_1KJTX1FXT1S0TM5Z	2026-02-26	2026-02-26	31310
rmv_1KJ5VF7H91S0NMTQ	2026-02-12	2026-02-12	25990

rmv_1KHYG84841S0PV28	2026-02-11	2026-02-11	26650
rmv_1KJDXWA011S0NEKZ	2026-02-25	2026-02-25	27270
rmv_1KJTB7YEQ1S0HWW9	2026-02-19	2026-02-19	28720
rmv_1KHYG0R6T1S0YRFS	2026-02-10	2026-02-10	27550
rmv_1KHYFS9EA1S0ZHED	2026-02-09	2026-02-09	26590
rmv_1KJT9YMYX1S0EYR2	2026-02-21	2026-02-21	5290
rmv_1KJ66R41Z1S0K0SE	2026-02-16	2026-02-16	23550
rmv_1KJTYRDN41S0M2CA	2026-03-01	2026-03-01	26570
rmv_1KJDXD3691S0FHHG	2026-02-24	2026-02-24	26210
rmv_1KJTYA3BN1S0JCCV	2026-03-01	2026-03-01	27020
rmv_1KJTZC0PZ1S0J5B5	2026-03-02	2026-03-02	25880
rmv_1KJTAZKZM1S06WE9	2026-02-25	2026-02-25	24420
rmv_1KJTX7Y691S0W2JC	2026-02-26	2026-02-26	26200
rmv_1KJTXTF961S0GPDC	2026-02-28	2026-02-28	11910
rmv_1KJTZ5QMM1S09XZX	2026-03-02	2026-03-02	26460
rmv_1KJ5VPNM61S0AYAE	2026-02-12	2026-02-12	26510
rmv_1KJZD4T7Z1S0XVXW	2026-02-25	2026-02-25	8110
TOTAL REMOVALS			764140

The quantity of **764.14 tonnes** of net carbon removals has been verified with a reasonable level of assurance and is eligible for crediting under the referenced Isometric Standard and Protocol.

350Solutions Inc. declares that it is an impartial verification body, approved by Isometric for verifications in the required technical area, free from any conflicts of interest, capable, and qualified to complete this verification for the current reporting period according to the *Isometric Standard v1.8, Bio-oil Geological Storage Protocol v1.1, Biomass Feedstock Accounting Module v1.2.1*, *Bio-oil Storage in Permeable Reservoirs Module v1.1, Embodied Emissions Accounting v1.0, Transportation Emissions Accounting v1.1,* and *Energy Use Accounting v1.2*.

Verifier Information		
Verification Body	**Verifier**	**Verification ID No.**
350Solutions, Inc.	Tim Hansen	VR-Charm-ISO2606.02

Timothy A. Hansen Digitally signed by Timothy A. Hansen Date: 2026.03.18 11:48:44 -04'00'

Signed: Tim Hansen (Verifier)

Bill Chatterton Digitally signed by Bill Chatterton Date: 2026.03.18 11:49:01 -04'00'

Bill Chatterton (QA)

2. VERIFICATION & STORAGE SITE VALIDATION DETAILS

2.1. VERIFICATION OBJECTIVES

A series of verification activities was conducted by 350Solutions to independently verify the claimed removals of the GHG statement submitted by Charm Industrial for operations conducted at the Charm Bio-oil Geologic Storage facility for the referenced Reporting Period. The verification was conducted following the specifications of the standards and protocols cited in Table 1.

2.2. RESPONSIBILITIES

The verification is based on the provision and fair presentation of a complete and accurate GHG Statement submitted by Charm Industrial to the Isometric registry. It is Charm's responsibility to ensure a fair, accurate, and complete presentation of the GHG Statement and Project Design Document are provided. This is confirmed and verified independently by 350Solutions based on supporting evidence in accordance with the Isometric criteria (Table 1, Section 3.2).

2.3. LEVEL OF ASSURANCE & MATERIALITY

The verification was conducted with a reasonable level of assurance. Any discrepancies between the claimed removals of the project and the removals estimated by the verification process for the reporting period are less than the materiality threshold of 5%.

2.4. VERIFICATION TEAM DETAILS

350Solutions is an accredited inspection & verification body by ANAB under ISO 17020:2012 for completion of ISO 14034:2016 Technology Verifications. 350Solutions is headquartered in Raleigh, North Carolina, USA. 350Solutions Technical Lead for the Charm verification is Tim Hansen. Mr. Hansen is a registered Professional Engineer with over 25 years of experience in the evaluation and verification of novel cleantech and carbon technologies. Mr. Hansen has led verifications of carbon removal technologies for multiple registries, including Isometric, and has experience in the development and testing of biomass conversion technologies, including gasification and pyrolysis. The verification report was provided QA by Bill Chatterton, a Carbon Removal Verification Engineer, with experience developing and verifying carbon removal technologies, MRV processes, and LCAs.

2.5. AUDIT PROCESS FOLLOWED

The specific verification and storage site validation activities conducted are summarized in Table 3. The list of all files that were reviewed is provided in Appendix 1. The list of findings from the verification can be found in Appendix 2. Audit results are documented using 350's Compliance Checklist, which includes all requirements from the Isometric standard, Bio-oil Geologic Storage protocol, and referenced modules.

TABLE 3. VERIFICATION & STORAGE SITE VALIDATION ACTIVITIES

Date(s)	Verification Activity	Verification Tasks	Documents Reviewed
March 16-17, 2026	Review of reporting period modifications and changes	• Review of GHG Statement and report and guidance from Charm	Final V 1.11 Charm Industrial Bio Oil Geologic Storage PDD + Biochar ggs_1KKD2V7PJ1S0HJ4Q gss_1KKD2XSFW1S0JRY2 Feb 1 – Mar 2 Removals Isometric GHG Statement Report v1.6 Feb-March 2026 VVB Guidance
March 16-17, 2026	Review of current Validation and GHG Statement Applicability	• Review of Validation Report • Review of prior Verification Report and findings • Identification of major and minor process steps, measurements, and calculations and changes in RP • Review of Standards/Protocols/Modules required for Verification • Generation of a checklist of verification issues and findings and opportunities for improvement	Validation_Report_for_Isometric_Charm_Industrial_Bio-Oil_Project_2024-06-25_r1 Isometric Standard Project Verification & Storage Site Validation Report For Charm Industrial (23Sep2025) Final V 1.11 Charm Industrial Bio Oil Geologic Storage PDD + Biochar ggs_1KKD2V7PJ1S0HJ4Q gss_1KKD2XSFW1S0JRY2 Feb 1 – Mar 2 Removals Isometric GHG Statement Report v1.6 Feb-March 2026 VVB Guidance Isometric Standard v1.8, Bio-oil Geological Storage Protocol v1.1, Biomass Feedstock Accounting Module v1.2, Bio-oil Storage in Permeable Reservoirs Module v1.1, Embodied Emissions Accounting v1.0, Transportation Emissions Accounting v1.1, and Energy Use Accounting v1.2
March 16-17, 2026	Verification of Removals	• Verify changes to the system • Review of measurements and calculations • Review of durability/permit requirement monitoring data • Review of GHG statement • Identification of initial findings and follow-up request for information • Write verification report • Internal Quality Assurance	File List provided in Appendix 1. Initial Findings in Appendix 2. Primary verification performed using Isometric Certify and supporting documentation

3. TECHNICAL ASPECTS

3.1. PROJECT DETAILS

Charm obtained bio-oil from a single source during this reporting period. Charm obtains bio-oil from a producer in Quebec, Canada (AECN) who uses an Ensyn/Honeywell UOP pyrolysis system to generate bio-oil from waste wood produced at a neighboring mill.

Bio-oil from AECN is shipped by tanker truck, rail car, or tote tanks on flatbed to Charm's underground injection and storage facility located in Evangeline Parish, Louisiana for storage into a geologic reservoir. At this facility, Charm pretreats the bio-oil via air sparging and any other adjustments to ensure bio-oil and aqueous products meet the requirements of the injection facility permit for storage in permeable reservoirs as specified by the Louisiana Department of Energy & Natural Resources (LDENR).

The bio-oil products are blended in on site storage tanks through recirculating pumps and injected as soon as practicable. Samples of the blended bio-oil are collected prior to injection and analyzed for bio-

oil characteristics to ensure compliance with permit requirements. Charm also monitors all injection parameters as required by the Underground Injection Control (UIC) permit.

3.2. PROTOCOLS AND MODULES APPLIED

The verification was conducted following the specifications of the following standards, protocols, and modules:

- Isometric Standard v1.8 [1]
- Bio-oil Geological Storage Protocol v1.1 [2]
- Biomass Feedstock Accounting Module v1.2 [3]
- Bio-oil Storage in Permeable Reservoirs v1.1 [4]
- Embodied Emissions Accounting v1.0 [5]
- Energy Use Accounting v1.2 [6]
- Transportation Emissions Accounting v1.1 [7]

Charm utilizes Book and Claim Units (BCUs) to substitute for some, or all, of project diesel fuel usage and purchases Renewable Energy Certificates (RECs) for some, or all, of its electricity consumption in accordance with the Isometric Energy Use and Transportation Modules.

3.3. APPLICABILITY OF APPLIED PROTOCOL AND MODULES

The Charm project takes mixed woody waste or forestry thinnings from wildfire prevention activities, converts it to bio-oil, which they pretreat and inject into geologic storage formations. The biomass feedstocks were assessed previously under the eligibility criteria of the Isometric Biomass Feedstock Module and were found to be eligible. As the biomass feedstocks have been validated as eligible biomass feedstocks, the storage of biomass conversion products (bio-oil) in a geologic formation makes both the Bio-oil Geological Storage Protocol and Bio-oil Storage in Permeable Reservoirs Module applicable to this project. All other modules for energy, transportation, and embodied emissions accounting are generally applicable to this project.

3.4. PROJECT BOUNDARY

The boundaries of the project include the supply of wood waste to the biomass processing site, the conversion of the biomass to bio-oil via AECN's pyrolysis process, transport of the bio-oil to Charm, completion of pretreatment, and injection of the bio-oil in the geologic reservoir. Monitoring and required analysis of the bio-oil and the storage formation are also included in the project boundary.

3.5. CHANGES FROM PREVIOUS VERIFICATIONS

Compared to the prior verification, some significant and some minor modifications were made to the Charm Industrial processes, data collection, and calculation procedures which have been specified in the GHG statement and supporting documentation. The following modifications and notes have been provided for clarity. All were reviewed and deemed acceptable under the Isometric requirements:

- Charm has modified injectate mass calculation to provide a conservative calculation when data from two different sources may provide slightly different results. The Total Injectate Mass reported by Charm uses the difference between loaded and unloaded scale tickets **or** the originating BOL mass, whichever is lower. This methodology has been reviewed and approved by Isometric.

- A small spill of bio-oil, which was cleaned and mostly recovered, and a tanker cleanout procedure resulted in small losses of bio-oil, which were properly calculated and accounted for in total injectate mass determination
- Charm has implemented an "Inventory Reconciliation" process which is included in the site emissions netted against gross removals. This represents the total outstanding bio-oil production emissions from Charm's bio-oil production in 2025. This is a result of comparing the total bio-oil production for a period vs the total bio-oil shipped from the facility for injection. For any Production Period that 1) Shows a positive quantity of bio-oil outstanding and 2) Has no more physical inventory on site, the outstanding quantity of oil is multiplied by the appropriate carbon intensity for the production period and oil type to quantify an "inventory reconciliation emission" that ensures all allocated emissions are accounted for. A small quantity of these reconciled production emissions was included in this reporting period.
- An air permit was required and secured for the site for the operation of the new sparging system. Charm has provided all information regarding the permit and compliance.
- The Kansas pre-treatment site decommissioning and equipment relocation, disposal, or return to rental companies has continued during this reporting period.
- BCUs were utilized to offset some of the new emissions associated with site construction, and equipment shipping, in addition to the typical usage for offsetting transportation diesel use.
- There are no emissions associated with Charm production of bio-oil this period, as no Charm oil was injected this period.
- Requirements for monitoring records for prior injections at the Vaulted facility and the required monitoring frequency and submission timing are under discussion with Isometric as operations are moving to a post-injection monitoring plan and approach. Isometric has approved a delay in obtaining and submitting monitoring data for the Vaulted site during this transition period as all parties modify contractual requirements for ongoing monitoring and reporting.
- Note that Charm is continuing to transition additional parts of its reporting to the Isometric Certify platform. As this occurs, certain components may appear partially complete or incomplete in Certify. However, the data has been submitted separately from Certify and verified by 350 as compliant. For this reporting period, Monitoring and Feedstocks requirements are included in Certify, but entries appear incomplete. However, these items are fully addressed outside of Certify.

3.6. PROCESS & DATA IRREGULARITIES & REQUIRED EXEMPTIONS DURING REPORTING PERIOD

One exemption to protocol requirements was provided by Isometric during this reporting period, as follows:

- Charm engaged a contractor to conduct wellhead gas testing as required every 6 months by the Isometric Protocol. The contractor performed the test and found no fugitive leaks at the wellhead. However, the test was carried out with reference to requirements from the US DOI Orphaned Wells Program Office, not the Isometric Protocol. As a result, the required monitoring for CO_2 and VOCs was not completed, only methane. Charm has contracted another entity to complete this required testing and will submit results with the next reporting period. Isometric has approved this as an exception to the protocol requirement for this reporting period.

It should be noted that the ongoing monitoring required for prior injections at the salt cavern storage site in Kansas (Vaulted Deep) continues to be completed. However, the reporting schedule and verification requirements for such monitoring are under discussion with Isometric and will be completed at a future date. It is also not relevant to the crediting associated with the current reporting period injections. Monitoring report timing and verification requirements for these prior injections are being developed with Isometric.

4. CREDITING DETAILS

4.1. PROJECT REPORTING PERIOD

This verification considers injections of bio-oil (oil and aqueous phases) by Charm during the period February 1 – March 2, 2026. The reporting period is based on the actual injection dates, with bio-oil production, transportation, monitoring, and related activities potentially occurring outside of this reporting period but properly accounted for and allocated to the bio-oil injected within the reporting period.

4.2. CREDITING PERIOD

The 5-year crediting period for the Charm Kansas Bio-oil Geologic Sequestration Project began March 1, 2024, and continues for five years, ending February 28, 2029. All claimed removals in this reporting period fall within the current crediting period.

5. GHG STATEMENT VERIFICATION & STORAGE SITE VALIDATION

5.1. ACCURACY OF THE STATEMENT

Confirmation of the GHG statement has been based on the following efforts:

- Review and confirmation of calculations of total bio-oil and CO_2 equivalent injected and all process, operational, and embodied emissions, as well as all supporting evidence for the following removals:

Removal ID	Date Removal Started
rmv_1KJTBJZ141S0704B	2/26/2026
rmv_1KJZD4T7Z1S0XVXW	2/25/2026
rmv_1KJTXTF961S0GPDC	2/28/2026

- This includes for these removals:
    - Calculation of mass of bio-oil delivered and injected including tracing to raw data (weigh scale tickets, carbon content lab results, addition of consumables)
    - Confirmation of transportation distances for tanker and rail car deliveries from AECN to to Basco site, LA, emission factors, and calculation of transportation emissions

  - Confirmation of weigh scale raw data for deliveries of bio-oil and injectate
  - Confirmation of raw data for fuel usage at Charm injection facilities
  - Confirmation of electricity usage at Charm and injection facilities
  - Confirmation of proper use and accounting of BCUs and RECs to offset diesel and electricity usage emissions, respectively
  - Confirmation of embodied emissions for added equipment during the reporting period
- Review of monitoring data as required for Basco site injection (monthly and quarterly reports) and post injection monitoring to ensure compliance with Class V permit for Basco site
- Review of updated stakeholder engagement activities and grievance log

5.2. VERIFICATION STORAGE SITE VALIDATION OPINION

350Solutions has reviewed the documentation of the technology, the instrumentation, the procedures, performance and collected data and has found that the data presented in the greenhouse gas removal statement indicates that the claims fall within the 5% materiality threshold for greenhouse gas emissions and removals as required by the Isometric Standard:

☒ ***Meets the requirements of the Isometric Standard v1.8, Biomass Geological Storage Protocol v1.1, Biomass Feedstock Accounting Module v1.2, and Bio-oil Storage in Permeable Reservoirs Module v1.1 for Verification***

☐ ***Meets the requirements with minor revisions of Isometric Standard v1.8, Biomass Geological Storage Protocol v1.1, Biomass Feedstock Accounting Module v1.2, and Biomass or Bio-oil Storage in Salt Caverns Module v1.1 for Verification***

☐ ***Does Not Meet the requirements of the Isometric Standard v1.8, Biomass Geological Storage Protocol v1.1, Biomass Feedstock Accounting Module v1.2, and Biomass or Bio-oil Storage in Salt Caverns Module v1.1 for Verification***

5.3. VERIFICATION & STORAGE SITE VALIDATION RESULTS SUMMARY

A summary of verification results and compliance with relevant requirements of the *Isometric Standard, Biomass Geological Storage Protocol, Biomass Feedstock Accounting Module*, and *Bio-oil Storage in Permeable Reservoirs Module* are summarized below.

TABLE 4. VERIFICATION RESULTS SUMMARY

Isometric Standard Section Ref.	Verification Topic	Changed since Project Validation? (Y/N)	Final Findings
2.1.	*Validated against approved Protocols*	N	Acceptable – No additional changes since validation
2.5.1	*Boundaries*	N	Acceptable – No additional changes since validation
2.5.2	*Baseline*	N	Acceptable – No change since validation
2.5.3	*Additionality - Financial*	N	Acceptable – No change since validation
2.5.3	*Additionality – Environmental*	N	Acceptable – No change since validation
2.5.3	*Additionality – Regulatory*	N	Acceptable – No change since validation

Isometric Standard Section Ref.	Verification Topic	Changed since Project Validation? (Y/N)	Final Findings
2.5.4	*Leakage*	N	Acceptable – No change since validation and prior verification.
2.5.5	*Default Emission Factors, Proxies, and Models*	N	Acceptable – No additional significant changes were made since prior verifications. See Section 3.5 for summary of modifications to any calculation methods, all of which are acceptable.
2.5.11	*Life Cycle Assessment (LCA) Policies*	N	
2.5.6	*Common Calculation Factors*	N	
2.5.7	*Uncertainty*	N	
2.5.8	*Durability and Monitoring*	Y	All updated durability evidence and storage monitoring requirements validated to meet protocol requirements. Note that ongoing discussions with Isometric and Charm are occurring regarding frequency of Kansas storage site monitoring reports as the prior injections transition into a post-injection / closure monitoring phase with no Charm injections occurring.
2.5.9	*Risk of Reversal*	N	Acceptable – No additional changes since validation
2.5.10 ***3.7***	*Environmental and Socioeconomic Impacts*	N	Acceptable – No additional changes since validation.
3.1	*Ownership*	N	Acceptable – No change since validation
3.2	*Documentation*	Y	Acceptable – No additional changes since prior verification. All documentation properly updated for reporting period
3.3	*Eligibility*	Y (GHG Statement Updated)	Acceptable – Project registered with Isometric and reporting period GHG Statement properly submitted to Isometric dMRV Certify platform.
3.4	*Project Crediting*	Y (GHG Statement Updated)	Acceptable – New reporting period GHG Statement is complete and verified. Reporting period is within current validation crediting period.
3.5	*Stakeholder Input Process*	N	Acceptable – No changes since prior verification
3.6	*Regulatory Compliance*	Y (Required Monitoring Updated)	Required monitoring and reporting completed during reporting period. No additional compliance issues identified for injections during period.
Biomass Feedstock Accounting Module			
2.1	*Eligibility Criteria for Market Leakage*	N	Acceptable – No change since prior feedstock validations
2.2	*Counterfactual Storage Eligibility*	N	Acceptable – No change since prior feedstock validations
2.3	*Dedicated Energy Feedstock Eligibility*	N	Acceptable – No change since prior feedstock validations
3.0	*Counterfactual Definition*	N	Acceptable – No change since prior feedstock validations
3.1	*Counterfactual Energy Definition*	N	Acceptable – No change since prior feedstock validations
3.2	*Counterfactual Replacement Definition*	N	Acceptable – No change since prior feedstock validations

TABLE 5. BASCO STORAGE SITE VERIFICATION SUMMARY

Isometric Standard Section Ref.	Verification Topic	Changed since Project Validation? (Y/N)	Final Findings
Bio-oil Storage in Permeable Reservoirs Module			
1.0	*Storage System Eligibility*	N	Acceptable – No change since validation
2.1	*Storage Reservoir – Permitting*	N	Acceptable – No change since validation
2.2	*Storage Reservoir – Capacity*	N	Acceptable – No change since validation
2.2	*Storage Reservoir – Integrity*	N	Acceptable – No change since validation
2.2	*Storage Reservoir – Integrity: Characterization*	N	Acceptable – No change since validation. Well maintenance and an additional Mechanical Integrity Test were completed during the reporting period which met all criteria.
2.2	*Storage Reservoir Characterization – Temperature, pH, conductivity, density*	N	Acceptable – No change since validation
2.2	*Storage Reservoir Characterization – $d^{13}C$ analysis (where applicable)*	NA	Acceptable – Not required
2.3	*Storage Reservoir Integrity – Well Construction*	N	Acceptable – No change since validation
3.1.1	*Storage Reservoir Integrity – Injection operations*	Y	Acceptable – Updated monitoring data provided indicating no exceedances of permit limits
3.1.1	*Storage Reservoir Integrity – Injection operations – Sampling & Analysis*	Y	Acceptable – Updated sampling and analytical data provided indicating no exceedances of permit limits
1.0, 3.2	*Well Closure and Post Closure Requirements*	N	Acceptable – No change since validation
3.1.3	*Injection Pressure*	Y	Acceptable – Pressure is continuously monitored and reported quarterly (monitoring reports indicate full compliance)
3.1.2	*Mechanical Integrity*	N	Acceptable – No change since prior verification
3.1.3	*Volatile Gas Monitoring*	N	Acceptable – No change since validation
3.1.3	*Reversal Risk & Monitoring*	N	Acceptable – No change since validation
3.3.1	*Attribution of Reversals*	N	Acceptable – No change since validation

5.4. VERIFICATION & STORAGE SITE VALIDATION FINDINGS

5.4.1. CRITICAL FINDINGS AND EXCEPTIONS

Assessment of the greenhouse gas removal statement identified a few minor findings and non-material data issues (see Appendix 2). No significant findings that materially impacted the verified net carbon removals nor compliance with protocol standard were identified. One non-conformity was identified, but was approved as an exemption by Isometric for this Reporting Period and modified to a Forward Action Request (FAR) (see 3.6 and Table 6 ID ISS-11). All findings, primarily clarifications and minor data errors, have been addressed and closed.

5.4.2. FORWARD ACTION REQUESTS & RECOMMENDATIONS

Forward action requests (FAR) and recommendations are also provided in Appendix 2 for consideration for improvement of future operations and GHG Removal Credit calculations and to ensure tracking of potential issues to be monitored by verifiers in future verifications. Open FARs and opportunities for improvement are summarized below for future verification reference:

TABLE 6. FORWARD ACTION REQUESTS AND RECOMMENDATIONS

ID No	Type	Finding / Issue	Supplier Response	Conclusion / Resolution
NA	FAR	The Q4 2025 injection report would be due Jan 30. We see the Q3 report but not Q4. Can you please provide a copy?	The Q4 injection report is the "annual report" for the year. Louisiana Department of Conservation and Energy (LDCE) circulated a notice that this report is now due by May 31st 2026. A screenshot of the email notice has been added to the "Basco MRV" file as documentation LDCE Annual Reporting Deadline Notice.png	Complete. Quarterly report provided
NA	FAR	Will there be an updated emission factor for AECN process emissions soon? And, will Charm be doing the full annual emission factor review in March 2026?	Yes, there will be an updated AECN process emissions factor for 2026. All injections during this reporting period were from 2025, so it was not applied. All other emission factors will be updated for March 2026, so those values will be reflected starting when March injections are reported for verification this year.	Acceptable - noted as a FAR for next RP.
ISS-11	FAR	Charm engaged Guardian Plug and Abandonment to conduct wellhead gas testing as required every 6 months by the Isometric Protocol. The contractor performed the test and found no fugitive leaks at the wellhead. However, as acknowledged by Charm the Isometric protocol also requires testing for CO2 and VOC, which was not completed within the 6 month test period. Charm notes that an additional contractor was hired to complete the CO2 and VOC testing and results will be included in the next Reporting Period.	[Isometric response] Isometric confirm making this request a FAR. There's clear intention and a timeline to obtain the data, and the outcome of the data being 'bad' would be indicative of a reversal which signifies an issue with *all* credits stored in that storage site, not just the credits from the latest verification activity.	Accepted as exemption for this Reporting Period. Confirm testing complete next Reporting Period.

ISS-14	FAR	Although the air permit may not require monitoring of thermal oxidizer during operation, we would prefer to see evidence that the oxidizer is being operated properly in the future. Can you clarify if oxidizer operational monitoring is done (i.e. temperature logging)	That should not be a problem. This request has been submitted to injection ops for review so we can identify how best to pull and report on this data going forward.	Acceptable. Review in next reporting period
NA	FAR (prior)	With injections no longer occurring at Vaulted, we would like to know how Charm will be notified of closure of the cavern where Charm oil was last injected, and to ensure that Charm will now be obtaining and submitting any post closure monitoring data to Isometric as part of the continued monitoring requirements. Please clarify that plans are in place for this and will be ongoing.	Charm has reached out to Vaulted on multiple occasions to get clarity regarding their future plans for the AR-09 injection well. The well still has considerable capacity and is the property of Vaulted, so it is up to them whether they plug and abandon the well or use it for their own emplacements. This decision on their part will affect the nature of the post-closure monitoring plan. We will continue to request clarity regarding these plans and, once received, we will define and submit a monitoring plan in light of the information we receive.	Verifier to review guidance and requirements from Isometric as ongoing discussions and post-closure monitoring plan requirements are evaluated with Isometric and Charm. Provide post-closure monitoring plan in near future as injections have now transitioned from Vaulted to the Basco facility.
NA	FAR (prior)	With injections no longer occurring at Vaulted, please provide updated contract for post-emplacement / post-closure management and monitoring and post-closure monitoring plan that documents how Charm will be notified of closure of the cavern where Charm oil was last injected, and to ensure that Charm will now be obtaining and submitting any post closure monitoring data to Isometric as part of the continued monitoring requirements or this storage location		Verifier to review guidance and requirements from Isometric for post-closure monitoring plan requirements are evaluated with Isometric and Charm. Charm to provide evidence of contractual agreement with Vaulted regarding post-closure monitoring and responsibilities.

6. REVISION HISTORY

Version	Date Issued	Noted Changes
v1.0 (Draft – Internal)	March 17, 2026	N/A Initial Version
v1.1 (Draft – External)	March 18, 2026	Minor edits from QA and Supplier
v1.2 (FINAL)	March 18, 2026	Final Version

References

[1] Isometric, “Isometric Standard v1.8.” [Online]. Available: https://registry.isometric.com/standard/1.8

[2] Isometric, “Bio-oil Geological Storage .1.1.” [Online]. Available: https://registry.isometric.com/protocol/bio-oil-geological-storage/1.1

[3] Isometric, “Biomass Feedstock Accounting .1.2.” [Online]. Available: https://registry.isometric.com/protocol/biomass-feedstock-accounting/1.2

[4] Isometric, “Biomass or Bio-oil Storage in Permeable Reservoirs v1.1.” https://registry.isometric.com/module/bio-oil-storage-in-permeable-reservoirs/1.1

[5] Isometric, “Embodied Emissions Accounting v1.0.” [Online]. Available: https://registry.isometric.com/protocol/embodied-emissions/1.0

[6] Isometric, “Energy Use Accounting v1.2.” [Online]. Available: https://registry.isometric.com/protocol/energy-use-accounting/1.2

[7] Isometric, “Transportation Emissions Accounting v1.1.” [Online]. Available: https://registry.isometric.com/protocol/transportation

See Appendix 1 and Table 3 for list of specific files reviewed during the verification.

APPENDIX 1: DOCUMENTS SUBMITTED FOR REVIEW

Name
src_1K31MHX8G1S038RS_Standard_Emission_Factors___Calculations__4_.xlsx
src_1K31MPMV51S0F34N_Standard_Emission_Factors___Calculations__4_.xlsx
src_1K36RC27E1S0S4W1_Production_Period_8_Summary.xlsx
src_1K370M1Z51S076JY_GLEC_NA_Fuel_Energy.png
src_1K371H3W11S0BQ7G_LA_Grid_Emissions.png
src_1K37244EA1S0DESA_LA_Water_Transport_Emissions.png
src_1K3729JS71S07WKT_GLEC_NA_Fuel_Energy.png
src_1K7J7C5MZ1S0HNWV_AECN_Process_Emissions_Calculation.xlsx
src_1K7J7C8Q71S0REVP_GLEC_NA_Road_Transport.png
src_1K7J7CB411S0NNRY_GLEC_NA_Road_Transport.png
src_1K7J7CFVH1S01G4T_Truck_Embodied_Emissions.png
src_1K7J7CHRD1S0B26D_Truck_Embodied_Emissions.png
src_1K7PQYDW91S0M21C_Screenshot_2025-10-15_at_2.28.45_PM.png
src_1K9QNCQ481S0N6KS_Charm-A3-2024-10-24-63-1976.pdf
src_1KA4YJYCT1S0Z5SF_Charm-A3-2024-10-24-64-1976.pdf
src_1KC0C25N11S041A0_Charm-A5-2024-10-24-63-1976.pdf
src_1KGTC5B2K1S0TZKC_AECN_to_Basco.png
src_1KGTT0PNR1S0PM09_Charm_Industrial_Delta_Region_FH25_retirement-2026-01-06T13_45_40.pdf
src_1KHCM9AKM1S0SEKX_BOL__2286-T_1__1_.pdf
src_1KHCMW9EW1S0WVS1_2-123_Empty_Scale_Ticket.jpg
src_1KHCMWAQQ1S0GGMP_PXL_20260204_133333633__1_.jpg
src_1KHCMWBS91S045GB_BATCH_2-123__BATCH_2-124__BATCH_2-125_Gas_Oil__SR26-00993.pdf
src_1KHCQ0W7S1S01M0N_BOL_2287-T_2.1_.pdf
src_1KHCQA2MM1S0BBAN_Empty_Scale_Ticket.jpg
src_1KHCQA3JR1S0Z06A_BATCH_2-123__BATCH_2-124__BATCH_2-125_Gas_Oil__SR26-00993.pdf
src_1KHCQA44H1S0JN1Z_Full_Scale_Ticket.jpg
src_1KHCQNR5V1S0GTJD_BATCH_2-123__BATCH_2-124__BATCH_2-125_Gas_Oil__SR26-00993.pdf
src_1KHCQNS2T1S04FE2_Full_Scale_Ticket__1_.jpg
src_1KHCQNTN81S0R49Q_Empty_Scale_Ticket__1_.jpg
src_1KHYG17A81S0TGDH_BOL_2288-T_2.3.pdf
src_1KHYG1N961S0JNXR_BOL_2288-T_2.3.pdf
src_1KHYG7SQ61S0QBTQ_2-125_Ops_Notes__2_.xlsx
src_1KHYHX2751S0BKSG_2-123_Ops_Notes__4_.xlsx
src_1KJ5V7YZ01S0GSNB_BOL_2290-T_2.5.pdf
src_1KJ5V8CP71S0NA9X_BOL_2290-T_2.5.pdf
src_1KJ5VES7P1S0RYNY_2-126_Full__1_.jpg
src_1KJ5VETDS1S0KX8X_2-126_Empty__1_.jpg
src_1KJ5VEVGY1S07J4J_BATCH_2-126__BATCH_2-127__SR26-01147.pdf

src_1KJ5VEW3C1S0V707_2-126_Ops_Notes__1_.xlsx
src_1KJ5VFNCE1S0HXGY_BOL_2293-T_2.5.pdf
src_1KJ5VP6PV1S0GGFY_2-127_Full__1_.jpg
src_1KJ5VP8HG1S045BK_2-127_Empty__1_.jpg
src_1KJ5VPA4A1S0QT78_BATCH_2-126__BATCH_2-127__SR26-01147.pdf
src_1KJ5VPAYZ1S0BF2X_2-127_Ops_Notes__1_.xlsx
src_1KJ66GXTK1S0RYF0_BOL_2294-T_2.6.pdf
src_1KJ66QNRT1S0RJYY_Full_Scale_Ticket_2-128.jpg
src_1KJ66QQB01S0C7TK_Empty_Scale_Ticket_2-128.jpg
src_1KJ66QS741S0ZWP8_2-128_Ops_Notes.xlsx
src_1KJ66QST21S0KHHX_CHN_2-128___2-129.PDF
src_1KJ66RKG81S0VMM0_Envoi_des_documents_Camion_2295-T.pdf
src_1KJ66Z4YS1S03SMK_2-129_Full_Scale_Ticket.jpg
src_1KJ66Z62X1S0QEG8_2-129_Empty_Scale_Ticket.jpg
src_1KJ66Z81E1S0B3BX_2-129_Ops_Notes__1_.xlsx
src_1KJ66Z8W91S0YR7J_CHN_2-128___2-129.PDF
src_1KJ8MWVPR1S06HE0_2-124_Ops_Notes__2_.xlsx
src_1KJDC4X8T1S0GP74_BOL__2296-T.pdf
src_1KJDCBRNR1S016FZ_2-131_Ops_Notes__1_.xlsx
src_1KJDCBS871S0MVBM_2-131_Empty_Scale_Ticket.jpg
src_1KJDCBT171S08G79_2-131_Full_Scale_Ticket.jpg
src_1KJDCBVAT1S0W52Y_BOL__2296-T.pdf
src_1KJDCBWKV1S0FSYK_CHN_2-130___2-131.PDF
src_1KJDCJ8ZP1S0WJXN_CHN_2-130___2-131.PDF
src_1KJDCJAT91S0G7SA_2-130R_Empty_Ticket.jpg
src_1KJDCJC0M1S03WMZ_2-130R_Full_Ticket_.jpg
src_1KJDCJDFP1S0QHGM_2-130_Ops_Notes_Rail.xlsx
src_1KJDWQT8B1S0AGQJ_Billing_Documents_2297-T.pdf
src_1KJDWYBZ11S0A57G_2-133_Empty_Ticket.jpg
src_1KJDWYDAN1S0XT35_2-133_Full_Ticket.jpg
src_1KJDWYEVQ1S0HEYT_2-133_Ops_Notes__1_.xlsx
src_1KJDWYFER1S053TF_2-132_--_2-138_CHN.pdf
src_1KJDWZ6DM1S0SJ0X_Billing_Documents_2298-T.pdf
src_1KJDX60P41S0FMF8_2-134_Ops_Notes.xlsx
src_1KJDX61CQ1S039AX_2-132_--_2-138_CHN.pdf
src_1KJDX62061S0PY6J_2-134_Empty_Ticket.jpg
src_1KJDX631V1S0AK27_2-134_Full_Ticket.jpg
src_1KJDX6V7N1S0Z18N_Billing_documents_Truck_2299-T.pdf
src_1KJDXCKTR1S0N3Q0_2-135_Ops_Notes.xlsx
src_1KJDXCMEQ1S08RJN_2-135_Empty_Ticket.jpg
src_1KJDXCNDG1S0WDEA_2-135_Full_Ticket.jpg
src_1KJDXCPS91S0G29Z_2-132_--_2-138_CHN.pdf
src_1KJDXDGPB1S04GGD_Billing_documents_truck_2300-T.pdf

src_1KJDXKWRP1S0TJYR_2-132_--_2-138_CHN.pdf
src_1KJDXKXBP1S0E7TD_2-136_Ops_Notes.xlsx
src_1KJDXKXZ91S01WP2_2-136_Full_Ticket.jpg
src_1KJDXKZRB1S0NHHQ_2-136_Empty_Ticket.jpg
src_1KJDXMRKF1S09ZR5_Billing_Truck_2301-T.pdf
src_1KJDXVWWR1S0V0SF_2-137_Ops_Notes.xlsx
src_1KJDXVXGR1S0ENN4_2-137_Empty_Ticket.jpg
src_1KJDXVYGS1S02AGS_2-137_Full_Ticket.jpg
src_1KJDXVZAB1S0NZCE_2-132_--_2-138_CHN.pdf
src_1KJGAP1TM1S0M1J4_AECN_to_SOPOR__Baie_Comeau___2_.png
[redacted]
src_1KJGAQH311S075NA_Screenshot_2026-01-27_125934.png
src_1KJGTDQV91S0KB72_2-132_--_2-138_CHN.pdf
src_1KJR6VC6E1S0NAH0_Screenshot_2026-02-23_at_11.29.10_AM.png
src_1KJR6VC6M1S08ZCN_Supporting_GHG_data_31Dec2025_S.xlsx
src_1KJR6VC7X1S0WM8A_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KJR6VCFK1S0G93Z_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KJR6Y2BE1S0JPPN_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KJR6Y2KZ1S06BJA_Supporting_GHG_data_31Dec2025_S.xlsx
src_1KJR6Y2NT1S0DN9M_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KJR7236B1S0KF26_BOL__2286-T_1__1_.pdf
src_1KJR75RYK1S0A290_Supporting_GHG_data_31Dec2025_S.xlsx
src_1KJR75RZM1S0XQ4N_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KJR75S6K1S050VZ_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KJR7DAMF1S0RV01_Supporting_GHG_data_31Dec2025_S.xlsx
src_1KJR7DAN21S0CFVP_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KJR7DB571S0KSK0_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KJR7EZYE1S0Z36D_BOL_2288-T_2.3.pdf
src_1KJR7JSX61S0TQT8_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KJR7JT7K1S09B8W_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KJR7JT7M1S021HJ_BOL_2290-T_2.5.pdf
src_1KJR7JT891S0NPD7_Supporting_GHG_data_31Dec2025_S.xlsx
src_1KJR7ZQYD1S0MZD3_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KJR7ZQZ51S08M8R_Supporting_GHG_data_31Dec2025_S.xlsx
src_1KJR7ZR8J1S0W94D_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KJR81D5G1S07JQT_BOL_2293-T_2.5.pdf
src_1KJRCFTS91S02DDS_BOL_2287-T_2.1_.pdf
src_1KJRCKGBW1S0GG3Y_BOL_2294-T_2.6.pdf

src_1KJRCKH3D1S044ZK_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KJRCKH3F1S0QSV8_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KJRCKH3G1S0BEPX_Screenshot_2026-02-23_at_11.29.10_AM.png
src_1KJRCKH471S0Z3JJ_Supporting_GHG_data_31Dec2025_S.xlsx
src_1KJRCQ6X21S0SPNF_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KJRCQ6X31S0DBH4_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KJRCQ77D1S010CS_Supporting_GHG_data_31Dec2025_S.xlsx
src_1KJRCQ7J21S08A43_Envoi_des_documents_Camion_2295-T.pdf
src_1KJRDXQZ31S0STYM_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KJRDXQZT1S014NY_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KJRDXR9J1S0MSHK_Supporting_GHG_data_31Dec2025_S.xlsx
src_1KJRDZGHA1S07XMS_Billing_Documents_2297-T.pdf
src_1KJRE39ER1S0VQRV_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KJRE39EV1S082X6_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KJRE39S31S0FCMG_Supporting_GHG_data_31Dec2025_S.xlsx
src_1KJRE49WM1S0V70C_Billing_Documents_2298-T.pdf
src_1KJRE82PN1S036RJ_Supporting_GHG_data_31Dec2025_S.xlsx
src_1KJRE82PY1S0PVM7_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KJRE82QN1S0AGFW_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KJREB17Z1S03C0Z_Supporting_GHG_data_31Dec2025_S.xlsx
src_1KJREB18Q1S0Q0WM_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KJREB1HZ1S0ANR9_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KJREBWHM1S02V8G_Billing_documents_truck_2300-T.pdf
src_1KJREEA9Q1S0YFWB_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KJREEAAQ1S0J4R0_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KJREEAM11S0SEFA_Supporting_GHG_data_31Dec2025_S.xlsx
src_1KJREF23Y1S0HKZH_Billing_Truck_2301-T.pdf
src_1KJRJ5XF11S08CER_Supporting_GHG_data_31Dec2025_S.xlsx
src_1KJRJ5YWN1S0W1AD_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KJRJ60FV1S03B1Q_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KJTAKFC91S0BGZV_2-132_--_2-138_CHN.pdf
src_1KJTAKG8Z1S0Z5VG_2-138_Scale_Ticket_Full.jpg
src_1KJTAKHVA1S0JTQ5_2-138_Scale_Ticket_Empty.jpg
src_1KJTAZ68J1S003FE_2-139_Scale_Ticket_Full.jpg
src_1KJTAZ7MW1S0KRB3_2-139_Scale_Ticket_Empty.jpg
src_1KJTAZ9FW1S07D6R_CHARM_INDUSTRIAL_-_BATCH_2-139__2-141__2-140.pdf

src_1KJTFA2J11S0RK9H_2-139_Scale_Ticket_Empty.jpg
src_1KJTFA2WM1S0C856_2-139_Scale_Ticket_Full.jpg
src_1KJTFWWRB1S0T4KP_2-138_Scale_Ticket_Full.jpg
src_1KJTFWX261S0DSFB_2-138_Scale_Ticket_Empty.jpg
src_1KJTGMBZW1S08VC7_2-130R_Empty_Ticket.jpg
src_1KJTGMC1T1S0WG7W_2-130R_Full_Ticket_.jpg
src_1KJTX12881S0KV74_2-142_Full_Ticket.jpg
src_1KJTX13PS1S07G2S_2-142_Empty_Ticket.jpg
src_1KJTX152T1S0V4YE_2-142_Ops_Notes_Rail__1_.xlsx
src_1KJTX1YXH1S0RYYT_documents_2303-T_charm.pdf
src_1KJTX7FGQ1S0WKAV_2-143_Ops_Notes.xlsx
src_1KJTX7G7K1S0G86G_2-143_Full_Ticket.jpg
src_1KJTX7HTJ1S03X25_2-143_Empty_Ticket.jpg
src_1KJTXGY5M1S0HGB8_2-144_Ops_Notes_Rail.xlsx
src_1KJTXGYY11S0556X_2-144_Empty_Ticket.jpg
src_1KJTXH0KM1S0RT2J_2-144_Full_Ticket.jpg
src_1KJTXT10J1S0H75V_2-145_Ops_Notes_Rail.xlsx
src_1KJTXT1MK1S04W1G_2-145_Full_Ticket.jpg
src_1KJTXT3AM1S0RGX5_2-145_Empty_Ticket.jpg
src_1KJTXTXDZ1S0S409_Biling_Documents_2304-T.pdf
src_1KJTY1SCS1S0K6AQ_2-146_Ops_Notes.xlsx
src_1KJTY1T8F1S06V6C_2-146_Full_Ticket.jpg
src_1KJTY1VM01S0TG21_2-146_Empty_Ticket.jpg
src_1KJTY2R2E1S0A7C8_Billing_Documents_2305-T.pdf
src_1KJTY2XC31S0XBFE_Charm-A5-2024-10-24-62-1976.pdf
src_1KJTY9KE31S0JX5A_2-147_Ops_Notes.xlsx
src_1KJTY9MAF1S06J0Z_2-147_Empty_Ticket.jpg
src_1KJTY9P3T1S0T6WM_2-147_Full_Ticket.jpg
src_1KJTYH19A1S040H9_2-148_Empty_Ticket.jpg
src_1KJTYH2YE1S0QNCY_2-148_Full_Ticket.jpg
src_1KJTYH4B01S0BA8K_2-148_Ops_Notes.xlsx
src_1KJTYQYKN1S0MK4S_2-149_Ops_Notes.xlsx
src_1KJTYQZ7X1S0880E_2-149_Full_Ticket.jpg
src_1KJTYR0XD1S0VWW3_2-149_Empty_Ticket.jpg
src_1KJTYYMP31S0J1N3_2-150_Full_Ticket.jpg
src_1KJTYYP0Q1S05PGR_2-150_Empty_Ticket.jpg
src_1KJTYYQQ01S0SBCD_2-150_Ops_Notes.xlsx
src_1KJTZ57YJ1S0FG5D_2-151_Empty_Ticket.jpg
src_1KJTZ592D1S03512_2-151_Full_Ticket.jpg
src_1KJTZ5A3C1S0PSWQ_Billing_Documents_2311-T.pdf
src_1KJTZ5BYZ1S0AERC_2-151_Ops_Notes.xlsx
src_1KJTZBHF81S0QQGN_2-152_Empty_Ticket.png
src_1KJTZBJN21S0BCCA_2-152_Full_Ticket.jpg

src_1KJTZBM441S0Z17Z_Billing_Documents_2309-T.pdf
src_1KJTZBNME1S0JP3M_2-152_Ops_Notes.xlsx
src_1KJWNMZEG1S0007A_Billing_Documents_2309-T.pdf
src_1KJWP130W1S0MB3V_Billing_Documents_2311-T.pdf
src_1KJWP2ER11S09QHA_Billing_Documents_2311-T.pdf
src_1KJWP79XF1S04VCP_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KJWP7A7R1S0C540_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KJWP7A7V1S0ZSZN_Supporting_GHG_data_31Dec2025_S.xlsx
src_1KJWPAEFH1S0JDAC_Billing_documents_2308-T.pdf
src_1KJWPC5RN1S0X65A_Billing_documents_2308-T.pdf
src_1KJWPNH781S0K8KN_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KJWPNHG61S0E76M_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KJWPNHG61S0TJAZ_Supporting_GHG_data_31Dec2025_S.xlsx
src_1KJWPTE5W1S0848N_Envoi_des_documents_Camion_2307-T.pdf
src_1KJWPXMYX1S04TDE_Envoi_des_documents_Camion_2307-T.pdf
src_1KJWQ1P6Z1S0G998_Supporting_GHG_data_31Dec2025_S.xlsx
src_1KJWQ1P751S03Y4X_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KJWQ1PMG1S0QK0J_Screenshot_2026-02-23_at_11.29.10_AM.png
src_1KJWQ1PN81S0B7W7_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KJWQ4P5G1S054Y8_Billing_Truck_2306-T.pdf
src_1KJWQ6CX31S0GEHN_Billing_Truck_2306-T.pdf
src_1KJWQ848W1S0D9YV_Supporting_GHG_data_31Dec2025_S.xlsx
src_1KJWQ84KP1S088HT_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KJWQ84KR1S0MKP5_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KJWQJNBS1S0FWSY_Supporting_GHG_data_31Dec2025_S.xlsx
src_1KJWQJNCN1S03HNK_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KJWQJNPG1S0Q6H8_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KJWQNA431S0QWJ4_2-142-2-146.pdf
src_1KJWQRCRB1S07W2G_Supporting_GHG_data_31Dec2025_S.xlsx
src_1KJWQRCS11S0VGY5_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KJWQRD2S1S02TNF_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KJWQZVY21S0D2QY_2-142-2-146.pdf
src_1KJWR1CYJ1S0H2M1_2-145_Empty_Ticket.jpg
src_1KJWR1D8M1S04QFP_2-145_Full_Ticket.jpg
src_1KJWR58ZT1S0ZAJK_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KJWR590V1S0JZE8_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KJWR591H1S06M9X_Supporting_GHG_data_31Dec2025_S.xlsx

src_1KJWR8GE41S03FQ3_2-142-2-146.pdf
src_1KJWRABCK1S07FK6_2-144_Full_Ticket.jpg
src_1KJWRABQ61S0V4EV_2-144_Empty_Ticket.jpg
src_1KJWRE09V1S0C5G5_2-142-2-146.pdf
src_1KJWRGE821S0GAMN_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KJWRGEJN1S0B97M_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KJWRGEJN1S0QMBZ_Supporting_GHG_data_31Dec2025_S.xlsx
src_1KJWRJD6F1S0RV5A_2-142-2-146.pdf
src_1KJWRP1GC1S0Y1TR_2-142_Ops_Notes_Rail__1___1_.xlsx
src_1KJWRP1GE1S0HPPD_2-142_Empty_Ticket.jpg
src_1KJWRP1VW1S05BJ2_2-142_Full_Ticket.jpg
src_1KJWT6E721S0M493_2-142_Ops_Notes_Rail__1___1_.xlsx
src_1KJX2RPMK1S0BN3V_BOL_2287-T_2.1_.pdf
src_1KJX30P8J1S05J5W_2-124_Ops_Notes__3_.xlsx
src_1KJX35TZ51S0VFBT_BOL_2288-T_2.3.pdf
src_1KJX38WT11S0TYKB_2-125_Ops_Notes__3_.xlsx
src_1KJX3B8W71S0GVS9_BOL_2290-T_2.5.pdf
src_1KJX3D4NR1S0919G_2-126_Ops_Notes__1__src_1KJ5VEW3C1S0V707.xlsx
src_1KJX3FTMA1S0W5CP_2-126_Ops_Notes__1__src_1KJ5VEW3C1S0V707.xlsx
src_1KJX3K9F11S0Q3ZN_BOL_2293-T_2.5.pdf
src_1KJX3MPND1S0XWYG_2-127_Ops_Notes__1_.xlsx
src_1KJX3PRMX1S07F03_2-127_Ops_Notes__1_.xlsx
src_1KJX3R1H71S0BZMN_BOL_2294-T_2.6.pdf
src_1KJX3T7161S0WVDJ_2-128_Ops_Notes_src_1KJ66QS741S0ZWP8.xlsx
src_1KJX3V2041S0QT0H_2-128_Ops_Notes_src_1KJ66QS741S0ZWP8.xlsx
src_1KJX3Y97V1S0N0XS_2-130_Ops_Notes_Rail_src_1KJDCJDFP1S0QHGM.xlsx
src_1KJX3YR061S0FZGR_2-130_Ops_Notes_Rail_src_1KJDCJDFP1S0QHGM.xlsx
src_1KJX3ZW0T1S05WPP_2-130_Ops_Notes_Rail_src_1KJDCJDFP1S0QHGM.xlsx
src_1KJX465131S0XHEE_2-131_Ops_Notes__1__src_1KJDCBRNR1S016FZ__1_.xlsx
src_1KJX477BC1S0Z908_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KJX477C31S0JXVX_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KJX477NT1S0T7K7_Supporting_GHG_data_31Dec2025_S.xlsx
src_1KJX4A57P1S07SGX_Envoi_des_documents_Camion_2295-T.pdf
src_1KJX4HQ0X1S0DGYT_2-129_Ops_Notes__1__src_1KJ66Z81E1S0B3BX.xlsx
src_1KJX4JAN41S0W4DE_2-129_Ops_Notes__1__src_1KJ66Z81E1S0B3BX.xlsx
src_1KJX4W28J1S0P6QW_Billing_Documents_2297-T.pdf
src_1KJX4Z2AF1S0VY5S_2-133_Ops_Notes__1__src_1KJDWYEVQ1S0HEYT.xlsx
src_1KJX4ZHC31S0PWRR_2-133_Ops_Notes__1__src_1KJDWYEVQ1S0HEYT.xlsx
src_1KJX50TBQ1S0HVBQ_Billing_Documents_2298-T__1_.pdf
src_1KJX54BSB1S0MSPW_2-134_Ops_Notes_src_1KJDX60P41S0FMF8.xlsx
src_1KJX54X5V1S0APWT_2-134_Ops_Notes_src_1KJDX60P41S0FMF8.xlsx

src_1KJX564EF1S05NFS_Billing_documents_Truck_2299-T.pdf
src_1KJX59VV31S07D1K_Billing_documents_Truck_2299-T.pdf
src_1KJX59VVV1S0V1X8_2-135_Ops_Notes_src_1KJDXCKTR1S0N3Q0.xlsx
src_1KJX5AB791S0XA7H_2-135_Ops_Notes_src_1KJDXCKTR1S0N3Q0.xlsx
src_1KJX5BMC61S0R8TG_Billing_documents_truck_2300-T__1_.pdf
src_1KJX5H9SW1S0CKQ1_2-136_Ops_Notes_src_1KJDXKXBP1S0E7TD.xlsx
src_1KJX5JRA41S02GWZ_2-136_Ops_Notes_src_1KJDXKXBP1S0E7TD.xlsx
src_1KJX62KBX1S0XFFY_Billing_Truck_2301-T.pdf
src_1KJX64GFQ1S0WYQF_2-137_Ops_Notes_src_1KJDXVWWR1S0V0SF.xlsx
src_1KJX64Z191S0T5MQ_2-137_Ops_Notes_src_1KJDXVWWR1S0V0SF.xlsx
src_1KJX7B2VR1S01KN6_2-142_Ops_Notes_Rail__1_.xlsx
src_1KJX7CYGG1S0QGV4_documents_2303-T_charm.pdf
src_1KJX7HG6T1S02ZPY_2-143_Ops_Notes.xlsx
src_1KJX7TFWX1S0H2D3_2-144_Ops_Notes_Rail_src_1KJTXGY5M1S0HGB8.xlsx
src_1KJX7WJ5M1S0E9AB_2-144_Ops_Notes_Rail_src_1KJTXGY5M1S0HGB8.xlsx
src_1KJX80EYH1S034ZB_2-145_Ops_Notes_Rail_src_1KJTXT10J1S0H75V.xlsx
src_1KJX8161M1S0Y3JA_2-145_Ops_Notes_Rail_src_1KJTXT10J1S0H75V.xlsx
src_1KJX82Q0W1S0VAFJ_2-145_Ops_Notes_Rail_src_1KJTXT10J1S0H75V.xlsx
src_1KJX85Y9W1S0W0GE_Biling_Documents_2304-T.pdf
src_1KJX87SVN1S0PZ3D_2-146_Ops_Notes.xlsx
src_1KJX88ZFF1S0HXPC_Billing_Documents_2305-T.pdf
src_1KJX8RYEK1S04H13_2-147_Ops_Notes_src_1KJTY9KE31S0JX5A.xlsx
src_1KJX8ZR241S0MB92_2-148_Ops_Notes_src_1KJTYH4B01S0BA8K.xlsx
src_1KJX9CAE21S0H1DV_2-149_Ops_Notes_src_1KJTYQYKN1S0MK4S.xlsx
src_1KJX9W0XG1S00AXB_2-150_Ops_Notes.xlsx
src_1KJXA3APQ1S0398G_2-151_Ops_Notes.xlsx
src_1KJXA90M91S0X6AH_2-152_Ops_Notes.xlsx
src_1KJXAAVV91S08FXY_Supporting_GHG_data_31Dec2025_S.xlsx
src_1KJXAAVVK1S0166M_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KJXAAW621S0MV29_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KJZBWXZW1S0K8YE_Standard_Emission_Factors___Calculations__5_.xlsx
src_1KJZBXW6Z1S0DPRY_Standard_Emission_Factors___Calculations__5_.xlsx
src_1KJZC2HA21S0KE6V_Standard_Emission_Factors___Calculations__5_.xlsx
src_1KJZC3T1C1S01GX0_Standard_Emission_Factors___Calculations__5_.xlsx
src_1KJZC9A291S0BRZF_2-141_Empty_Ticket.jpg
src_1KJZC9BTC1S0ZDV4_2-141_Full_Ticket.jpg
src_1KJZC9DF41S0K2PS_CHARM_INDUSTRIAL_-_BATCH_2-139__2-141__2-140.pdf
src_1KJZCA9DW1S0VTTG_Billing__Documents_2302-T.pdf
src_1KJZCRCT71S056ME_Diesel_Delivery_February_LA__1_.pdf
src_1KJZCTYDE1S0V92S_2.19.26_Gas_LA.pdf
src_1KJZCTZCC1S0EXYE_2.2.26_LA_Gas.pdf
src_1KJZCV0DP1S02JT3_2.24.26_Gasoline_Receipt_LA.pdf

src_1KJZCV20B1S09WHD_2_1_26-3_9_26_Gasoline_Tracker_LA.xlsx
src_1KJZCVE7W1S0221M_Argon_Consumption_Tracking_Feb_Mar_26.xlsx
src_1KJZCVEX51S0NPX9_Argon_2.3.26.pdf
src_1KJZCVFE61S09BRY_Argon_2.6.26.pdf
src_1KJZCVHE41S0X0MK_Argon_2.9.26.pdf
src_1KJZCVJ6A1S0GNG8_Feb_Basco_Electricity.xlsx
src_1KJZCVYHD1S03SKE_Brine_Usage_2_1-3_9.xlsx
src_1KJZCVZ4D1S0QEF3_Brine_2.16.26__1_.pdf
src_1KJZCW03W1S0B3AR_Brine_2.23.26_.pdf
src_1KJZCZCRA1S02R2G_Basco_Support_Travel_Calc_Sheet_Feb-March__1_.xlsx
src_1KJZCZE1J1S0PCY5_Feb-Mar_9_2026_Railcar_Emissions_Calc_Sheet.xlsx
src_1KJZCZET11S0A1ST_Feb-Mar_9_2026_Railcar_Emissions_Calc_Sheet__1_.xlsx
src_1KJZCZFPK1S0XPNF_Feb-Mar_9_2026_Railcar_Emissions_Calc_Sheet__2_.xlsx
src_1KJZCZGKQ1S0HBH4_Additional_Transport_.xlsx
src_1KJZCZH7P1S050CS_Louisiana_Sitework_Feb_1_-_March.xlsx
src_1KJZCZHTA1S0RN8E_Argon_Consumption_Tracking_Feb_Mar_26.xlsx
src_1KJZCZJBN1S0CA43_Argon_Consumption_Tracking_Feb_Mar_26.xlsx
src_1KJZCZK831S0ZYZR_Basco_Inj_Operations_Inventory_Feb_1_-_March___1_.xlsx
src_1KJZD4AWD1S0W4C2_CHARM_INDUSTRIAL_-_BATCH_2-139__2-141__2-140.pdf
src_1KJZD4BDX1S0FS7Q_2-140_Ops_Notes.xlsx
src_1KJZD4C361S03E3C_2-140_Empty_Ticket.jpg
src_1KJZD4E351S0Q2Z1_2-140_Full_Ticket.jpg
src_1KJZSK9FF1S01BMN_CHARM_INDUSTRIAL_-_147__148__149__150__150B__151__152__153.pdf
src_1KJZSN5YW1S0Y1SE_CHARM_INDUSTRIAL_-_147__148__149__150__150B__151__152__153.pdf
src_1KJZSSRYK1S0TQY7_CHARM_INDUSTRIAL_-_147__148__149__150__150B__151__152__153.pdf
src_1KJZSV5001S0QE30_CHARM_INDUSTRIAL_-_147__148__149__150__150B__151__152__153.pdf
src_1KJZSXA881S0M47S_CHARM_INDUSTRIAL_-_147__148__149__150__150B__151__152__153.pdf
src_1KJZSYAMF1S0GTCJ_CHARM_INDUSTRIAL_-_147__148__149__150__150B__151__152__153.pdf
src_1KJZTMKTA1S003W2_Supporting_GHG_data_31Dec2025_S.xlsx
src_1KJZTMKTG1S0KRQQ_BH_2025_LCA_w_Stack_Emissions.xlsx
src_1KJZTMMG21S07DKC_Bioenergy_AE_Cote-Nord_Canada_-_LCA_CI_calculation_-_1Jul2025_to_31Dec2025_S.xlsx
src_1KJZVSC4V1S0TGQA_2_1-3_9_Diesel_Consumption_Calcs.xlsx
src_1KK1SJVHC1S07939_Basco_Support_Travel_Calc_Sheet_Feb-March__1_.xlsx
src_1KK1SQ72Z1S0TJEW_Feb-Mar_9_2026_Railcar_Emissions_Calc_Sheet__2___1_.xlsx
src_1KK1THC8B1S07HNK_Basco_Inj_Operations_Inventory_Feb_1_-_March___1___1_.xlsx
src_1KK1VTJBM1S0QBXJ_Water_Transport_Calc_Sheet__2_.xlsx
src_1KK1W8DYE1S00D6P_Water_Transport_Calc_Sheet__2_.xlsx
src_1KK1WA8811S0PACM_Water_Transport_Calc_Sheet__2_.xlsx
src_1KK1WBD8F1S0C7JJ_Brine_Usage_2_1-3_2.xlsx
src_1KK1WYPAE1S0DZ4C_2025_Inventory_Reconciliation_v2.xlsx
src_1KK1X41CG1S05KW4_Moffit_to_Basco_Distance_src_1KGWSQ08F1S07C8D.png
src_1KK1Z4MH21S0WX3T_2-141_Ops_Notes_Rail__1_.xlsx

src_1KK1Z5JJR1S0BGJE_2-141_Ops_Notes_Rail__1_.xlsx
src_1KK1Z6DK51S0T412_2-141_Ops_Notes_Rail__1_.xlsx
src_1KK20A5Y01S0RP0T_Standard_Emission_Factors___Calculations__5_.xlsx
src_1KK20BNGV1S0B9BH_Feb_Basco_Electricity__1_.xlsx
src_1KK20FQSX1S02DAT_Feb_Basco_Electricity__1_.xlsx
src_1KK20KQDK1S0Z3FK_Standard_Emission_Factors___Calculations__5_.xlsx
src_1KK20KY3D1S084RQ_Standard_Emission_Factors___Calculations__5_.xlsx
src_1KK20PF211S0505X_Feb_Basco_Electricity__1_.xlsx
src_1KK20VG691S0J1B4_Standard_Emission_Factors___Calculations__5_.xlsx
src_1KK20W1NH1S0HGJN_Standard_Emission_Factors___Calculations__5_.xlsx
src_1KK243YH11S0RBXY_Brine_Usage_2_1-3_2.xlsx
src_1KK24FXS41S0S1YT_Diesel_Delivery_February_LA.pdf
src_1KK24FY5N1S00BP4_2_1-3_2_Diesel_Consumption_Calcs.xlsx
src_1KK24FY5N1S0CPTF_2.24.26_Diesel.pdf
src_1KK2GWAYN1S0ZQ0N_Argon_Consumption_Tracking_Feb_Mar_26__2_.xlsx
src_1KK2GXGHR1S0QBRD_Argon_Consumption_Tracking_Feb_Mar_26__2_.xlsx
src_1KK2H00MG1S0F0G5_Louisiana_Sitework_Feb_1_-_March__2_.xlsx
src_1KK2W834M1S0VGWX_Additional_Transport___2_.xlsx
src_1KKA15HXH1S007YX_2-132_Second_Weigh.jpg
src_1KKA15J9C1S0KWTJ_2-132_Third_Weigh.jpg
src_1KKA15J9G1S07HP7_2-132_First_Weigh.jpg
src_1KKA15J9M1S0V6HW_2-132_Ops_Notes_Rail.xlsx
src_1KKA194401S0G26W_2-132_Ops_Notes_Rail.xlsx
src_1KKA1BDTX1S0JFSJ_2-132_Ops_Notes_Rail.xlsx
src_1KKA1GWV21S0E4DD_2-132_Third_Weigh.jpg
src_1KKA1GX7Z1S01S92_2-132_Ops_Notes_Rail.xlsx
src_1KKA1JX0J1S0FB6R_2-132_Ops_Notes_Rail.xlsx
src_1KKA3H5A11S0AMAH_2-138_Ops_Notes_Rail.xlsx
src_1KKA3J8T11S0S7S5_2-138_Ops_Notes_Rail.xlsx
src_1KKA3K9ZV1S07V7S_2-138_Ops_Notes_Rail.xlsx
src_1KKA3MBNQ1S0PEPD_2-138_Ops_Notes_Rail.xlsx
src_1KKA4JEBE1S0CBWB_2-139_Ops_Notes_Rail.xlsx
src_1KKA4KK4Q1S0TZAZ_2-139_Ops_Notes_Rail.xlsx
src_1KKA4NV9Z1S0R687_2-139_Ops_Notes_Rail.xlsx
src_1KKA4QTDX1S0ND5F_2-139_Ops_Notes_Rail.xlsx
src_1KKA63TXC1S09R20_Feb-Mar_Railcar_Loss_Emissions.xlsx
src_1KKCKP4QG1S0959A_Argon_Consumption_Tracking_Feb_Mar_26.xlsx
src_1KKCKQ92Q1S032BB_Argon_Consumption_Tracking_Feb_Mar_26.xlsx
src_1KKCZ6N711S0NCRD_Basco_6_Capital_and_Sitework_Embodied_Emissions_Inventory_Feb_1_-_March.xlsx

APPENDIX 2: VERIFICATION AUDIT FINDINGS AND RESPONSES

Code	Type	Title	Issue	Supplier Response	Resolution
ISS-15	Clarification Request	Tank installation permits	Can you clarify if final inspections and approvals for the new storage tank (for which fire marshal and parish permits have been shared) have been completed and issued? If so, please provide copies	No additional inspections or approvals are required beyond the addition and fire marshal permits provided in the reporting package.	Resolved
ISS-14	Clarification Request / FAR	ThermOx on ASV monitoring	Although the air permit may not require monitoring of thermal oxidizer during operation, we would prefer to see evidence that the oxidizer is being operated properly in the future. Can you clarify if oxidizer operational monitoring is done (i.e. temperature logging). We would request providing a log of oxidizer operating temperature for the reporting period. This will ensure that operations are not negatively impacting the community and BTEX / VOCs are destroyed	That should not be a problem. This request has been submitted to injection ops for review so we can identify how best to pull and report on this data going forward.	Resolved and converted to FAR. Review at next reporting period
ISS-13	Clarification Request	Air Permit clarifications	Please confirm if there are any reporting or monitoring requirements associated with the new air permit. We did not observe any in the documentation provided but want to confirm	That's correct, no additional monitoring is required by the permit.	Resolved
ISS-12	Clarification Request	Community engagement CCS issue	Charm has provided additional information regarding community and stakeholder engagement issues related to environmental groups targeting CCS projects in LA. We appreciate the excellent documentation in the Grievance Record and transparency regarding these engagements. Please continue to update and provide additional information regarding contacts with the Save My Louisiana group. We would request that this update is provided with each reporting period to track any issues with these engagements	Absolutely -- Our Community Engagement Manager is actively working on this issue with stakeholders across the parish. Additional updates will be provided in subsequent reporting periods until the issue is resolved.	Resolved

ISS-11	Nonconformity (converted to FAR)	Wellhead gas testing incomplete	Charm engaged Guardian Plug and Abandonment to conduct wellhead gas testing as required every 6 months by the Isometric Protocol. The contractor performed the test and found no fugitive leaks at the wellhead. However, as acknowledged by Charm the Isometric protocol also requires testing for CO2 and VOC, which was not completed within the 6 month test period. Charm notes that an additional contractor was hired to complete the CO2 and VOC testing and results will be included in the next Reporting Period	Isometric User (03-17-2026 06:32): Isometric confirm making this request a FAR. There's clear intention and a timeline to obtain the data, and the outcome of the data being 'bad' would be indicative of a reversal which signifies an issue with *all* credits stored in that storage site, not just the credits from the latest verification activity.	Converted to FAR. To be confirmed next RP
ISS-10	Clarification Request	Inventory Reconciliation clarification	Please confirm that in the 2025 Inventory Reconciliation spreadsheet that the residual values for the WODO and Aqueous outstanding, where it is indicated in Column H that they have not shipped, indicates that they will be shipped and injected in the future and that process emissions associated with those shipments will be accounted for at that time	Confirmed -- Production Periods are reconciled after all physical inventory from a given period has left the site and the only purpose bio-oil leaves site for is to be injected. Although sometimes bio-oil intended for injection is disposed of due to operational issues, upstream production and transport emissions are accounted for in the disposal accounting. Therefore all oil that leaves site is accounted for either in injection or disposal accounting. So, once all oil has left site, this final reconciliation step ensures against any product/emissions going unaccounted for.	Resolved

APPENDIX 3: VERIFIER QUALIFICATIONS

Supporting documentation, including verifier resumes, and verifier or corporate accreditations are also included in this appendix.

Verifier Qualifications	Criteria Met?	Evidence / Notes *(note how the criteria was met, specific documents - resume/CV, publications, certifications, etc.).*
Verifier has relevant technical knowledge of the type of technology being evaluated and carbon removal processes in general		
A) Does Verifier have:		
1. An in-depth technical knowledge of the technology type under verification;	☑	350Solutions is accredited to ISO/IEC 17020:2012 and ISO 14034 Environmental Technology Verification (ETV) as a Type A (third party) Inspection Body (ANAB Certificate Number: AI-2618). The technical scope of 350's accreditation includes verification of performance and environmental impact as it relates to design, materials, equipment, installation and operations of technologies in the categories of Energy, Clean Production and Process, and Air Pollution Monitoring and Abatement. As documented in 350Solutions' ETV Standard Operating Procedure (ETV QPM 350-223-03), and Quality Systems Procedures for verifier qualifications (QSP-350-005-02), 350Solutions conforms to the requirements of ISO 17020 Annex A with respect to verifier qualifications and procedures. These procedures and quality management programs are generally relevant to verification under the Isometric Standard. Note that verifications completed for Isometric are not equivalent to ISO 14034 verifications. 350 staff have participated in the evaluation and verification of novel technologies that sequester carbon via various methods, including biomass conversion to liquids, solids, and other products which are then permanantly stored in ways such as land application or geologic storage, conversion of captured CO2 into building materials and co-products, and the production of chemicals, fuels, and products via biomass pyrolysis and gasification. 350 also served as lead verifier for the Carbon XPrize competition and contributed to the development of procedures and processes for verification of relevant calculations, modeling, and statistical methods in order to assess team results and calculations of performance metrics and uncertainty. 350 has demonstrated knowledge of data quality and data validation approaches and execution in supporting verification of performance claims and results.
2. Knowledge of specific risk areas associated with performance of such technologies (i.e. common failure points, performance issues, barriers to scaleup);	☑	
3. Knowledge of the environmental implications related to the use of the technology from a life cycle perspective, such as impact of the technology on lifecycle CO2 emissions and carbon removal;	☑	
4. Knowledge of relevant applicable test methods and standards for evaluating performance or impact of the technology;	☑	
5. Knowledge of relevant calculation, modeling, and statistical methods in order to assess test results and calculations of performance metrics and uncertainty, as applicable;	☑	
6. Knowledge of data quality and data validation approaches, including QA/QC procedures, for example.	☑	
Verifier is a credible independent 3rd party		
B) Is Verifier:		
1. third-party body independent of the team registered for the Isometric Registry	☑	350Solutions is accredited to ISO/IEC 17020:2012 and ISO 14034 ETV as a Type A (third party) Inspection Body. As documented in 350Solutions ETV Policy Manual (ETV QPM 350-200-03), 350Solutions conforms to the requirements of ISO 17020 Annex A with respect to impartiality for Type A inspections, pursuant to ISO 14034 activities.
2. Not directly involved in the design, manufacture or construction, marketing, installation, use or maintenance of the specific technologies submitted to Isometric for verification, or represent the parties engaged in those activities.	☑	
3. Not part of a legal entity that is engaged in design, manufacture, supply, installation, purchase, ownership, use or maintenance of the items inspected.	☑	

Tim Hansen, P.E.
Founder and CEO, 350Solutions

EDUCATION:
B.S., Chemical Engineering, University of Virginia, 1993
M.S., Engineering Science, Thayer School of Engineering, Dartmouth College, 1995

EXPERIENCE SUMMARY:
Mr. Hansen has 26 years of experience in management of energy and environmental technology development and demonstration projects and programs, as well as multimedia environmental engineering efforts. The majority of his recent work has focused on the evaluation of innovative carbon capture, utilization, and removal technologies. Mr. Hansen has led the development and management of large technology evaluation programs in the advanced energy, transportation, and climate change areas.

RESEARCH AND PROFESSIONAL EXPERIENCE:
2019-Present Founder – CEO, 350Solutions, Inc.
Owns and operates a small cleantech engineering consulting business focused on the independent evaluation of new cleantech innovations and their impact on the environment and carbon emissions. Provides engineering consulting, testing and evaluation, techno-economic assessment, and other support to companies developing, using, or investing in new clean technology innovations. Manages administrative, business development, and project activities for 350Solutions.

2012-2019: Director - Energy and Environment, Southern Research
Manages scientific and technical staff performing research, development, and evaluation of innovative clean energy technologies. Projects range from $25,000 to $6million in size, and are funded by the US Department of Energy, Department of Defense, and commercial partners. Technical focus areas are conversion of biomass to fuels and chemicals, carbon capture and utilization, energy efficient building technologies and renewable energy generation.

2009-2012: Program Manager – Transportation & Climate Change Technology, Southern Research
2003-2009 Sr. Project Leader, Environmental Engineer, Southern Research
1996-2003 Environmental Engineer, Bensinger & Garrison Environmental

PROJECT EXPERIENCE:
Mr. Hansen has executed several independent technology performance verifications of emerging carbon, energy and transportation technologies, as CEO of 350Solutions, Director of Energy & Environment at Southern Research, and Director of the U.S. EPA's Greenhouse Gas Technology Center. Mr. Hansen has completed clean technology evaluations for the Department of Defense, state energy agencies, commercial clients, investors, and technology developers, involving evaluation of commercial feasibility, economic and environmental impacts, and technology performance. Mr. Hansen served as the Measurement and Verification Program Lead for the NRG COSIA Carbon XPrize – a $20M prize competition for technologies that capture and beneficially utilize CO_2. Mr. Hansen also served as U.S. Technical Expert for the development and implementation of ISO 14034 – Environmental Technology Verification, an international standard, issued in 2016

Bill Chatterton
Senior Verification Scientist, 350Solutions

EDUCATION:
B.S. Environmental Science, SUNY at Plattsburgh, 1982
A.A.S. Environmental Technology, Paul Smith College, 1979
Certified Measurement and Verification Professional (CMVP), 2019

EXPERIENCE SUMMARY:
Mr. Chatterton has over 30 years of experience in management of energy and environmental technology development and demonstration projects and programs, as well as multimedia environmental engineering efforts. The majority of his recent work has focused on the evaluation of innovative carbon capture, utilization, and removal technologies. Mr. Chatterton has supported the development and management of large technology evaluation programs in the advanced energy, transportation, and climate change areas.

RESEARCH AND PROFESSIONAL EXPERIENCE:
2019-Present Sr Verification Scientist – 350Solutions, Inc.
Owns and operates a small cleantech engineering consulting business focused on the independent evaluation of new cleantech innovations and their impact on the environment and carbon emissions. Provides engineering consulting, testing and evaluation, techno-economic assessment, and other support to companies developing, using, or investing in new clean technology innovations. Manages administrative, business development, and project activities for 350Solutions.

2010-2019: Program Manager - Energy and Environment, Southern Research
Managed scientific and technical staff performing research, development, and evaluation of innovative clean energy technologies. Projects range from $25,000 to $6million in size, and are funded by the US Department of Energy, Department of Defense, and commercial partners. Technical focus areas are conversion of biomass to fuels and chemicals, carbon capture and utilization, energy efficient building technologies and renewable energy generation.

2000-2009 Sr. Project Leader, Environmental Engineer, Southern Research

PROJECT EXPERIENCE:
Mr. Chatterton has executed several independent technology performance verifications of emerging carbon, energy and transportation technologies for 350Solutions and previously at Southern Research Institute. Mr. Chatterton has completed clean technology evaluations for the Department of Defense, state energy agencies, commercial clients, investors, and technology developers, involving evaluation of commercial feasibility, economic and environmental impacts, and technology performance. Mr. Chatterton served as a Lead Verifier for the NRG COSIA Carbon XPrize – a $20M prize competition for technologies that capture and beneficially utilize CO_2. Mr. Chatterton is also a Certified Measurement and Verification Professional, issued in 2019.