Isometric Standard Project Verification Report

For

Charm Industrial

Client	Isometric
Company / GHG Removal Supplier	Charm Industrial
Facility or Project Name	Charm Bio-oil Geologic Storage
Facility Address	**Bio-oil Production:** AE Cote-Nord Canada Bioenergy Inc (AECN) Port Cartier, Quebec, Canada Charm Miniforge Fort Lupton, CO, USA **Bio-oil Pre-Processing:** Charm Industrial El Dorado, KS, USA **Bio-oil Injection:** Charm Industrial Evangeline Parish, LA, USA
Greenhouse Gas Statement ID/Gas Statement Version ID	ggs_1KGT7Y1711S08CVR gss_1KHSPJD6W1S0BEH1
Net Greenhouse Gas Removals	43.47 tonnes CO_{2e}
Removal Method	Bio-oil Geological Storage
Removal Period	07NOV2025 – 31JAN2026
Verification Opinion	Positive (fully meets criteria)
Verifier/Validation and Verification Body	Tim Hansen Bill Chatterton 350Solutions, Inc.

ISSUED:

FEBRUARY 23, 2026

CONTENTS

1. Key Project Data 3
1.1. Verification Summary 4
2. Verification & Storage Site Validation Details 6
2.1. Verification Objectives 6
2.2. Responsibilities 6
2.3. Level of Assurance & Materiality 6
2.4. Verification Team Details 6
2.5. Audit Process Followed 6
3. Technical Aspects 7
3.1. Project Details 7
3.2. Protocols and Modules Applied 8
3.3. Applicability of Applied Protocol and Modules 8
3.4. Project Boundary 8
3.5. Changes from Previous Verifications 9
3.6. Process & Data Irregularities During Reporting Period 10
4. Crediting Details 10
4.1. Project Reporting Period 10
4.2. Crediting Period 10
5. GHG Statement Verification & Storage Site Validation 10
5.1. Accuracy of the Statement 10
5.2. Verification Storage Site Validation Opinion 11
5.3. Verification & Storage Site Validation Results Summary 11
5.4. Verification & Storage Site Validation Findings 14
5.4.1. Critical Findings and Exceptions 14
5.4.2. Forward Action Requests & Recommendations 14
6. Revision History 15
Appendix 1: Documents Submitted for Review 17
Appendix 2: Verification Audit Findings and Responses 22
Appendix 3: Verifier Qualifications 25

ISOMETRIC STANDARD VERIFICATION REPORT		
Company: Charm Industrial	Company Contact: *Max Lavine	Validation and Verification Team: *Tim Hansen, PE Bill Chatterton
Removal Method: Bio-oil Geological Storage		
Report Date: February 23, 2026		
Document No: 350VR-Charm-ISO2606.01		
Rev: v1.2		

** Primary contact/lead author*

1. KEY PROJECT DATA

TABLE 1. VERIFICATION SUMMARY FOR CHARM INDUSTRIAL BIO-OIL STORAGE

Title	Charm Bio-Oil Geologic Storage
Location	Bio-oil Production: AE Cote-Nord Canada Bioenergy Inc (AECN) @ Produits Forestiers Arbec S.E.N.C., 175 Bd du Portage des Mousses Port-Cartier, QC G0W 1X0, Canada 50.025323, -66.818910 Charm Industrial Miniforge 2360 S Rollie Ave Fort Lupton, CO, USA 80621 40.076570, -104.804680 Bio-oil Injection & Storage: Charm Industrial (Basco Injection site) Evangeline Parish, LA 30.916251, -92.297908
Reporting Period	November 7, 2025 – January 31, 2026
Greenhouse Gas Statement ID	ggs_1KGT7Y1711S08CVR gss_1KHSPJD6W1S0BEH1
Project Proponents	CDR Supplier: Charm Industrial Feedstock Supplier: Produits Forestiers Arbec S.E.N.C (Quebec mill waste supplier); Altitude Forestry (CO forestry fire prevention waste supplier) Geologic Storage Management: Charm Industrial Salt Cavern Storage Management (Prior Injections): Vaulted Deep Regulatory Agency (Injections / Storage): Louisiana Department of Energy & Natural Resources; Kansas Department of Health & Environment (KDHE) (Prior Injections)
Legal Ownership of the Credits	Charm Industrial
Removals in Reporting Period	43.47 tonnes
Removal Method	Bio-oil Geological Storage
Verification Report Date	February 23, 2026
Verification Type & Criteria	Isometric Standard Verification for ongoing deliveries of carbon removal credits by Charm Industrial in accordance with the documents used during project validation:

	• Isometric Standard v1.8 • Bio-oil Geological Storage Protocol v1.1 • Biomass Feedstock Accounting Module v1.2 • Bio-oil Storage in Permeable Reservoirs v1.1 • Embodied Emissions Accounting v1.0 • Energy Use Accounting v1.2 • Transportation Emissions Accounting v1.1

1.1. VERIFICATION SUMMARY

350Solutions was contracted to perform a project verification of the greenhouse gas (GHG) statement of Charm Industrial's bio-oil geological storage process for the referenced reporting period. The validation report for the Charm Kansas Bio-oil Geologic Storage project was completed on June 25, 2024, by Futurepast, which focused on the use of third-party produced bio-oils and was issued by Isometric for the Crediting Period March 1, 2024 – February 28, 2029. An additional validation of the Charm Bio-oil Geologic Storage project for use of bio-oil produced by Charm was completed on October 18, 2024, for the same crediting period. These validations remain valid for this verification reporting period. Further details and findings can be found in the validation report (https://registry.isometric.com/project/prj_1HZSSWBQM1S08H83#project-documentation). Validation of an additional injection and storage location in Evangeline Parish, Louisiana was completed in September 2025 and is the injection and storage site for all injections during this reporting period. This storage site validation is included in the report located here: https://storage.googleapis.com/isometric--production--eu--public-documents/spl_1H31MW3T81S0R67B/prj_1HZSSWBQM1S08H83/pjd_1K5XPX61T1S0TM0Z/verification_report.pdf.

350Solutions affirms that Charm has the appropriate equipment, procedures, and protocols in place and is documented to quantify GHG removal through the injection of bio-oil into permeable reservoirs via a permitted Class V well in accordance with the requirements of the applicable Isometric standards, protocols and modules.

The carbon removals for the reporting period are provided in Table 2. These values have been verified by 350Solutions.

TABLE 2. VERIFIED TOTAL REMOVALS BY CHARM INDUSTRIAL FOR REPORTING PERIOD ENDING JANUARY 31, 2026

Removal ID	Date removal started	Date removal completed	Discounted CO_2e net removed, rounded (kg)
rmv_1KGWHNZWY1S0CREX	2025-12-09	2025-12-09	4970
rmv_1KGTQ8N4B1S0BVRE	2025-12-12	2025-12-12	6820
rmv_1KGT7Z0WY1S0W1QD	2025-11-07	2025-11-07	31680
TOTAL			43470

The quantity of **43.47 tonnes** of net carbon removals has been verified with a reasonable level of assurance and is eligible for crediting under the referenced Isometric Standard and Protocol.

350Solutions Inc. declares that it is an impartial verification body, approved by Isometric for verifications in the required technical area, free from any conflicts of interest, capable, and qualified to complete this verification for the current reporting period according to the *Isometric Standard v1.8, Bio-oil Geological Storage Protocol v1.1, Biomass Feedstock Accounting Module v1.2.1*, *Bio-oil Storage in Permeable Reservoirs Module v1.1, Embodied Emissions Accounting v1.0, Transportation Emissions Accounting v1.1,* and *Energy Use Accounting v1.2*.

Verifier Information		
Verification Body	**Verifier**	**Verification ID No.**
350Solutions, Inc.	Tim Hansen	VR-Charm-ISO2606.01

Timothy A. Hansen Digitally signed by Timothy A. Hansen Date: 2026.02.23 17:01:35 -05'00'

Signed: Tim Hansen (Verifier)

Bill Chatterton Digitally signed by Bill Chatterton Date: 2026.02.23 17:01:53 -05'00'

Bill Chatterton (QA)

2. VERIFICATION & STORAGE SITE VALIDATION DETAILS

2.1. VERIFICATION OBJECTIVES

A series of verification activities was conducted by 350Solutions to independently verify the claimed removals of the GHG statement submitted by Charm Industrial for operations conducted at the Charm Bio-oil Geologic Storage facility for the referenced Reporting Period. The verification was conducted following the specifications of the standards and protocols cited in Table 1.

2.2. RESPONSIBILITIES

The verification is based on the provision and fair presentation of a complete and accurate GHG Statement submitted by Charm Industrial to the Isometric registry. It is Charm's responsibility to ensure a fair, accurate, and complete presentation of the GHG Statement and Project Design Document are provided. This is confirmed and verified independently by 350Solutions based on supporting evidence in accordance with the Isometric criteria (Table 1, Section 3.2).

2.3. LEVEL OF ASSURANCE & MATERIALITY

The verification was conducted with a reasonable level of assurance. Any discrepancies between the claimed removals of the project and the removals estimated by the verification process for the reporting period are less than the materiality threshold of 5%.

2.4. VERIFICATION TEAM DETAILS

350Solutions is an accredited inspection & verification body by ANAB under ISO 17020:2012 for completion of ISO 14034:2016 Technology Verifications. 350Solutions is headquartered in Raleigh, North Carolina, USA. 350Solutions Technical Lead for the Charm verification is Tim Hansen. Mr. Hansen is a registered Professional Engineer with over 25 years of experience in the evaluation and verification of novel cleantech and carbon technologies. Mr. Hansen has led verifications of carbon removal technologies for multiple registries, including Isometric, and has experience in the development and testing of biomass conversion technologies, including gasification and pyrolysis. The verification report was provided QA by Bill Chatterton, a Carbon Removal Verification Engineer, with experience developing and verifying carbon removal technologies, MRV processes, and LCAs.

2.5. AUDIT PROCESS FOLLOWED

The specific verification and storage site validation activities conducted are summarized in Table 3. The list of all files that were reviewed is provided in Appendix 1. The list of findings from the verification can be found in Appendix 2. Audit results are documented using 350's Compliance Checklist, which includes all requirements from the Isometric standard, Bio-oil Geologic Storage protocol, and referenced modules.

TABLE 3. VERIFICATION & STORAGE SITE VALIDATION ACTIVITIES

Date(s)	Verification Activity	Verification Tasks	Documents Reviewed
February 17-20, 2026	Review of reporting period modifications and changes	• Review of GHG Statement and report and guidance from Charm	Final V 1.11 Charm Industrial Bio Oil Geologic Storage PDD + Biochar ggs_1KGT7Y1711S08CVR gss_1KHSPJD6W1S0BEH1 Nov 6-Jan 31 Removals Isometric GHG Statement Report v1.6 VVB Guidance Nov-Feb
February 17-20, 2026	Review of current Validation and GHG Statement Applicability	• Review of Validation Report • Review of prior Verification Report and findings • Identification of major and minor process steps, measurements, and calculations and changes in RP • Review of Standards/Protocols/Modules required for Verification • Generation of a checklist of verification issues and findings and opportunities for improvement	Validation_Report_for_Isometric_Charm_Industrial_Bio-Oil_Project_2024-06-25_r1 Isometric Standard Project Verification & Storage Site Validation Report For Charm Industrial (23Sep2025) ggs_1KGT7Y1711S08CVR gss_1KHSPJD6W1S0BEH1 Nov 6-Jan 31 Removals Isometric GHG Statement Report v1.6 VVB Guidance Nov-Feb Isometric Standard v1.8, Bio-oil Geological Storage Protocol v1.1, Biomass Feedstock Accounting Module v1.2, Bio-oil Storage in Permeable Reservoirs Module v1.1, Embodied Emissions Accounting v1.0, Transportation Emissions Accounting v1.1, and Energy Use Accounting v1.2
February 20-23, 2026	Verification of Removals	• Verify changes to the system • Review of measurements and calculations • Review of durability/permit requirement monitoring data • Review of GHG statement • Identification of initial findings and follow-up request for information • Write verification report • Internal Quality Assurance	File List provided in Appendix 1. Initial Findings in Appendix 2. Primary verification performed using Isometric Certify and supporting documentation

3. TECHNICAL ASPECTS

3.1. PROJECT DETAILS

Charm obtained bio-oil from two sources during this reporting period. Charm obtains bio-oil from a producer in Quebec, Canada (AECN) who uses an Ensyn/Honeywell UOP pyrolysis system to generate bio-oil from waste wood produced at a neighboring mill. In addition, Charm produces bio-oil at its pyrolysis facility in Fort Lupton, CO. Production of bio-oil for sequestration and carbon removal credit generation began in August of 2024, with the initial installation of four pyrolyzers, with plans for up to 18 pyrolyzers total to be installed. Charm's pyrolyzers utilize wood chips, placed into a high temperature pressurized reactor in a low oxygen environment to reduce the wood chips into a combination of products, including syngas and light hydrocarbon gases, pyrolysis oils, biochar, and wood vinegar. All hot pyrolysis gases from the reactor are quenched with water to produce the oil and wood vinegar products. Excess gases are routed to a combustion device for emissions control, with the heat produced from the combustion of excess gas utilized for drying the biomass from 40%-50% moisture content to 10% moisture content before introduction into the pyrolyzer.

Bio-oil from AECN and aqueous fraction product from Charm pyrolyzers are shipped by tanker truck, rail car, or tote tanks on flatbed to the injection facility in Louisiana. At this facility, Charm pretreats the bio-oil via air sparging and any other adjustments to ensure bio-oil and aqueous product meet the requirements of the injection facility permit for storage in permeable reservoirs as specified by the Louisiana Department of Energy & Natural Resources (LDENR).

Charm Bio-oil product, AECN oil, and Charm aqueous product are trucked to Charm's underground injection and storage facility located in Evangeline Parish, Louisiana for storage into a geologic reservoir. The bio-oil products are blended in on site storage tanks through recirculating pumps and injected as soon as practicable. Samples of the blended bio-oil are collected prior to injection and analyzed for bio-oil characteristics to ensure compliance with permit requirements. Charm also monitors all injection parameters as required by the Underground Injection Control (UIC) permit.

3.2. PROTOCOLS AND MODULES APPLIED

The verification was conducted following the specifications of the following standards, protocols, and modules:

- Isometric Standard v1.8 [1]
- Bio-oil Geological Storage Protocol v1.1 [2]
- Biomass Feedstock Accounting Module v1.2 [3]
- Bio-oil Storage in Permeable Reservoirs v1.1 [4]
- Embodied Emissions Accounting v1.0 [5]
- Energy Use Accounting v1.2 [6]
- Transportation Emissions Accounting v1.1 [7]

Charm utilizes Book and Claim Units (BCUs) to substitute for some, or all, of project diesel fuel usage and purchases Renewable Energy Certificates (RECs) for some, or all, of its electricity consumption in accordance with the Isometric Energy Use and Transportation Modules.

3.3. APPLICABILITY OF APPLIED PROTOCOL AND MODULES

The Charm project takes mixed woody waste or forestry thinnings from wildfire prevention activities, converts it to bio-oil, which they pretreat and inject into geologic storage formations. The biomass feedstocks were assessed previously under the eligibility criteria of the Isometric Biomass Feedstock Module and were found to be eligible. As the biomass feedstocks have been validated as eligible biomass feedstocks, the storage of biomass conversion products (bio-oil) in a geologic formation makes both the Bio-oil Geological Storage Protocol and Bio-oil Storage in Permeable Reservoirs Module applicable to this project. All other modules for energy, transportation, and embodied emissions accounting are generally applicable to this project.

3.4. PROJECT BOUNDARY

The boundaries of the project include the supply of wood waste to the biomass processing sites (AECN and Charm Fort Lupton), the conversion of the biomass to bio-oil via AECN's pyrolysis process and Charm's pyrolysis process, transport of the bio-oil to Charm, completion of pretreatment, and injection of the bio-oil in the geologic reservoir. Monitoring and required analysis of the bio-oil and the storage formation are also included in the project boundary.

3.5. CHANGES FROM PREVIOUS VERIFICATIONS

Compared to prior verification (Reporting Period 01OCT-06NOV2025), some significant and some minor modifications were made to the Charm Industrial processes, data collection, and calculation procedures which have been specified in the GHG statement and supporting documentation. The following modifications and notes have been provided for clarity. All were reviewed and deemed acceptable under the Isometric requirements:

- Charm had maintenance issues with the brine flow sensor, so instead vendor invoices for evidence and tracking of brine shipments to Basco Louisiana.
- The Kansas pre-treatment site is no longer operating, resulting in several modifications to prior processes:
    - This reporting period was the first in which trucks of oil were shipped from AECN directly to Basco 6 in LA for injection (no pretreatment in Kansas)
    - The equipment and site work associated with on-site sparging capabilities at the Basco injection site were completed in this reporting period and all equipment that was moved from Kansas was accounted for (transportation & installation). All emissions associated with construction and equipment, including embodied emissions, were accounted for and added to the amortization tally and schedule.
    - Any equipment fully decommissioned and disposed of from the Kansas site was fully depreciated and accounted for in the reporting period and removed from the amortized emissions
    - Changes in weighing procedures from shipments from AECN to Charm resulted in some corrections made to final weights, including conservatively deducting the mass of a full tank of diesel fuel from weighed truck mass
    - Emission calculations have been appropriately aligned with masses of bio-oil shipped in rail car (production emissions) and masses transferred by truck from rail to injection (total injected bio-oil)
- Additional railcar cleaning and post-spill cleanup and disposal activities were completed and accounted for in this reporting period. All cleanup activities and waste disposals from the prior spill were completed.
- BCUs were utilized to offset some of the new emissions associated with site construction, and equipment shipping, in addition to the typical usage for offsetting transportation diesel use.
- Losses associated with bio-oil sparging on site in LA were determined via lab studies and a loss rate established and utilized for onsite sparging activities. This was not previously done, as masses of bio-oil injected were determined via weigh scale upon delivery to injection, which occurred after sparging had been completed.
- There are no emissions associated with Charm production of bio-oil this period, as no Charm oil was injected this period.
- Requirements for monitoring records for prior injections at the Vaulted facility and the required monitoring frequency and submission timing are under discussion with Isometric as operations are moving to a post-injection monitoring plan and approach. Isometric has approved a delay in obtaining and submitting monitoring data for the Vaulted site during this transition period as all parties modify contractual requirements for ongoing monitoring and reporting.
- Note that Charm is continuing to transition additional parts of its reporting to the Isometric Certify platform. As this occurs, certain components may appear partially complete or incomplete in Certify. However, the data has been submitted separately from Certify and verified by 350 as compliant. For this reporting period, Monitoring and Feedstocks requirements

are included in Certify, but entries appear incomplete. However, these items are fully addressed outside of Certify.

3.6. PROCESS & DATA IRREGULARITIES DURING REPORTING PERIOD

No major irregularities or data issues were identified during this period.

It should be noted that the ongoing monitoring required for prior injections at the salt cavern storage site in Kansas (Vaulted Deep) continues to be completed. However, the reporting schedule and verification requirements for such monitoring is under discussion with Isometric and will be completed at a future date. It is also not relevant to the crediting associated with the current reporting period injections. Monitoring report timing and verification requirements for these prior injections are being developed with Isometric.

4. CREDITING DETAILS

4.1. PROJECT REPORTING PERIOD

This verification considers injections of bio-oil (oil and aqueous phases) by Charm during the period November 7, 2025 – January 31, 2026. The reporting period is based on the actual injection dates, with bio-oil production, transportation, monitoring, and related activities potentially occurring outside of this reporting period but properly accounted for and allocated to the bio-oil injected within the reporting period.

4.2. CREDITING PERIOD

The 5-year crediting period for the Charm Kansas Bio-oil Geologic Sequestration Project began March 1, 2024, and continues for five years, ending February 28, 2029. All claimed removals in this reporting period fall within the current crediting period.

5. GHG STATEMENT VERIFICATION & STORAGE SITE VALIDATION

5.1. ACCURACY OF THE STATEMENT

Confirmation of the GHG statement has been based on the following efforts:

- Review and confirmation of calculations of total bio-oil and CO_2 equivalent injected and all process, operational, and embodied emissions, as well as all supporting evidence for the following removals:

Removal ID	Date Removal Started
rmv_1KGWHNZWY1S0CREX	2025-12-09
rmv_1KGTQ8N4B1S0BVRE	2025-12-12
rmv_1KGT7Z0WY1S0W1QD	2025-11-07

- This includes for these removals:
  - Calculation of mass of bio-oil delivered and injected including tracing to raw data (weigh scale tickets, carbon content lab results, addition of consumables)
  - Confirmation of transportation distances for tanker and rail car deliveries from AECN to El Dorado, KS and to Basco site, LA, emission factors, and calculation of transportation emissions
  - Confirmation of emissions accounting for equipment relocation from KS to LA, including installation and construction emissions
  - Confirmation of sparging bio-oil mass losses and accounting
  - Confirmation of weigh scale raw data for deliveries of bio-oil and injectate
  - Confirmation of raw data for fuel usage at Charm injection facilities
  - Confirmation of electricity usage at Charm and injection facilities
  - Confirmation of proper use and accounting of BCUs and RECs to offset diesel and electricity usage emissions, respectively
  - Confirmation of embodied emissions for added equipment during the reporting period
- Review of monitoring data as required for Basco site injection (monthly and quarterly reports) and post injection monitoring to ensure compliance with Class V permit for Basco site

5.2. VERIFICATION STORAGE SITE VALIDATION OPINION

350Solutions has reviewed the documentation of the technology, the instrumentation, the procedures, performance and collected data and has found that the data presented in the greenhouse gas removal statement indicates that the claims fall within the 5% materiality threshold for greenhouse gas emissions and removals as required by the Isometric Standard:

☒ ***Meets the requirements of the Isometric Standard v1.8, Biomass Geological Storage Protocol v1.1, Biomass Feedstock Accounting Module v1.2, and Bio-oil Storage in Permeable Reservoirs Module v1.1 for Verification***

☐ ***Meets the requirements with <u>minor revisions</u> of Isometric Standard v1.8, Biomass Geological Storage Protocol v1.1, Biomass Feedstock Accounting Module v1.2, and Biomass or Bio-oil Storage in Salt Caverns Module v1.1 for Verification***

☐ ***Does Not Meet the requirements of the Isometric Standard v1.8, Biomass Geological Storage Protocol v1.1, Biomass Feedstock Accounting Module v1.2, and Biomass or Bio-oil Storage in Salt Caverns Module v1.1 for Verification***

5.3. VERIFICATION & STORAGE SITE VALIDATION RESULTS SUMMARY

A summary of verification results and compliance with relevant requirements of the *Isometric Standard, Biomass Geological Storage Protocol, Biomass Feedstock Accounting Module*, and *Bio-oil Storage in Permeable Reservoirs Module* are summarized below.

TABLE 4. VERIFICATION RESULTS SUMMARY

Isometric Standard Section Ref.	Verification Topic	Changed since Project Validation? (Y/N)	Final Findings
2.1.	*Validated against approved Protocols*	N	Acceptable – No additional changes since validation
2.5.1	*Boundaries*	N	Acceptable – No additional changes since validation
2.5.2	*Baseline*	N	Acceptable – No change since validation
2.5.3	*Additionality - Financial*	N	Acceptable – No change since validation
2.5.3	*Additionality – Environmental*	N	Acceptable – No change since validation
2.5.3	*Additionality – Regulatory*	N	Acceptable – No change since validation
2.5.4	*Leakage*	N	Acceptable – No change since validation and prior verification.
2.5.5	*Default Emission Factors, Proxies, and Models*	N	Acceptable – No additional significant changes were made since prior verifications. See Section 3.5 for summary of modifications to any calculation methods, all of which are acceptable.
2.5.11	*Life Cycle Assessment (LCA) Policies*	N	
2.5.6	*Common Calculation Factors*	N	
2.5.7	*Uncertainty*	N	
2.5.8	*Durability and Monitoring*	Y	All updated durability evidence and storage monitoring requirements validated to meet protocol requirements. Note that ongoing discussions with Isometric and Charm are occurring regarding frequency of Kansas storage site monitoring reports as the prior injections transition into a post-injection / closure monitoring phase with no Charm injections occurring.
2.5.9	*Risk of Reversal*	N	Acceptable – No additional changes since validation
2.5.10 ***3.7***	*Environmental and Socioeconomic Impacts*	N	Acceptable – No additional changes since validation.
3.1	*Ownership*	N	Acceptable – No change since validation
3.2	*Documentation*	Y	Acceptable – No additional changes since prior verification. All documentation properly updated for reporting period
3.3	*Eligibility*	Y (GHG Statement Updated)	Acceptable – Project registered with Isometric and reporting period GHG Statement properly submitted to Isometric dMRV Certify platform.
3.4	*Project Crediting*	Y (GHG Statement Updated)	Acceptable – New reporting period GHG Statement is complete and verified. Reporting period is within current validation crediting period.
3.5	*Stakeholder Input Process*	N	Acceptable – No changes since prior verification
3.6	*Regulatory Compliance*	Y (Required Monitoring Updated)	Required monitoring and reporting completed during reporting period. No additional compliance issues identified for injections during period.
Biomass Feedstock Accounting Module			
2.1	*Eligibility Criteria for Market Leakage*	N	Acceptable – No change since prior feedstock validations
2.2	*Counterfactual Storage Eligibility*	N	Acceptable – No change since prior feedstock validations

Isometric Standard Section Ref.	Verification Topic	Changed since Project Validation? (Y/N)	Final Findings
2.3	*Dedicated Energy Feedstock Eligibility*	N	Acceptable – No change since prior feedstock validations
3.0	*Counterfactual Definition*	N	Acceptable – No change since prior feedstock validations
3.1	*Counterfactual Energy Definition*	N	Acceptable – No change since prior feedstock validations
3.2	*Counterfactual Replacement Definition*	N	Acceptable – No change since prior feedstock validations

TABLE 5. BASCO STORAGE SITE VERIFICATION SUMMARY

Isometric Standard Section Ref.	Verification Topic	Changed since Project Validation? (Y/N)	Final Findings
Bio-oil Storage in Permeable Reservoirs Module			
1.0	*Storage System Eligibility*	N	Acceptable – No change since validation
2.1	*Storage Reservoir – Permitting*	N	Acceptable – No change since validation
2.2	*Storage Reservoir – Capacity*	N	Acceptable – No change since validation
2.2	*Storage Reservoir – Integrity*	N	Acceptable – No change since validation
2.2	*Storage Reservoir – Integrity: Characterization*	N	Acceptable – No change since validation. Well maintenance and an additional Mechanical Integrity Test were completed during the reporting period which met all criteria.
2.2	*Storage Reservoir Characterization – Temperature, pH, conductivity, density*	N	Acceptable – No change since validation
2.2	*Storage Reservoir Characterization – $d^{13}C$ analysis (where applicable)*	NA	Acceptable – Not required
2.3	*Storage Reservoir Integrity – Well Construction*	N	Acceptable – No change since validation
3.1.1	*Storage Reservoir Integrity – Injection operations*	Y	Acceptable – Updated monitoring data provided indicating no exceedances of permit limits
3.1.1	*Storage Reservoir Integrity – Injection operations – Sampling & Analysis*	Y	Acceptable – Updated sampling and analytical data provided indicating no exceedances of permit limits
1.0, 3.2	*Well Closure and Post Closure Requirements*	N	Acceptable – No change since validation
3.1.3	*Injection Pressure*	Y	Acceptable – Pressure is continuously monitored and reported quarterly (monitoring reports indicate full compliance)
3.1.2	*Mechanical Integrity*	N	Acceptable – No change since prior verification
3.1.3	*Volatile Gas Monitoring*	N	Acceptable – No change since validation
3.1.3	*Reversal Risk & Monitoring*	N	Acceptable – No change since validation
3.3.1	*Attribution of Reversals*	N	Acceptable – No change since validation

5.4. VERIFICATION & STORAGE SITE VALIDATION FINDINGS

5.4.1. CRITICAL FINDINGS AND EXCEPTIONS

Assessment of the greenhouse gas removal statement identified several minor findings and non-material data issues (see Appendix 2). No significant findings that materially impacted the verified net carbon removals nor compliance with protocol standard were identified. All findings, primarily clarifications and minor data errors, have been addressed and closed.

5.4.2. FORWARD ACTION REQUESTS & RECOMMENDATIONS

Forward action requests (FAR) and recommendations are also provided in Appendix 2 for consideration for improvement of future operations and GHG Removal Credit calculations and to ensure tracking of potential issues to be monitored by verifiers in future verifications. Open FARs and opportunities for improvement are summarized below for future verification reference:

TABLE 6. FORWARD ACTION REQUESTS AND RECOMMENDATIONS

ID No	Type	Finding / Issue	Supplier Response	Conclusion / Resolution
2	FAR	The Q4 2025 injection report would be due Jan 30. We see the Q3 report but not Q4. Can you please provide a copy?	The Q4 injection report is the "annual report" for the year. Louisiana Department of Conservation and Energy (LDCE) circulated a notice that this report is now due by May 31st 2026. A screenshot of the email notice has been added to the "Basco MRV" file as documentation LDCE Annual Reporting Deadline Notice.png	Complete - Modified to FAR. Thank you for the updated reporting schedule and evidence. We will anticipate submission of the report in May.
8		Will there be an updated emission factor for AECN process emissions soon? And, will Charm be doing the full annual emission factor review in March 2026?	Yes, there will be an updated AECN process emissions factor for 2026. All injections during this reporting period were from 2025, so it was not applied. All other emission factors will be updated for March 2026, so those values will be reflected starting when March injections are reported for verification this year.	Acceptable - noted as a FAR for next RP.
11	FAR (prior)	With injections no longer occurring at Vaulted, we would like to know how Charm will be notified of closure of the cavern where Charm oil was last injected, and to ensure that Charm will now be obtaining and submitting any post closure monitoring data to Isometric as part of the continued monitoring requirements. Please clarify that plans are in place for this and will be ongoing.	Charm has reached out to Vaulted on multiple occasions to get clarity regarding their future plans for the AR-09 injection well. The well still has considerable capacity and is the property of Vaulted, so it is up to them whether they plug and abandon the well or use it for their own emplacements. This decision on their part will affect the nature of the post-closure monitoring plan. We will continue to request clarity regarding these plans and, once received, we will define and submit a monitoring plan in light of the information we receive.	Verifier to review guidance and requirements from Isometric as ongoing discussions and post-closure monitoring plan requirements are evaluated with Isometric and Charm. Provide post-closure monitoring plan in near future as injections have now transitioned from Vaulted to the Basco facility.

12	FAR (prior)	With injections no longer occurring at Vaulted, please provide updated contract for post-emplacement / post-closure management and monitoring and post-closure monitoring plan that documents how Charm will be notified of closure of the cavern where Charm oil was last injected, and to ensure that Charm will now be obtaining and submitting any post closure monitoring data to Isometric as part of the continued monitoring requirements or this storage location		Verifier to review guidance and requirements from Isometric for post-closure monitoring plan requirements are evaluated with Isometric and Charm. Charm to provide evidence of contractual agreement with Vaulted regarding post-closure monitoring and responsibilities.

6. REVISION HISTORY

Version	Date Issued	Noted Changes
v1.0 (Draft – Internal)	February 23, 2026	N/A Initial Version
v1.1 (Draft – External)	February 23, 2026	Minor edits from QA
v1.2 (FINAL)	February 23, 2026	Final Version

References

[1] Isometric, “Isometric Standard v1.8.” Accessed: Feb. 23, 2026. [Online]. Available: https://registry.isometric.com/standard/1.2.0

[2] Isometric, “Bio-oil Geological Storage .1.1.” Accessed: Feb. 19, 2025. [Online]. Available: https://registry.isometric.com/protocol/bio-oil-geological-storage/1.1

[3] Isometric, “Biomass Feedstock Accounting .1.” Accessed: Feb. 19, 2025. [Online]. Available: https://registry.isometric.com/protocol/biomass-feedstock-accounting/1.1

[4] Isometric, “Biomass or Bio-oil Storage in Salt Caverns .0.4.” Accessed: Feb. 19, 2025. [Online]. Available: https://registry.isometric.com/protocol/salt-cavern-storage/1.0

[5] Isometric, “Embodied Emissions Accounting v1.0.3.” Accessed: Nov. 20, 2024. [Online]. Available: https://registry.isometric.com/protocol/embodied-emissions/1.0

[6] Isometric, “Energy Use Accounting v1.1.” Accessed: Nov. 20, 2024. [Online]. Available: https://registry.isometric.com/protocol/energy-use-accounting/1.1

[7] Isometric, “Transportation Emissions Accounting v1.1.” Accessed: Nov. 20, 2024. [Online]. Available: https://registry.isometric.com/protocol/transportation

See Appendix 1 and Table 3 for list of specific files reviewed during the verification.

APPENDIX 1: DOCUMENTS SUBMITTED FOR REVIEW

Name
src_1K31MHX8G1S038RS_Standard_Emission_Factors___Calculations__4_.xlsx
src_1K31MPMV51S0F34N_Standard_Emission_Factors___Calculations__4_.xlsx
src_1K36RC27E1S0S4W1_Production_Period_8_Summary.xlsx
src_1K36Y2T6A1S0MYR9_KS_Electricity_Calcs.png
src_1K36Y2YSX1S0J5NH_KS_Electricity_Calcs.png
src_1K36Z8JC91S099MT_GLEC_NA_Fuel_Energy.png
src_1K370M1Z51S076JY_GLEC_NA_Fuel_Energy.png
src_1K371H3W11S0BQ7G_LA_Grid_Emissions.png
src_1K37244EA1S0DESA_LA_Water_Transport_Emissions.png
src_1K3729JS71S07WKT_GLEC_NA_Fuel_Energy.png
src_1K39DSZWT1S0T93V_GLEC_NA_Road_Transport.png
src_1K39DWK2E1S0G69S_GLEC_NA_Road_Transport.png
src_1K39E29BY1S0W0NN_Truck_Embodied_Emissions.png
src_1K39E4ZYC1S07V1H_Truck_Embodied_Emissions.png
src_1K3RPXAS01S0W0MG_LCS_Emissions_Calc_Sheet.xlsx
src_1KGT83PVC1S0EJ4C_BATCH_2-119__1___1_.pdf
src_1KGT83Q7B1S02701_IMG_8001__3_.jpg
src_1KGT83QHS1S0NVVP_IMG_9602__4_.jpg
src_1KGT83QJ01S09GQB_2-119_Ops_Notes__2_.xlsx
src_1KGT9830P1S099GE_AECN_to_SOPOR__Baie_Comeau___2___1_.png
src_1KGT9FBZQ1S0YV6A_Screenshot_2026-01-27_125934__1_.png
src_1KGT9H5CG1S05M55_Screenshot_2026-01-27_125934__1_.png
src_1KGT9KY6D1S0F66R_2-119_Ops_Notes__2_.xlsx
src_1KGT9SK6N1S0AA24_2-119_Ops_Notes__2_.xlsx
src_1KGTA00VM1S05YNZ_AECN_to_SOPOR__Baie_Comeau___2___1_.png
src_1KGTC4J8F1S0RQ93_Standard_Emission_Factors___Calculations__3_.xlsx
src_1KGTQD6FJ1S05NWQ_SR25-08704_2-120-121-122__1_.pdf
src_1KGTQF1EY1S02WSZ_Truck_1_Full__1_.jpg
src_1KGTQF1F11S0PHNM_2-121_Ops_Notes__4_.xlsx
src_1KGTQF1F61S0A6H9_Truck_2_Full.jpg
src_1KGTQF1SH1S0XVCY_Truck_1_Empty.jpg
src_1KGTQF1SR1S0HG8K_Truck_2_Empty__1_.jpg
src_1KGTQYVKF1S008ZM_AECN_to_Basco__1_.png
src_1KGTR68381S01FRZ_Truck_1_Full__1_.jpg
src_1KGTR68DV1S0N4MM_Truck_2_Full.jpg
src_1KGTR8CY31S05FN2_AECN_to_Basco__1_.png
src_1KGTRT1NB1S0MYCZ_11_7_25-1_31_25_Gasoline_Tracker_LA.xlsx
src_1KGTRT1WX1S08K8M_12_16_25__3_.pdf

src_1KGTRT1ZS1S0W849_1.12.26__1_.pdf
src_1KGTRT2021S03HVK_1_5_26__1_.pdf
src_1KGTRT20H1S0Q6Q8_11.18.26_LA_Gas__1_.pdf
src_1KGTRT20J1S0FWZY_1.22.26_Gas_LA__1_.pdf
src_1KGTRT2EX1S0AVJX_12_16_25__2_.pdf
src_1KGTRT2FY1S0YGEJ_12_10_25__1_.pdf
src_1KGTRT2HC1S0J5A7_11.24.25_LA_Gas__1_.pdf
src_1KGTRT2J21S05T5W_12.3.25_LA_Gas__1_.pdf
src_1KGTRT2JX1S0SF1H_1.21.26_Gas_LA__1_.pdf
src_1KGTRT2R31S0D3X6_1.15.26_Gas__1_.pdf
src_1KGTRT37Z1S00RRV_12.1.25_LA_gas__1_.pdf
src_1KGTSB66X1S0767M_Standard_Emission_Factors___Calculations_-_2025_LA_Electricity_EFs.pdf
src_1KGTSF95X1S0K0KG_Nov_7_-_Jan_31_Basco_Electricity.xlsm_-_Total_RP__1_.pdf
src_1KGTSJGZG1S01SAH_Nov_7_-_Jan_31_Basco_Electricity.xlsm_-_Total_RP__1_.pdf
src_1KGTST0FD1S0QB0D_11_6-1_31_Diesel_Consumption_Calcs.xlsx
src_1KGTT6WX01S0CH67_Basco_6___KS_Embodied_Emissions_Inventory_Nov_7_-_Jan_31__3___1_.xlsx
src_1KGTTGAFH1S0AE4B_Basco_Inj_Operations_Inventory_Nov_7-Jan_31__3_.xlsx
src_1KGTTN94F1S04B6C_INVOICE_9421__1_.pdf
src_1KGTTN94F1S0R021_Distance_Evidence_Methanol__1___1___1_.png
src_1KGTTN94G1S0GPAQ_Methanol_Flush_Impact_Nov_7_-_Jan_31__1___1_.xlsx
src_1KGTTN9E61S0BMXP_INVOICE_9390__2_.pdf
src_1KGTTN9EV1S0Z9SB_Inv_9270_from_Vision_Production_Chemicals_LLC_12520__1___1_.pdf
src_1KGTTQN5X1S02RWZ_Louisiana_Sitework_Nov__1_.xlsx
src_1KGTTWD471S0TJX4_Basco_Support_Travel_Calc_Sheet_Nov-Jan.xlsx
src_1KGTV053S1S0WFQB_Equipment_KS_--__LA.xlsx
src_1KGTW5YBD1S0NA96_Brine_Invoice_2__1_.pdf
src_1KGTW5YC31S08Z4V_Brine_Invoice_4.pdf
src_1KGTW5YF31S0WM0G_Brine_Invoice_3__1_.pdf
src_1KGTW5YNS1S0G8W5_Baton_Rouge_Tank_Wash__1___1_.png
src_1KGTW5YP11S03XQT_Brine_Invoice_1__1_.pdf
src_1KGWHTE4J1S0NQSH_SR25-08704_2-120-121-122__1_.pdf
src_1KGWHYFFQ1S0JYPS_2-120_Ops_Notes__3_.xlsx
src_1KGWHYFFZ1S06KJE_BOL_2273-T_Full_Weight__2_.jpg
src_1KGWHYFG51S0DX9R_BOL_2272-T_Full_Weight__2_.jpg
src_1KGWHYFG51S0T8E3_BOL_2272__Empty_Weight__1_.jpg
src_1KGWHYFTD1S01J5D_BOL_2273-T_Empty_Weight__2_.png
src_1KGWHZHC91S0HX5V_BOL_2273-T_Full_Weight__2_.jpg
src_1KGWHZHGV1S05J1G_BOL_2272-T_Full_Weight__2_.jpg
src_1KGWJ0TAN1S0GVMX_BOL_2273-T_Full_Weight__2_.jpg
src_1KGWJ0TB11S04GGJ_BOL_2272-T_Full_Weight__2_.jpg
src_1KGWJ6K7A1S0A7YF_BOL_2273-T_Full_Weight__2_.jpg

src_1KGWJ6KHM1S0XWT4_BOL_2272-T_Full_Weight__2_.jpg
src_1KGWJ797N1S0450G_AECN_to_Basco__1_.png
src_1KGWJ8HE01S0DQ23_AECN_to_Basco__1_.png
src_1KGWJBAG11S0AD6W_Railcar_Waste_Disposal_Emissions_Calc_Sheet__3_.xlsx
src_1KGWMB99P1S0G8XY_Limestone.pdf
src_1KGWMB9A31S03XSK_Arcos-2025-12-11__1_.pdf
src_1KGWMB9B01S0B7GX_Arcosa_to_Basco.png
src_1KGWMB9M71S0YWCJ_Inv_7648_from_BALLS_CRANE_SERVICE_LLC._5052__1_.pdf
src_1KGWMB9P21S0JH87_20250862_Charm_Basco6SWD1__2_.pdf
src_1KGWMB9YB1S0663W_26Y01M0020_Charm_25085__1_.pdf
src_1KGWMB9Z01S0STZH_25Y11M0020_Charm_25080__1_.pdf
src_1KGWMBA3Z1S0DFV6_25Y11M0011_Charm_25078__1_.pdf
src_1KGWMBA521S014PV_25Y11M0002_Charm_25076__1_.pdf
src_1KGWMBA8S1S0MSJG_19398__1_.pdf
src_1KGWMBA8X1S08EE5_25Y12M0009_Charm_25085__1_.pdf
src_1KGWME0N51S02W8N_Railline_Distances.png
src_1KGWMG1AA1S0035X_Scale_Ticket_Empty.png
src_1KGWMG1AA1S054JY_Full_KSLA0001_scale.jpg
src_1KGWMG1AF1S0RSEK_Scale_Ticket_Full.png
src_1KGWMG1AG1S0CEA8_Empty_KSLA0001_Scale_ticket.jpg
src_1KGWMG1AH1S0KR1J_KS_to_LA_Distance__1_.png
src_1KGWMG1MT1S07CX7_KSCO0002_Scale_Ticket.jpg
src_1KGWMG1W51S0V1RW_BOL__KSLA0003.pdf
src_1KGWMG1WE1S0EPMH_KS_to_CO_Distance.png
src_1KGWMG26N1S02BG6_UF-4324868086-SCALE_TICKET__1___1_.PDF
src_1KGWMHDD31S01TQQ_D00048103__1___1_.pdf
src_1KGWMHDD31S0NFKC_D00047854__1___1_.pdf
src_1KGWMHDDC1S094F1_D00047413__1___1_.pdf
src_1KGWMHDQZ1S0WSAP_D00048002__1___1_.pdf
src_1KGWMHDR41S0GE6B_D00047712__1___1_.pdf
src_1KGWMHDRA1S04320_D00047644__1___1_.pdf
src_1KGWMJ43C1S08KPJ_D00048103__1___1_.pdf
src_1KGWMJ43J1S0W8J7_D00048002__1___1_.pdf
src_1KGWMJ43X1S0FXDW_D00047413__1___1_.pdf
src_1KGWMJ43Z1S03J9H_D00047854__1___1_.pdf
src_1KGWMJ4DV1S0Q756_D00047644__1___1_.pdf
src_1KGWMJ4GB1S0AW0V_D00047712__1___1_.pdf
src_1KGWMS2701S05F3R_AECN_to_Basco__1_.png
src_1KGWMTJ4H1S028GQ_RP_Summary_Nov_6-Jan_2.xlsx
src_1KGWMW9471S0R5PN_RP_Summary_Nov_6-Jan_2.xlsx
src_1KGWNKKP11S0DVNP_image__44___1_.png

src_1KGWQD6TD1S00M8T_2-119_Ops_Notes__4_.xlsx
src_1KGWQGCDP1S04M4X_image__44___1_.png
src_1KGWQHSTK1S01A9P_2-119_Ops_Notes__4_.xlsx
src_1KGWQMHHM1S0Y0EF_Jan_2026_Railcar_Cleaning_Emissions_Calc_Sheet__2_.xlsx
src_1KGWSHNMW1S03QWC_Moffit_to_Basco_Distance.png
src_1KGWSQ08F1S07C8D_Moffit_to_Basco_Distance.png
src_1KGWWVD4D1S08299_Brine_Invoice_2__1_.pdf
src_1KGWWVD4E1S0FC0K_Baton_Rouge_Tank_Wash__1___1_.png
src_1KGWWVD4M1S030W8_Brine_Invoice_4.pdf
src_1KGWWVDGD1S0PNQX_Brine_Invoice_1__1_.pdf
src_1KGWWVDYG1S0AAKJ_Brine_Invoice_3__1_.pdf
src_1KGWX4X2F1S0KWN5_src_1KA7C7KMW1S07AZ9_Water_Transport_Calc_Sheet__1_.xlsx
src_1KGWX60YS1S0P4ZE_src_1KA7C7KMW1S07AZ9_Water_Transport_Calc_Sheet__1_.xlsx
src_1KGWXCJMP1S0QBRS_Brine_Usage_11_7-1_31__3_.xlsx
src_1KGWXDG041S0YNG3_Brine_Usage_11_7-1_31__3_.xlsx
src_1KGWYKT471S0PFG8_CHARM_INDUSTRIAL_INV_651216__2___4_.pdf
src_1KGWYKT4B1S0A4BX_ace8af9c-6c99-4107-b417-1459f7fdb64e__3_.JPEG
src_1KGWYKT4J1S0XS7J_a8d2c10c-9978-4f87-875e-9aa38202a06a__3_.JPEG
src_1KGWYKTEV1S0HE37_11_6-1_31_Diesel_Consumption_Calcs__1_.xlsx
src_1KGWZ7XFK1S0ET8W_Standard_Emission_Factors___Calculations_-_2025_LA_Electricity_EFs.pdf
src_1KGWZJ63B1S08QAX_Argon_Consumption_Tracking_Jan_26__2_.xlsx
src_1KGX0RG671S0TSX5_Nov-Jan_RP_BCU_Quant__3_.xlsx
src_1KGX1SFKP1S023MF_RP_Summary_Nov_6-Jan__1_.xlsx
src_1KGX1T28K1S04BYR_RP_Summary_Nov_6-Jan__1_.xlsx
src_1KGX1VTV01S06M91_RP_Summary_Nov_6-Jan__1_.xlsx
src_1KGX3TSJS1S0M66Q_2-119_Ops_Notes__6_.xlsx
src_1KGX3W5561S0VFY1_2-119_Ops_Notes__6_.xlsx
src_1KGX3WR331S02SNB_2-119_Ops_Notes__6_.xlsx
src_1KGX3YGY31S0XR8A_2-119_Ops_Notes__6_.xlsx
src_1KGX3YGY41S0A3CN_RP_Summary_Nov_6-Jan__1_.xlsx
src_1KGX40NJK1S0RPV9_RP_Summary_Nov_6-Jan__1_.xlsx
src_1KGX422761S000JK_RP_Summary_Nov_6-Jan__1_.xlsx
src_1KGX43PFY1S07A9X_RP_Summary_Nov_6-Jan__1_.xlsx
src_1KGYYF37P1S0QZV5_Argon_Consumption_Tracking_Jan_26__2_.xlsx
src_1KGYYF37V1S0GP3V_D00048103__1___1_.pdf
src_1KGYYF3801S0BMPT_D00047644__1___1_.pdf
src_1KGYYF3811S04AZG_D00047712__1___1_.pdf
src_1KGYYF3J91S0JYE4_D00047854__1___1_.pdf
src_1KGYYF3JE1S0Z9JF_D00048002__1___1_.pdf
src_1KGYYF46M1S06K9S_D00047413__1___1_.pdf
src_1KGYYRZ181S0FMJX_Argon_Consumption_Tracking_Jan_26__3_.xlsx

src_1KGZ2M3XN1S0DHH1_Opelousas_Cleanup_Operations.xlsx
src_1KGZCC99E1S0J7E0_RP_Summary_Inventory_Reconciliation.xlsx
src_1KGZCC99E1S0YJJB_RP_Summary_Nov_6-Jan__1_.xlsx
src_1KGZCGD561S0QYVX_Nov-Jan_RP_BCU_Quant__4_.xlsx

APPENDIX 2: VERIFICATION AUDIT FINDINGS AND RESPONSES

ID No	Type	Finding / Issue	Supplier Response	Conclusion / Resolution
1	Clarification	Thank you for the information on sparge losses for Basco on site sparging. The calculations are acceptable. However, can you please clarify the anticipated emissions associated from the process? Specifically, 1) are there any anticipated methane emissions generated (unlikely, but confirming) and 2) what are the levels of BTEX emissions anticipated if, as displayed by the chart in the sparging test summary, the goal is removal of benzene (i.e. emitted to air)	The purpose of the experiment was to measure the loss of bio-oil mass due to sparging to remove VOCs. What the experiment did not include, as it did not serve that purpose, was the end of the sparging process was the rapid combustion of displaced compounds in a thermal oxidizer. Multiple studies have shown that the combustion of benzene in a thermal oxidizer can achieve 99% VOC destruction efficiencies, converting BTEX to CO2 and H2O. There is no reason to anticipate methane emissions, as no parts of the sparging process generate methane and even if methane were generated somehow it would also be destroyed in the oxidizer. All combusted gases are converted to CO2 and H2O. Biogenic CO2 emissions would have been emitted in a non-intervention counterfactual, so they are not netted against gross removals when calculating Net CDR. Additionally, the Combined Emissions Monitoring and Accounting Plan for the site, submitted as a supplement to the PDD, specifies that net additional GHG emissions from the thermal oxidizer will be considered to be *de minimis* until the site is configured to sparge over 8k gal of bio-oil at once. Currently, the site is configured to sparge approximately 4.5k gal at once.	Complete. No additional information required.
2	FAR	The Q4 2025 injection report would be due Jan 30. We see the Q3 report but not Q4. Can you please provide a copy?	The Q4 injection report is the "annual report" for the year. Louisiana Department of Conservation and Energy (LDCE) circulated a notice that this report is now due by May 31st 2026. A screenshot of the email notice has been added to the "Basco MRV" file as documentation LDCE Annual Reporting Deadline Notice.png	Complete - Modified to FAR. Thank you for the updated reporting schedule and evidence. We will anticipate submission of the report in May.

3	Misstatement (Non-material)	The limestone amount delivered is indicated in 'Louisiana Sitework Nov.xls' Scale Tickets 7 Transport tab as 54.5 metric tons. The receipt 'Limestone.pdf' indicates 57.14 US tons of limestone was delivered at a cost of 54.5 $/ton.	New Limestone EE: 5.1426 MT Old Limestone EE: 4.905 MT New Transport Process: 0.727958 MT Old Transport Process: 0.715862 MT Difference Limestone: 0.2376 MT Difference Transport Process: 0.012096 MT (BCU's) Total Difference: 0.249696 MT See Louisiana Sitework Nov.xlsx -- All limestone EE has been added to the Louisiana Sitework line item in the Embodied Emissions inventory. The process emissions are offset with BCUs and accounted for in the Nov-Jan BCU Quant file	Complete. Data and calculations updated
4	Clarification	Can you please clarify where the emission factor for the Roll Off and RailCar cleaning is derived from? Value indicated is 0.988 kg/$, but that doesn't match any values on the Emissions Factor list in the Opelousas Cleanup Operations spreadsheet	This emissions factor is found in the following database (SupplyChainGHGEmissionFactors_v1.3.0_NAICS_CO2e_USD2022 (4)). This fast under NAICS Code 562910 (Remediation Services). All related and similar waste disposal and waste handling in the NAICS are at this 0.988 EF.	Complete.
5	Clarification	Two items from the KS site are indicated as Disposed in the 'Basco 6 + KS Embodied Emissions Inventory Nov 7 - Jan 31' spreadsheet. If these are no longer in use and disposed, were the unamortized embodied emissions fully accounted for in this reporting period? We believe they should now be, since they reached end of life. The items are the Salt Dosing Auger Motor and the Auger System.	Identified items were slated for disposal, but had not yet been disposed of at the time of reporting. For simplicity's sake, we will net the outstanding embodied emissions against this period's removals. Total of 541 kgs will be added to the baseline Reporting Period EE Penalty. Baseline Reporting Period EE Penalty = 247.73 kg New Adjusted Value: 247.73 kg + 541 kg = 788.73 kg	Complete.
6	Misc	The tags for Distance travelled and Mass of Load for the B6 Injection Diesel Delivery - Transport Process Emissions in Certify for rmv_1KGTQ8N4B1S0BVRE appear to be swapped. The calculation and data fields are correct so and there is no impact. Just clarifying to ensure your data fields align in Mangrove / Certify.	This is a great catch, this has been adjusted in Certify. Diesel delivery Distance Mileage - Distance Traveled B6 Injection Diesel Mass - Mass of Load	Complete.
7	Clarification	Can you please clarify what the "SP&C KS + LA Kg Penalty/RP" column is on the Amortization tab for the 'Basco 6 + KS Embodied Emissions Inventory Nov 7 - Jan 31' spreadsheet?	The SP&C Penalty are the emissions associated with Spare Parts and Consumables for our injection operations. See associated spreadsheet that has the details behind the value: (Basco Inj Operations Inventory Nov 7-Jan 31.xlsx)	Complete. Thank you for the clarification

8	FAR / Clarification	Will there be an updated emission factor for AECN process emissions soon? And, will Charm be doing the full annual emission factor review in March 2026?	Yes, there will be an updated AECN process emissions factor for 2026. All injections during this reporting period were from 2025, so it was not applied. All other emission factors will be updated for March 2026, so those values will be reflected starting when March injections are reported for verification this year.	Acceptable - noted as a FAR for next RP.
9	Clarification	The BCU amounts reported in the Charm EAC Verification Inventory tracker spreadsheet match what is reported for the BCU usage in Certify. However, I can't seem to reconcile the reported 52.537 MT CO2e from BCUs reported with the values in the BCU RP summary: Nov-Jan RP BCU Quant. Can you please provide more detail / explanation?	The original Nov-Jan RP BCU Quant was used for internal notes and contained some small errors which were corrected WRT the data in Certify, but not corrected on the sheet itself, leading to a discrepancy. Now, the values are different due to some of the changes made as a result of this review, and both the revised Nov-Jan RP BCU Quant sheet and Certify values match at 54.305 MTCO2e.	Complete. Updated values accurate
10	Omission	Copies of the BOL for Batch 2-119 (railcar deliery) were not provided (on Certify nor Google Drive) that we see, so full railcar load amount cannot be verified. Please provide these BOLs.	Note: There is no specific BOL for the railcar itself. Instead, the BOL's associated with the each truck in the railcar delivery have been added into drive and into certify on Rail Transport Process emissions component for evidence. BOLs are assumed to be loaded into the railcar with no loss to ensure a conservative estimate of upstream emissions	Complete. Understood.
11	FAR (prior)	With injections no longer occurring at Vaulted, we would like to know how Charm will be notified of closure of the cavern where Charm oil was last injected, and to ensure that Charm will now be obtaining and submitting any post closure monitoring data to Isometric as part of the continued monitoring requirements. Please clarify that plans are in place for this and will be ongoing.	NA - In Process. Waiting for final guidance from Isometric	Verifier to review guidance and requirements from Isometric as ongoing discussions and post-closure monitoring plan requirements are evaluated with Isometric and Charm. Provide post-closure monitoring plan in near future as injections have now transitioned from Vaulted.
12	FAR (prior)	With injections no longer occurring at Vaulted, please provide updated contract for post-emplacement / post-closure management and monitoring and post-closure monitoring plan that documents how Charm will be notified of closure of the cavern where Charm oil was last injected, and to ensure that Charm will now be obtaining and submitting any post closure monitoring data to Isometric as part of the continued monitoring requirements or this storage location	NA - In Process. Waiting for final guidance from Isometric	Verifier to review guidance and requirements from Isometric for post-closure monitoring plan requirements are evaluated with Isometric and Charm. Charm to provide evidence of contractual agreement with Vaulted regarding post-closure monitoring and responsibilities.

APPENDIX 3: VERIFIER QUALIFICATIONS

Supporting documentation, including verifier resumes, and verifier or corporate accreditations are also included in this appendix.

Verifier Qualifications	Criteria Met?	Evidence / Notes *(note how the criteria was met, specific documents - resume/CV, publications, certifications, etc.).*
Verifier has relevant technical knowledge of the type of technology being evaluated and carbon removal processes in general		
A) Does Verifier have:		
1. An in-depth technical knowledge of the technology type under verification;	☑	350Solutions is accredited to ISO/IEC 17020:2012 and ISO 14034 Environmental Technology Verification (ETV) as a Type A (third party) Inspection Body (ANAB Certificate Number: AI-2618). The technical scope of 350's accreditation includes verification of performance and environmental impact as it relates to design, materials, equipment, installation and operations of technologies in the categories of Energy, Clean Production and Process, and Air Pollution Monitoring and Abatement. As documented in 350Solutions' ETV Standard Operating Procedure (ETV QPM 350-223-03), and Quality Systems Procedures for verifier qualifications (QSP-350-005-02), 350Solutions conforms to the requirements of ISO 17020 Annex A with respect to verifier qualifications and procedures. These procedures and quality management programs are generally relevant to verification under the Isometric Standard. Note that verifications completed for Isometric are not equivalent to ISO 14034 verifications. 350 staff have participated in the evaluation and verification of novel technologies that sequester carbon via various methods, including biomass conversion to liquids, solids, and other products which are then permanantly stored in ways such as land application or geologic storage, conversion of captured CO2 into building materials and co-products, and the production of chemicals, fuels, and products via biomass pyrolysis and gasification. 350 also served as lead verifier for the Carbon XPrize competition and contributed to the development of procedures and processes for verification of relevant calculations, modeling, and statistical methods in order to assess team results and calculations of performance metrics and uncertainty. 350 has demonstrated knowledge of data quality and data validation approaches and execution in supporting verification of performance claims and results.
2. Knowledge of specific risk areas associated with performance of such technologies (i.e. common failure points, performance issues, barriers to scaleup);	☑	
3. Knowledge of the environmental implications related to the use of the technology from a life cycle perspective, such as impact of the technology on lifecycle CO2 emissions and carbon removal;	☑	
4. Knowledge of relevant applicable test methods and standards for evaluating performance or impact of the technology;	☑	
5. Knowledge of relevant calculation, modeling, and statistical methods in order to assess test results and calculations of performance metrics and uncertainty, as applicable;	☑	
6. Knowledge of data quality and data validation approaches, including QA/QC procedures, for example.	☑	
Verifier is a credible independent 3rd party		
B) Is Verifier:		
1. third-party body independent of the team registered for the Isometric Registry	☑	350Solutions is accredited to ISO/IEC 17020:2012 and ISO 14034 ETV as a Type A (third party) Inspection Body. As documented in 350Solutions ETV Policy Manual (ETV QPM 350-200-03), 350Solutions conforms to the requirements of ISO 17020 Annex A with respect to impartiality for Type A inspections, pursuant to ISO 14034 activities.
2. Not directly involved in the design, manufacture or construction, marketing, installation, use or maintenance of the specific technologies submitted to Isometric for verification, or represent the parties engaged in those activities.	☑	
3. Not part of a legal entity that is engaged in design, manufacture, supply, installation, purchase, ownership, use or maintenance of the items inspected.	☑	

Tim Hansen, P.E.
Founder and CEO, 350Solutions

EDUCATION:
B.S., Chemical Engineering, University of Virginia, 1993
M.S., Engineering Science, Thayer School of Engineering, Dartmouth College, 1995

EXPERIENCE SUMMARY:
Mr. Hansen has 26 years of experience in management of energy and environmental technology development and demonstration projects and programs, as well as multimedia environmental engineering efforts. The majority of his recent work has focused on the evaluation of innovative carbon capture, utilization, and removal technologies. Mr. Hansen has led the development and management of large technology evaluation programs in the advanced energy, transportation, and climate change areas.

RESEARCH AND PROFESSIONAL EXPERIENCE:
2019-Present Founder – CEO, 350Solutions, Inc.
Owns and operates a small cleantech engineering consulting business focused on the independent evaluation of new cleantech innovations and their impact on the environment and carbon emissions. Provides engineering consulting, testing and evaluation, techno-economic assessment, and other support to companies developing, using, or investing in new clean technology innovations. Manages administrative, business development, and project activities for 350Solutions.

2012-2019: Director - Energy and Environment, Southern Research
Manages scientific and technical staff performing research, development, and evaluation of innovative clean energy technologies. Projects range from $25,000 to $6million in size, and are funded by the US Department of Energy, Department of Defense, and commercial partners. Technical focus areas are conversion of biomass to fuels and chemicals, carbon capture and utilization, energy efficient building technologies and renewable energy generation.

2009-2012: Program Manager – Transportation & Climate Change Technology, Southern Research
2003-2009 Sr. Project Leader, Environmental Engineer, Southern Research
1996-2003 Environmental Engineer, Bensinger & Garrison Environmental

PROJECT EXPERIENCE:
Mr. Hansen has executed several independent technology performance verifications of emerging carbon, energy and transportation technologies, as CEO of 350Solutions, Director of Energy & Environment at Southern Research, and Director of the U.S. EPA's Greenhouse Gas Technology Center. Mr. Hansen has completed clean technology evaluations for the Department of Defense, state energy agencies, commercial clients, investors, and technology developers, involving evaluation of commercial feasibility, economic and environmental impacts, and technology performance. Mr. Hansen served as the Measurement and Verification Program Lead for the NRG COSIA Carbon XPrize – a $20M prize competition for technologies that capture and beneficially utilize CO_2. Mr. Hansen also served as U.S. Technical Expert for the development and implementation of ISO 14034 – Environmental Technology Verification, an international standard, issued in 2016

Bill Chatterton
Senior Verification Scientist, 350Solutions

EDUCATION:
B.S. Environmental Science, SUNY at Plattsburgh, 1982
A.A.S. Environmental Technology, Paul Smith College, 1979
Certified Measurement and Verification Professional (CMVP), 2019

EXPERIENCE SUMMARY:
Mr. Chatterton has over 30 years of experience in management of energy and environmental technology development and demonstration projects and programs, as well as multimedia environmental engineering efforts. The majority of his recent work has focused on the evaluation of innovative carbon capture, utilization, and removal technologies. Mr. Chatterton has supported the development and management of large technology evaluation programs in the advanced energy, transportation, and climate change areas.

RESEARCH AND PROFESSIONAL EXPERIENCE:
2019-Present Sr Verification Scientist – 350Solutions, Inc.
Owns and operates a small cleantech engineering consulting business focused on the independent evaluation of new cleantech innovations and their impact on the environment and carbon emissions. Provides engineering consulting, testing and evaluation, techno-economic assessment, and other support to companies developing, using, or investing in new clean technology innovations. Manages administrative, business development, and project activities for 350Solutions.

2010-2019: Program Manager - Energy and Environment, Southern Research
Managed scientific and technical staff performing research, development, and evaluation of innovative clean energy technologies. Projects range from $25,000 to $6million in size, and are funded by the US Department of Energy, Department of Defense, and commercial partners. Technical focus areas are conversion of biomass to fuels and chemicals, carbon capture and utilization, energy efficient building technologies and renewable energy generation.

2000-2009 Sr. Project Leader, Environmental Engineer, Southern Research

PROJECT EXPERIENCE:
Mr. Chatterton has executed several independent technology performance verifications of emerging carbon, energy and transportation technologies for 350Solutions and previously at Southern Research Institute. Mr. Chatterton has completed clean technology evaluations for the Department of Defense, state energy agencies, commercial clients, investors, and technology developers, involving evaluation of commercial feasibility, economic and environmental impacts, and technology performance. Mr. Chatterton served as a Lead Verifier for the NRG COSIA Carbon XPrize – a $20M prize competition for technologies that capture and beneficially utilize CO_2. Mr. Chatterton is also a Certified Measurement and Verification Professional, issued in 2019.