Isometric Standard Project Verification Report

For

Charm Industrial

Client	Isometric
Company / GHG Removal Supplier	Charm Industrial
Facility or Project Name	Charm Bio-oil Geologic Storage
Facility Address	**Bio-oil Production:** AE Cote-Nord Canada Bioenergy Inc (AECN) Port Cartier, Quebec, Canada Charm Miniforge Fort Lupton, CO, USA **Bio-oil Pre-Processing:** Charm Industrial El Dorado, KS, USA **Bio-oil Injection:** Charm Industrial Evangeline Parish, LA, USA
Greenhouse Gas Statement ID/Gas Statement Version ID	ggs_1K7TCVRDH1S0XY5Z gss_1K7TCWX661S0HK1M
Net Greenhouse Gas Removals	291.85 tonnes CO_{2e}
Removal Method	Bio-oil Geological Storage
Removal Period	September 9-30, 2025
Verification Opinion	Positive (fully meets criteria)
Verifier/Validation and Verification Body	Tim Hansen Guy Hardwick 350Solutions, Inc.

ISSUED:

OCTOBER 31, 2025

CONTENTS

1. Key Project Data 3
1.1. Verification Summary 4
2. Verification & Storage Site Validation Details 6
2.1. Verification Objectives 6
2.2. Responsibilities 6
2.3. Level of Assurance & Materiality 6
2.4. Verification Team Details 6
2.5. Audit Process Followed 6
3. Technical Aspects 7
3.1. Project Details 7
3.2. Protocols and Modules Applied 8
3.3. Applicability of Applied Protocol and Modules 8
3.4. Project Boundary 8
3.5. Changes from Previous Verifications 9
3.6. Process & Data Irregularities During Reporting Period 9
4. Crediting Details 10
4.1. Project Reporting Period 10
4.2. Crediting Period 10
5. GHG Statement Verification & Storage Site Validation 10
5.1. Accuracy of the Statement 10
5.2. Verification Storage Site Validation Opinion 11
5.3. Verification & Storage Site Validation Results Summary 11
5.4. Verification & Storage Site Validation Findings 13
5.4.1. Critical Findings and Exceptions 13
5.4.2. Forward Action Requests & Recommendations 15
6. Revision History 17
Appendix 1: Documents Submitted for Review 19
Appendix 2: Verification Audit Findings and Responses 28
Appendix 3: Verifier Qualifications 31

ISOMETRIC STANDARD VERIFICATION REPORT		
Company: Charm Industrial	Company Contact: *Max Lavine	Validation and Verification Team: *Tim Hansen, PE Guy Hardwick
Removal Method: Bio-oil Geological Storage		
Report Date: October 31, 2025		
Document No: 350VR-Charm-ISO2504.08		
Rev: v1.2		

** Primary contact/lead author*

1. KEY PROJECT DATA

TABLE 1. VERIFICATION SUMMARY FOR CHARM INDUSTRIAL BIO-OIL STORAGE

Title	Charm Bio-Oil Geologic Storage
Location	Bio-oil Production: AE Cote-Nord Canada Bioenergy Inc (AECN) @ Produits Forestiers Arbec S.E.N.C., 175 Bd du Portage des Mousses Port-Cartier, QC G0W 1X0, Canada 50.025323, -66.818910 Charm Industrial Miniforge 2360 S Rollie Ave Fort Lupton, CO, USA 80621 40.076570, -104.804680 Bio-oil Pre-Processing: Charm Industrial 838 SW Purity Springs Rd El Dorado, KS 67042 37.813906, -96.914982 Bio-oil Injection & Storage: Charm Industrial Evangeline Parish, LA 30.916251, -92.297908
Reporting Period	September 9-30, 2025
Greenhouse Gas Statement ID	ggs_1K7TCVRDH1S0XY5Z gss_1K7TCWX661S0HK1M
Project Proponents	CDR Supplier: Charm Industrial Feedstock Supplier: Produits Forestiers Arbec S.E.N.C (Quebec mill waste supplier); Altitude Forestry (CO forestry fire prevention waste supplier) Geologic Storage Management: Charm Industrial Salt Cavern Storage Management (Prior Injections): Vaulted Deep Regulatory Agency (Injections / Storage): Louisiana Department of Energy & Natural Resources; Kansas Department of Health & Environment (KDHE) (Prior Injections)
Legal Ownership of the Credits	Charm Industrial
Removals in Reporting Period	291.85 tonnes

Removal Method	Bio-oil Geological Storage
Verification Report Date	October 31, 2025
Verification Type & Criteria	Isometric Standard Verification for ongoing deliveries of carbon removal credits by Charm Industrial in accordance with the documents used during project validation: • Isometric Standard v1.7 • Bio-oil Geological Storage Protocol v1.1 • Biomass Feedstock Accounting Module v1.2 • Bio-oil Storage in Permeable Reservoirs v1.1 • Embodied Emissions Accounting v1.0 • Energy Use Accounting v1.2 • Transportation Emissions Accounting v1.1

1.1. VERIFICATION SUMMARY

350Solutions was contracted to perform a project verification of the greenhouse gas (GHG) statement of Charm Industrial's bio-oil geological storage process for the referenced reporting period. The validation report for the Charm Kansas Bio-oil Geologic Storage project was completed on June 25, 2024, by Futurepast, which focused on the use of third-party produced bio-oils and was issued by Isometric for the Crediting Period March 1, 2024 – February 28, 2029. An additional validation of the Charm Kansas Bio-oil Geologic Storage project for use of bio-oil produced by Charm was completed on October 18, 2024, for the same crediting period. These validations remain valid for this verification reporting period. Further details and findings can be found in the validation report (https://registry.isometric.com/project/prj_1HZSSWBQM1S08H83#project-documentation). Validation of an additional injection and storage location in Evangeline Parish, Louisiana was completed in September, 2025 and is the injection and storage site for all injections during this reporting period, and storage site validation is included in the report located here: https://storage.googleapis.com/isometric--production--eu--public-documents/spl_1H31MW3T81S0R67B/prj_1HZSSWBQM1S08H83/pjd_1K5XPX61T1S0TM0Z/verification_report.pdf.

350Solutions affirms that Charm has the appropriate equipment, procedures, and protocols in place and is documented to quantify GHG removal through the injection of bio-oil into permeable reservoirs via a permitted Class V well in accordance with the requirements of the applicable Isometric standards, protocols and modules.

The carbon removals for the reporting period are provided in Table 2. These values have been verified by 350Solutions.

TABLE 2. VERIFIED TOTAL REMOVALS BY CHARM INDUSTRIAL FOR REPORTING PERIOD ENDING SEPTEMBER 30, 2025

Removal ID	Date removal started	Date removal completed	Discounted CO_2e net removed, rounded (kg)
rmv_1K7Q5S8PS1S0S6MW	2025-09-11	2025-09-11	26970
rmv_1K7Q5R4WR1S02BV0	2025-09-10	2025-09-10	28060
rmv_1K7Q5XMS01S0AF2A	2025-09-24	2025-09-24	29520
rmv_1K7Q608RS1S0QKXK	2025-09-09	2025-09-09	39070

rmv_1K7Q5PZX91S0QW5F	2025-09-30	2025-09-30	12640
rmv_1K7Q5WKD21S0KM8E	2025-09-23	2025-09-23	27360
rmv_1K7Q62VV51S0X7EG	2025-09-10	2025-09-10	13080
rmv_1K7Q5VEHB1S01TVK	2025-09-19	2025-09-19	27560
rmv_1K7Q5TAWB1S03PAD	2025-09-17	2025-09-17	29370
rmv_1K7Q5YWH31S0Q724	2025-09-25	2025-09-25	58220
TOTAL			291850

The quantity of **291.85 tonnes** of net carbon removals has been verified with a reasonable level of assurance and are eligible for crediting under the referenced Isometric Standard and Protocol.

350Solutions Inc. declares that it is an impartial verification body, approved by Isometric for verifications in the required technical area, free from any conflicts of interest, capable, and qualified to complete this verification for the current reporting period according to the *Isometric Standard v1.7, Bio-oil Geological Storage Protocol v1.1, Biomass Feedstock Accounting Module v1.2.1*, *Bio-oil Storage in Permeable Reservoirs Module v1.1, Embodied Emissions Accounting v1.0, Transportation Emissions Accounting v1.1,* and *Energy Use Accounting v1.2*.

Verifier Information		
Verification Body	**Verifier**	**Verification ID No.**
350Solutions, Inc.	Tim Hansen	VR-Charm-ISO2504.08

Timothy A. Hansen Digitally signed by Timothy A. Hansen Date: 2025.10.31 13:05:23 -04'00'

Signed: Tim Hansen (Verifier)

Guy Hardwick Digitally signed by Guy Hardwick Date: 2025.11.01 17:54:32 -04'00'

Guy Hardwick (QA)

2. VERIFICATION & STORAGE SITE VALIDATION DETAILS

2.1. VERIFICATION OBJECTIVES

A series of verification activities was conducted by 350Solutions to independently verify the claimed removals of the GHG statement submitted by Charm Industrial for operations conducted at the Charm Bio-oil Geologic Storage facility for the referenced Reporting Period. The verification was conducted following the specifications of the standards and protocols cited in Table 1.

2.2. RESPONSIBILITIES

The verification is based on the provision and fair presentation of a complete and accurate GHG Statement submitted by Charm Industrial to the Isometric registry. It is Charm's responsibility to ensure a fair, accurate, and complete presentation of the GHG Statement and Project Design Document are provided. This is confirmed and verified independently by 350Solutions based on supporting evidence in accordance with the Isometric criteria (Table 1, Section 3.2).

2.3. LEVEL OF ASSURANCE & MATERIALITY

The verification was conducted with a reasonable level of assurance. Any discrepancies between the claimed removals of the project and the removals estimated by the verification process for the reporting period are less than the materiality threshold of 5%.

2.4. VERIFICATION TEAM DETAILS

350Solutions is an accredited inspection & verification body by ANAB under ISO 17020:2012 for completion of ISO 14034:2016 Technology Verifications. 350Solutions is headquartered in Raleigh, North Carolina, USA. 350Solutions Technical Lead for the Charm verification is Tim Hansen. Mr. Hansen is a registered Professional Engineer with over 25 years of experience in the evaluation and verification of novel cleantech and carbon technologies. Mr. Hansen has led verifications of carbon removal technologies for multiple registries, including Isometric, and has experience in the development and testing of biomass conversion technologies, including gasification and pyrolysis. The verification report was provided QA by Guy Hardwick, a Carbon Removal Verification Engineer, with experience developing and verifying carbon removal technologies, including biochar and biomass terrestrial storage.

2.5. AUDIT PROCESS FOLLOWED

The specific verification and storage site validation activities conducted are summarized in Table 3. The list of all files that were reviewed is provided in Appendix 1. The list of findings from the verification can be found in Appendix 2. Audit results are documented using 350's Compliance Checklist, which includes all requirements from the Isometric standard, Bio-oil Geologic Storage protocol, and referenced modules.

TABLE 3. VERIFICATION & STORAGE SITE VALIDATION ACTIVITIES

Date(s)	Verification Activity	Verification Tasks	Documents Reviewed
October 18-30, 2025	Review of reporting period modifications and changes	• Review of GHG Statement and report and guidance from Charm	Final V 1.10 Charm Industrial Bio-Oil Geologic Storage PDD.docx gss_1K7TCWX661S0HK1M September 9th-30th Removals Isometric GHG Statement Report v1.6.docx VVB Findings.xlsx VVB Guidance Finalized.docx
October 28-30	Review of current Validation and GHG Statement Applicability	• Review of Validation Report • Review of prior Verification Report and findings • Identification of major and minor process steps, measurements, and calculations and changes in RP • Review of Standards/Protocols/Modules required for Verification • Generation of a checklist of verification issues and findings and opportunities for improvement	Validation_Report_for_Isometric_Charm_Industrial_Bio-Oil_Project_2024-06-25_r1 Isometric Standard Project Verification & Storage Site Validation Report For Charm Industrial (23Sep2025) gss_1K7TCWX661S0HK1M September 9th-30th Removals Isometric GHG Statement Report v1.6.docx VVB Findings.xlsx VVB Guidance Finalized.docx Isometric Standard v1.7, Bio-oil Geological Storage Protocol v1.1, Biomass Feedstock Accounting Module v1.2, Bio-oil Storage in Permeable Reservoirs Module v1.1, Embodied Emissions Accounting v1.0, Transportation Emissions Accounting v1.1, and Energy Use Accounting v1.2
October 28-30, 2025	Verification of Removals	• Verify changes to the system • Review of measurements and calculations • Review of durability/permit requirement monitoring data • Review of GHG statement • Identification of initial findings and follow-up request for information • Write verification report	File List provided in Appendix 1. Initial Findings in Appendix 2. Primary verification performed using Isometric Certify and supporting documentation (https://registry.isometric.com/account/certify/project/prj_1HZSSWBQM1S08H83/ghg-statement/ggs_1K7TCVRDH1S0XY5Z)

3. TECHNICAL ASPECTS

3.1. PROJECT DETAILS

Charm obtained bio-oil from two sources during this reporting period. Charm obtains bio-oil from a producer in Quebec, Canada (AECN) who uses an Ensyn/Honeywell UOP pyrolysis system to generate bio-oil from waste wood produced at a neighboring mill. In addition, Charm produces bio-oil at its pyrolysis facility in Fort Lupton, CO. Production of bio-oil for sequestration and carbon removal credit generation began in August of 2024, with the initial installation of four pyrolyzers, with plans for up to 18 pyrolyzers total to be installed. Charm's pyrolyzers utilize wood chips, placed into a high temperature pressurized reactor in a low oxygen environment to reduce the wood chips into a combination of products, including syngas and light hydrocarbon gases, pyrolysis oils, biochar, and wood vinegar. All hot pyrolysis gases from the reactor are quenched with water to produce the oil and wood vinegar products. Excess gases are routed to a combustion device for emissions control, with the heat produced from the combustion of excess gas utilized for drying the biomass from 40%-50% moisture content to 10% moisture content before introduction into the pyrolyzer.

Bio-oil from AECN and aqueous fraction product from Charm pyrolyzers are shipped by tanker truck, rail car, or tote tanks on flatbed to a Charm facility in El Dorado, Kansas. At this facility, Charm pretreats the bio-oil through the addition and sparging of liquid caustic soda (LCS) as needed to adjust the pH of the bio-oil and aqueous product to meet the requirements of the injection facility permit for storage in permeable reservoirs as specified by the Louisiana Department of Energy & Natural Resources (LDENR). Charm-produced bio-oil is not pretreated when injected at the Basco injection site in Louisiana.

Charm Bio-oil product and the treated AECN oil and Charm aqueous product are trucked to Charm's underground injection and storage facility located in Evangeline Parish, Louisiana for storage into a geologic reservoir. The bio-oil products are blended in on site storage tanks through recirculating pumps and injected as soon as practicable. Samples of the blended bio-oil are collected prior to injection and analyzed for bio-oil characteristics to ensure compliance with permit requirements. Charm also monitors all injection parameters as required by the Underground Injection Control (UIC) permit.

3.2. PROTOCOLS AND MODULES APPLIED

The verification was conducted following the specifications of the following standards, protocols, and modules:

- Isometric Standard v1.7 [1]
- Bio-oil Geological Storage Protocol v1.1 [2]
- Biomass Feedstock Accounting Module v1.2 [3]
- Bio-oil Storage in Permeable Reservoirs v1.1 [4]
- Embodied Emissions Accounting v1.0 [5]
- Energy Use Accounting v1.2 [6]
- Transportation Emissions Accounting v1.1 [7]

Charm utilizes Book and Claim Units (BCUs) to substitute for some, or all, or project diesel fuel usage and purchases Renewable Energy Certificates (RECs) for some or all its electricity consumption in accordance with the Isometric Energy Use and Transportation Modules.

3.3. APPLICABILITY OF APPLIED PROTOCOL AND MODULES

The Charm project takes mixed woody waste or forestry thinnings from wildfire prevention activities, converts it to bio-oil, which they pretreat and inject into geologic storage formations. The biomass feedstocks were assessed previously under the eligibility criteria of the Isometric Biomass Feedstock Module and were found to be eligible. As the biomass feedstocks have been validated as eligible biomass feedstocks, the storage of biomass conversion products (bio-oil) in a geologic formation makes both the Bio-oil Geological Storage Protocol and Bio-oil Storage in Permeable Reservoirs Module applicable to this project. All other modules for energy, transportation, and embodied emissions accounting are generally applicable to this project.

3.4. PROJECT BOUNDARY

The boundaries of the project include the supply of wood waste to the biomass processing sites (AECN and Charm Fort Lupton), the conversion of the biomass to bio-oil via AECN's pyrolysis process and Charm's pyrolysis process, transport of the bio-oil to Charm for preprocessing at its El Dorado, Kansas facility, completion of pretreatment, shipment to the Charm Louisiana injection and storage site, and injection of the bio-oil in the geologic reservoir. Monitoring and required analysis of the bio-oil and the storage formation are also included in the project boundary.

3.5. CHANGES FROM PREVIOUS VERIFICATIONS

Compared to prior verification (Reporting Period 01AUG-15AUG2025), no significant modifications were made to the Charm Industrial processes, data collection, and calculation procedures which have been specified in the GHG statement and supporting documentation. The following minor modifications and notes have been provided for clarity. All were reviewed and deemed acceptable under the Isometric requirements:

- Water is required for on-site R+D work at Charm's Colorado facility. Water usage for R&D is measured by filling 330 gallon totes at the beginning of each month. The total gallons used for R&D purposes (330 x number of totes) is deducted from the total volume for the month captured by the water flow meter and not accounted for within the project boundary. The remainder of water usage is allocated to production emissions.
- During September, well maintenance was performed by flushing the system with methanol. The GHG impact of solvent purchased for use on site is included in the Site Emissions for this reporting period using the current GREET emission factor for methanol. The approved permit from LDENR for the use of methanol and injection in the well was also provided. Results of a required mechanical integrity test after the well maintenance was also provided.
- Updated scale calibration certificates for all scales used to weigh bio-oil and biomass in CO and the truck scale AECN uses to weigh bio-oil in QC were provided with calibrations completed on schedule and meeting requirements.
- Updated Community Engagement documentation has been provided for this reporting period
- Requirements for monitoring records for prior injections at the Vaulted facility and the required monitoring frequency and submission timing are under discussion with Isometric as operations are moving to a post-injection monitoring plan and approach. Isometric has approved a delay in obtaining and submitting monitoring data for the Vaulted site during this transition period as all parties modify contractual requirements for ongoing monitoring and reporting.
- Note that Charm is continuing to transition additional parts of its reporting to the Isometric Certify platform. As this occurs, certain components may appear partially complete or incomplete in Certify. However, the data has been submitted separately from Certify and verified by 350 as compliant. For this reporting period, Monitoring and Feedstocks requirements are included in Certify, but entries appear incomplete. However, these items are fully addressed outside of Certify.

3.6. PROCESS & DATA IRREGULARITIES DURING REPORTING PERIOD

No significant data anomalies or irregularities occurred during the reporting period related to data collection and operations.

It should be noted that the ongoing monitoring required for prior injections at the salt cavern storage site in Kansas (Vaulted Deep) continues to be completed. However, the reporting schedule for such monitoring does not always align with the data submissions for current reporting periods. It is also not relevant to the crediting associated with the current reporting period.

Note that rounding and significant figure utilization in data collection and calculations may cause slight discrepancies in data reported, but any noted discrepancies are non-material and typically on the order of 1-2 kg.

4. CREDITING DETAILS

4.1. PROJECT REPORTING PERIOD

This verification considers injections of bio-oil (oil and aqueous phases) by Charm during the period September 9-30, 2025. The reporting period is based on the actual injection dates, with bio-oil production, transportation, monitoring, and related activities potentially occurring outside of this reporting period, but properly accounted for and allocated to the bio-oil injected within the reporting period.

4.2. CREDITING PERIOD

The 5-year crediting period for the Charm Kansas Bio-oil Geologic Sequestration Project began March 1, 2024, and continues for five years, ending February 28, 2029. All claimed removals in this reporting period fall within the current crediting period.

5. GHG STATEMENT VERIFICATION & STORAGE SITE VALIDATION

5.1. ACCURACY OF THE STATEMENT

The values represented in the GHG statement have been evaluated, cross-referenced with the presented evidence, and confirmed with no material misstatements nor critical errors.

Confirmation of the GHG statement has been based on the following efforts:

- Review and confirmation of calculations of total bio-oil and CO_2 equivalent injected and all process, operational, and embodied emissions, as well as all supporting evidence for the following removals:

Removal ID	Date Removal Started
rmv_1K7Q62VV51S0X7EG	2025-09-10
rmv_1K7Q5YWH31S0Q724	2025-09-25
rmv_1K7Q5PZX91S0QW5F	2025-09-30

- This includes for these removals:
  - Calculation of mass of bio-oil delivered and injected including tracing to raw data (weigh scale tickets, carbon content lab results, addition of consumables)
  - Confirmation of transportation distances for tanker and rail car deliveries from AECN to El Dorado, KS and to Basco site, LA, emission factors, and calculation of transportation emissions
  - Confirmation of weigh scale raw data for deliveries of bio-oil and injectate
  - Confirmation of raw data for fuel usage at Charm pre-treatment and injection facilities
  - Confirmation of electricity usage at Charm pretreatment and injection facilities

  - Confirmation of proper use and accounting of BCUs and RECs to offset diesel and electricity usage emissions, respectively
  - Review of Charm pyrolysis process emissions, supporting evidence, and calculations
- Review of monitoring data as required for Basco site injection (August and September monthly reports) and post injection monitoring to ensure compliance with Class V permit for Basco site
- Review of updated calibration certificates for weigh scales used by Charm at its CO and KS facilities and by AECN
- Review of methanol utilization and emissions calculations, including total methanol purchases, methanol embodied emissions factors, and calculations of total emissions

5.2. VERIFICATION STORAGE SITE VALIDATION OPINION

350Solutions has reviewed the documentation of the technology, the instrumentation, the procedures, performance and collected data and has found that the data presented in the greenhouse gas removal statement indicates that the claims fall within the 5% materiality threshold for greenhouse gas emissions and removals as required by the Isometric Standard:

☒ ***Meets the requirements of the Isometric Standard v1.7, Biomass Geological Storage Protocol v1.1, Biomass Feedstock Accounting Module v1.2, and Bio-oil Storage in Permeable Reservoirs Module v1.1 for Verification***

☐ ***Meets the requirements with minor revisions of Isometric Standard v1.7, Biomass Geological Storage Protocol v1.1, Biomass Feedstock Accounting Module v1.2, and Biomass or Bio-oil Storage in Salt Caverns Module v1.1 for Verification***

☐ ***Does Not Meet the requirements of the Isometric Standard v1.7, Biomass Geological Storage Protocol v1.1, Biomass Feedstock Accounting Module v1.2, and Biomass or Bio-oil Storage in Salt Caverns Module v1.1 for Verification***

5.3. VERIFICATION & STORAGE SITE VALIDATION RESULTS SUMMARY

A summary of verification results and compliance with relevant requirements of the *Isometric Standard, Biomass Geological Storage Protocol, Biomass Feedstock Accounting Module*, and *Bio-oil Storage in Permeable Reservoirs Module* are summarized below.

TABLE 4. VERIFICATION RESULTS SUMMARY

Isometric Standard Section Ref.	Verification Topic	Changed since Project Validation? (Y/N)	Final Findings
2.1.	*Validated against approved Protocols*	N	Acceptable – No additional changes since validation
2.5.1	*Boundaries*	N	Acceptable – No additional changes since validation
2.5.2	*Baseline*	N	Acceptable – No change since validation
2.5.3	*Additionality - Financial*	N	Acceptable – No change since validation
2.5.3	*Additionality – Environmental*	N	Acceptable – No change since validation
2.5.3	*Additionality – Regulatory*	N	Acceptable – No change since validation

Isometric Standard Section Ref.	Verification Topic	Changed since Project Validation? (Y/N)	Final Findings
2.5.4	*Leakage*	N	Acceptable – No change since validation and prior verification.
2.5.5	*Default Emission Factors, Proxies, and Models*	N	Acceptable – No additional significant changes were made since prior verifications. See Section 3.5 for summary of modifications to any calculation methods, all of which are acceptable.
2.5.11	*Life Cycle Assessment (LCA) Policies*	N	
2.5.6	*Common Calculation Factors*	N	
2.5.7	*Uncertainty*	N	
2.5.8	*Durability and Monitoring*	Y	All updated durability evidence and storage monitoring requirements validated to meet protocol requirements. Note that ongoing discussions with Isometric and Charm are occurring regarding frequency of Kansas storage site monitoring reports as the prior injections transition into a post-injection / closure monitoring phase with no Charm injections occurring. As a result, no monitoring reports were provided for the KS site during this period
2.5.9	*Risk of Reversal*	N	Acceptable – No additional changes since validation
2.5.10 ***3.7***	*Environmental and Socioeconomic Impacts*	N	Acceptable – No additional changes since validation.
3.1	*Ownership*	N	Acceptable – No change since validation
3.2	*Documentation*	Y	Acceptable – No additional changes since prior verification. All documentation properly updated for reporting period
3.3	*Eligibility*	Y (GHG Statement Updated)	Acceptable – Project registered with Isometric and reporting period GHG Statement properly submitted to Isometric dMRV Certify platform.
3.4	*Project Crediting*	Y (GHG Statement Updated)	Acceptable – New reporting period GHG Statement is complete and verified. Reporting period is within current validation crediting period.
3.5	*Stakeholder Input Process*	Y	Acceptable – Updated community engagement documentation provided documenting additional activities as well as grievances and responses.
3.6	*Regulatory Compliance*	Y (Required Monitoring Updated)	Required monitoring and reporting completed during reporting period. No additional compliance issues identified.
Biomass Feedstock Accounting Module			
2.1	*Eligibility Criteria for Market Leakage*	N	Acceptable – No change since prior feedstock validations
2.2	*Counterfactual Storage Eligibility*	N	Acceptable – No change since prior feedstock validations
2.3	*Dedicated Energy Feedstock Eligibility*	N	Acceptable – No change since prior feedstock validations
3.0	*Counterfactual Definition*	N	Acceptable – No change since prior feedstock validations
3.1	*Counterfactual Energy Definition*	N	Acceptable – No change since prior feedstock validations
3.2	*Counterfactual Replacement Definition*	N	Acceptable – No change since prior feedstock validations

TABLE 5. BASCO STORAGE SITE VERIFICATION SUMMARY

Isometric Standard Section Ref.	Verification Topic	Changed since Project Validation? (Y/N)	Final Findings
Bio-oil Storage in Permeable Reservoirs Module			
1.0	*Storage System Eligibility*	N	Acceptable – No change since validation
2.1	*Storage Reservoir – Permitting*	N	Acceptable – No change since validation
2.2	*Storage Reservoir – Capacity*	N	Acceptable – No change since validation
2.2	*Storage Reservoir – Integrity*	N	Acceptable – No change since validation
2.2	*Storage Reservoir – Integrity: Characterization*	N	Acceptable – No change since validation. An additional Mechanical Integrity Test was completed during the reporting period which met all criteria.
2.2	*Storage Reservoir Characterization – Temperature, pH, conductivity, density*	N	Acceptable – No change since validation
2.2	*Storage Reservoir Characterization – $d^{13}C$ analysis (where applicable)*	NA	Acceptable – Not required
2.3	*Storage Reservoir Integrity – Well Construction*	N	Acceptable – No change since validation
3.1.1	*Storage Reservoir Integrity – Injection operations*	Y	Acceptable – Updated monitoring data provided indicating no exceedances of permit limits
3.1.1	*Storage Reservoir Integrity – Injection operations – Sampling & Analysis*	Y	Acceptable – Updated sampling and analytical data provided indicating no exceedances of permit limits
1.0, 3.2	*Well Closure and Post Closure Requirements*	N	Acceptable – No change since validation
3.1.3	*Injection Pressure*	Y	Acceptable – Pressure is continuously monitored and reported quarterly (monitoring reports indicate full compliance)
3.1.2	*Mechanical Integrity*	Y	Acceptable – An additional Mechanical Integrity Test was completed during the reporting period which met all criteria.
3.1.3	*Volatile Gas Monitoring*	N	Acceptable – No change since validation
3.1.3	*Reversal Risk & Monitoring*	N	Acceptable – No change since validation
3.3.1	*Attribution of Reversals*	N	Acceptable – No change since validation

5.4. VERIFICATION & STORAGE SITE VALIDATION FINDINGS

5.4.1. CRITICAL FINDINGS AND EXCEPTIONS

Assessment of the greenhouse gas removal statement identified several initial findings (Appendix 2). All findings, primarily associated with missing supporting evidence, have been addressed and closed. Findings of note include the following:

TABLE 6. CRITICAL FINDINGS

ID No	Type	Finding / Issue	Supplier Response	Conclusion / Resolution

1	Clarification	The invoice for methanol has no units on it. The methanol injection spreadsheet indicates 1700 gallons of methanol was used. Can you provide invoices and calculations from invoice data to show this is the amount used?	An additional invoice for 1500 gal of Methanol has been added to the evidence package in Drive. We were advised by site management that an initial purchase of 100 gal had been made on a personal card and the purchaser did not receive a formal invoice, so an additional 100 gallons has been added to the total to ensure a complete accounting for consumables purchased by the project. We now have an account with the vendor so the issue with the initial 100 gallon purchase is not expected to recur	Complete. Additional information provided.
2	Clarification	The methanol emission factor was stated to be taken from GREET. However, our review of the emissions factors from GREET and EcoInvent indicates higher cradle to grave emissions factors for methanol. Can you clarify which factor was used (i.e. which pathway or feedstock) and provide documentation of the emission factor?	Yes -- The emission factor used is for "Methanol: Combined" in the MeOH_FTD tab of GREET. This shows 8138g GHGs associated with feedstock and 13321g GHGs associated with fuel per mmBtu in the "Energy Use, Water Consumption, and Total Emissions" table. In the spreadsheet calc, these values are summed and divided by 1000 to compute a kg CO2e/mmBtu factor, which is then converted to kg CO2e/gal based on the energy.gov mmBtu/gal constant.	Complete. Supporting information provided.
3	Omission	It does not appear that the BCU or RECs tracker sheets were properly updated for this reporting period. No data for this period is included on the REC GHG Statement tracer tab and the data entries after the last RP on the BCU GHG Statement tab has no dates and does not match the summary of BCU tCO2e that are in Certify (summed from all removals = 79.251 t CO2e for non-process diesel use). Please update the tracker sheets and review for any inconsistencies with Certify entries	The sheets have been updated to reflect this reporting period's use of BCUs and RECs. The sum of reductions in the reporting period as recorded on Certify is 79.161 -- I have added a list of the date and total reduction quantity for each removal in columns H and I of this sheet to confirm.	Complete
4	Omission - modified to FAR	Calibration certificate updates were provided for scales in use at Charm and at AECN. In addition to these, we request that the calibration certificates for the commercial scales used to provide the weigh tickets for deliveries are also provided. The commercial scale operator (CAT Scales) should be able to provide these certificates.	Each scale ticket provided notes that "This is to certify that the following described merchandise was weighed, counted, or measured by a public or deputy weighmaster, and when properly signed and sealed shall be prima facia evidence of the accuracy of the weight shown as prescribed by law". We have used these without issue so far, so have been operating under the understanding that this certification and signature of the weighmaster serves as sufficient evidence of the calibration and maintenance of the scale as required by law and satisfies the protocol requirement to provide calibration records for scales. If it is necessary to provide additional documentation, we are happy to discuss how to manage that, but	Adequate justification provided for current and potentially future reporting periods. Additional inquiries to commercial weigh scale operators being completed over next reporting period regarding availability of additional documentation.

			in light of the above we had no reason to assume that this was in the scope of the original request. That said, we will be happy to reach out to CAT scales to understand the process for requesting and receiving these records.	
5	Clarification	The density used in the MRV Ops Notes spreadsheets doesn't reflect the density from the lab testing. For example, for Batch 5-06, the density shows 1.22 kg/L, where the results show 1.092 kg/L. This does not impact the calculations, since they are based on weigh tickets, but is confusing and inconsistent.	This is a placeholder from a prior data collection and calculations. It's not serving any purpose at this point and can be deleted	Complete
6	Clarification	Please confirm that RECs were not used for the electricity consumption for Basco injection electricity use (removal X7EG) lists only grid emissions in Certify for B6 Injection site electricity emissions (RECs applied) category	Correct. RECs were not used for the LA injection site during this period	Complete

5.4.2. FORWARD ACTION REQUESTS & RECOMMENDATIONS

Forward action requests (FAR) and recommendations are also provided in Appendix 2 for consideration for improvement of future operations and GHG Removal Credit calculations and to ensure tracking of potential issues to be monitored by verifiers in future verifications. Open FARs and opportunities for improvement are summarized below for future verification reference:

TABLE 7. FORWARD ACTION REQUESTS AND RECOMMENDATIONS

ID No	Type	Finding / Issue	Supplier Response	Conclusion / Resolution
7	FAR (prior)	Please plan to provide updated documentation on community engagement and stakeholder input activities by 12/31/2025	2025/26 community engagement plans and a log of grievances and responses are included in the “2025 Comm Eng Docs” subfolder in the “Additional Documentation” folder	Updated Community engagement information provided, including activity plan for 2026. Complete and adequate for now, but will maintain as a forward action request to continue monitoring activity and development of additional community engagement documentation.
8	FAR (prior)	Please plan to provide updated documentation on grievance mechanism updates and any complaints/grievances received and responses (or confirmation of no issues) by 12/31/2025		Complete. Grievance mechanism and responses were provided. Will continue to monitor in future verifications

9	FAR (prior)	With injections no longer occurring at Vaulted, we would like to know how Charm will be notified of closure of the cavern where Charm oil was last injected, and to ensure that Charm will now be obtaining and submitting any post closure monitoring data to Isometric as part of the continued monitoring requirements. Please clarify that plans are in place for this and will be ongoing.	Charm has reached out to Vaulted on multiple occasions to get clarity regarding their future plans for the AR-09 injection well. The well still has considerable capacity and is the property of Vaulted, so it is up to them whether they plug and abandon the well or use it for their own emplacements. This decision on their part will affect the nature of the post-closure monitoring plan. We will continue to request clarity regarding these plans and, once received, we will define and submit a monitoring plan in light of the information we receive.	Modified to a FAR as ongoing discussions and post-closure monitoring plan requirements are evaluated with Isometric and Charm. Provide post-closure monitoring plan in near future as injections have now transitioned from Vaulted.
10	FAR (prior)	With injections no longer occurring at Vaulted, please provide updated contract for post-emplacement / post-closure management and monitoring and post-closure monitoring plan that documents how Charm will be notified of closure of the cavern where Charm oil was last injected, and to ensure that Charm will now be obtaining and submitting any post closure monitoring data to Isometric as part of the continued monitoring requirements or this storage location		Modified to a FAR as ongoing discussions and post-closure monitoring plan requirements are evaluated with Isometric and Charm. Provide evidence of contractual agreement with Vaulted regarding post-closure monitoring and responsibilities.

6. REVISION HISTORY

Original date of issue: October 30, 2025

Version	Date Issued	Noted Changes
v1.0 (Draft – Internal)	October 30, 2025	N/A Initial Version
v1.1 (Draft – External)	October 30, 2025	Minor edits from QA
v1.2 (FINAL)	October 31, 2025	Final Version – Minor Edits from Isometric and Charm; Closure of Findings List

References

[1] Isometric, “Isometric Standard v1.2.0.” Accessed: Feb. 19, 2025. [Online]. Available: https://registry.isometric.com/standard/1.2.0

[2] Isometric, “Bio-oil Geological Storage .1.1.” Accessed: Feb. 19, 2025. [Online]. Available: https://registry.isometric.com/protocol/bio-oil-geological-storage/1.1

[3] Isometric, “Biomass Feedstock Accounting .1.” Accessed: Feb. 19, 2025. [Online]. Available: https://registry.isometric.com/protocol/biomass-feedstock-accounting/1.1

[4] Isometric, “Biomass or Bio-oil Storage in Salt Caverns .0.4.” Accessed: Feb. 19, 2025. [Online]. Available: https://registry.isometric.com/protocol/salt-cavern-storage/1.0

[5] Isometric, “Embodied Emissions Accounting v1.0.3.” Accessed: Nov. 20, 2024. [Online]. Available: https://registry.isometric.com/protocol/embodied-emissions/1.0

[6] Isometric, “Energy Use Accounting v1.1.” Accessed: Nov. 20, 2024. [Online]. Available: https://registry.isometric.com/protocol/energy-use-accounting/1.1

[7] Isometric, “Transportation Emissions Accounting v1.1.” Accessed: Nov. 20, 2024. [Online]. Available: https://registry.isometric.com/protocol/transportation

See Appendix 1 and Table 3 for list of specific files reviewed during the verification.

APPENDIX 1: DOCUMENTS SUBMITTED FOR REVIEW

Name	File Category
Final V 1.10 Charm Industrial Bio-Oil Geologic Storage PDD.docx	**PDD**
gss_1K7TCWX 661S0HK1M	**GHG Statement**
September 9th-30th Removals Isometric GHG Statement Report v1.6.docx	\Additional Documentation\
VVB Findings.xlsx	\Additional Documentation\
VVB Guidance Finalized.docx	\Additional Documentation\
Charm Louisiana LLC_Order No. IMD 2025-05 EW_Response to Public Comments.pdf	\Additional Documentation\2025 Comm Eng Docs\
Evangeline Stakeholder Engagement_Fall 2025.docx	\Additional Documentation\2025 Comm Eng Docs\
Grievance Record_All Locations.xlsx	\Additional Documentation\2025 Comm Eng Docs\
Submitted Questions_ Charm Industrial Public Hearing July 17, 2025.docx	\Additional Documentation\2025 Comm Eng Docs\
AECN Calibration 3_25.pdf	\Additional Documentation\Updated Scale Calibration Certs\
Charm CO Calibration 8_25.pdf	\Additional Documentation\Updated Scale Calibration Certs\
Amended SN 974025 WP 46286.pdf	\Additional Documentation\Work Permits\
Basco Injection Site MRV	
Basco MIT 9.23.pdf	Basco Site MRV\
Charm_WoodVinegar_SDS.pdf	Basco Site MRV\August MRV Reporting\August-September 2025 LDENR Injection Reporting\
LDENR Injection Reporting _ Charm Sept 2025.xlsx	Basco Site MRV\August MRV Reporting\August-September 2025 LDENR Injection Reporting\
LDENR Injection Report_August 2025.xlsx	Basco Site MRV\August MRV Reporting\August-September 2025 LDENR Injection Reporting\
RTP™ Liquid RFO™ Biofuel Low Carbon Fuel Oil (LCFO) Fast Pyrolysis Bio Oil (FPBO) Biocrude - English (2023).pdf	Basco Site MRV\August MRV Reporting\August-September 2025 LDENR Injection Reporting\
Wet Oil _ Dry Oil (WO_DO).pdf	Basco Site MRV\August MRV Reporting\August-September 2025 LDENR Injection Reporting\
Wood Vinegar _ Quench Oil (WV_QO).pdf	Basco Site MRV\August MRV Reporting\August-September 2025 LDENR Injection Reporting\
Screenshot 2025-10-06 at 10.50.40 AM.png	Basco Site MRV\August MRV Reporting\Evidence of Reciept\August\
Screenshot 2025-10-06 at 10.50.58 AM.png	Basco Site MRV\August MRV Reporting\Evidence of Reciept\August\
Screenshot 2025-10-06 at 10.51.15 AM.png	Basco Site MRV\August MRV Reporting\Evidence of Reciept\August\
Screenshot 2025-10-17 at 3.20.48 PM.png	Basco Site MRV\August MRV Reporting\Evidence of Reciept\September\
Charm Bio-oil Production MRV	
September Deliveries.xlsx	Charm BO MRV\Charm BO Deliveries\
September 2025 Production Period Summary.xlsx	Charm BO MRV\Charm Production Docs\September 2025 Production Period\
September 2025 PP (9_1-9_30) Biomass Throughput.xlsx	Charm BO MRV\Charm Production Docs\September 2025 Production Period\Biomass Throughput\
September Miniforge Biomass Transport Allocation -- Updated.xlsx	Charm BO MRV\Charm Production Docs\September 2025 Production Period\Biomass Transport\

Diesel Consumption Calc 9_1_25-9_30_25.xlsx	Charm BO MRV\Charm Production Docs\September 2025 Production Period\Diesel\
9_10_25 (3).PDF	Charm BO MRV\Charm Production Docs\September 2025 Production Period\Diesel\Receipts\
9_1-9_30 Electricity Usage.xlsx	Charm BO MRV\Charm Production Docs\September 2025 Production Period\Electricity\
Electricity Data.csv	Charm BO MRV\Charm Production Docs\September 2025 Production Period\Electricity\
September 2025 Miniforge Electricity Consumption Calculator.xlsx	Charm BO MRV\Charm Production Docs\September 2025 Production Period\Electricity\
Cap Ex MRV September.xlsx	Charm BO MRV\Charm Production Docs\September 2025 Production Period\Embodied Emissions\
SP&C September.xlsx	Charm BO MRV\Charm Production Docs\September 2025 Production Period\Embodied Emissions\
Sept 2025 PP Gasoline Consumption Calculator.xlsx	Charm BO MRV\Charm Production Docs\September 2025 Production Period\Gasoline\
September 2025 Production Period Output Summary.xlsx	Charm BO MRV\Charm Production Docs\September 2025 Production Period\Output\
Biochar 20251006 CAR-410.pdf	Charm BO MRV\Charm Production Docs\September 2025 Production Period\Output\Testing\
QOWV 20251010 CAR-410.pdf	Charm BO MRV\Charm Production Docs\September 2025 Production Period\Output\Testing\
WODO 10062025.pdf	Charm BO MRV\Charm Production Docs\September 2025 Production Period\Output\Testing\
Propane Consumption Calculator 9_1_25-9_30_25.xlsx	Charm BO MRV\Charm Production Docs\September 2025 Production Period\Propane\
9_11_25 (1).PDF	Charm BO MRV\Charm Production Docs\September 2025 Production Period\Propane\Receipts\Bulk\
9_18_25.PDF	Charm BO MRV\Charm Production Docs\September 2025 Production Period\Propane\Receipts\Bulk\
9_3_25 (3).PDF	Charm BO MRV\Charm Production Docs\September 2025 Production Period\Propane\Receipts\Bulk\
9_10_25 (2).pdf	Charm BO MRV\Charm Production Docs\September 2025 Production Period\Propane\Receipts\Cylinders\
9_24_25.pdf	Charm BO MRV\Charm Production Docs\September 2025 Production Period\Propane\Receipts\Cylinders\
9_3_25 (2).pdf	Charm BO MRV\Charm Production Docs\September 2025 Production Period\Propane\Receipts\Cylinders\
Miniforge Pyrolysis Up-Time Reporting.xlsx	Charm BO MRV\Charm Production Docs\September 2025 Production Period\Pyrolysis Up-Time\
Up-Time Data 9_1-9_30.png	Charm BO MRV\Charm Production Docs\September 2025 Production Period\Pyrolysis Up-Time\
September 2025 PP (9_1-9_30) Vendor Delivery Emissions Calc Sheet.xlsx	Charm BO MRV\Charm Production Docs\September 2025 Production Period\Vendor Delivery Emissions\
Manifest_009511913SKS (22000).pdf	Charm BO MRV\Charm Production Docs\September 2025 Production Period\Waste Disposal\
Sept PP Waste Disposal Emissions Calc Sheet.xlsx	Charm BO MRV\Charm Production Docs\September 2025 Production Period\Waste Disposal\
SK Manifest(10,000).pdf	Charm BO MRV\Charm Production Docs\September 2025 Production Period\Waste Disposal\
September 2025 PP Water Usage Log.xlsx	Charm BO MRV\Charm Production Docs\September 2025 Production Period\Water\
Injection Lot Data	
RP Summary September 9th-30th.xlsx	Injection Lot Data\
2-104 Ops Notes.xlsx	Injection Lot Data\2-104\
KSLA-0010 Empty Weight LA.jpg	Injection Lot Data\2-104\Scale Tickets\

KSLA-0010 Full Weight LA.jpg	Injection Lot Data\2-104\Scale Tickets\
BATCH 2-104 (1).pdf	Injection Lot Data\2-104\Testing\
2-107 Ops Notes.xlsx	Injection Lot Data\2-107\
KSLA-0014 Empty (2).jpg	Injection Lot Data\2-107\Scale Tickets\
KSLA-0014 Full weight (1).jpg	Injection Lot Data\2-107\Scale Tickets\
BATCH 2-105, 2-106, 2-107 AECN (1).pdf	Injection Lot Data\2-107\Testing\
2-108 Ops Notes.xlsx	Injection Lot Data\2-108\
KSLA-0015 empty.PNG	Injection Lot Data\2-108\Scale Tickets\
KSLA-0015 Full (1).png	Injection Lot Data\2-108\Scale Tickets\
Batch 2-108, 2-109, 2-110, 2-111 (1).pdf	Injection Lot Data\2-108\Testing\
2-109 Ops Notes.xlsx	Injection Lot Data\2-109\
KSLA-0016 Empty.jpg	Injection Lot Data\2-109\Scale Tickets\
KSLA-0016 Full.jpg	Injection Lot Data\2-109\Scale Tickets\
Batch 2-108, 2-109, 2-110, 2-111 (1).pdf	Injection Lot Data\2-109\Testing\
2-110 Ops Notes.xlsx	Injection Lot Data\2-110\
KSLA-0017 empty (1).jpg	Injection Lot Data\2-110\Scale Tickets\
KSLA-0017 full (1).jpg	Injection Lot Data\2-110\Scale Tickets\
Batch 2-108, 2-109, 2-110, 2-111 (1).pdf	Injection Lot Data\2-110\Testing\
2-111 Ops Notes.xlsx	Injection Lot Data\2-111\
KSLA-0018 empty_ (2).jpg	Injection Lot Data\2-111\Scale Tickets\
KSLA-0018 full (2).jpg	Injection Lot Data\2-111\Scale Tickets\
Batch 2-108, 2-109, 2-110, 2-111 (1).pdf	Injection Lot Data\2-111\Testing\
2-112 Ops Notes.xlsx	Injection Lot Data\2-112\
KSLA-0019 Empty (1).jpg	Injection Lot Data\2-112\Scale Tickets\
KSLA-0019 Full (1).jpg	Injection Lot Data\2-112\Scale Tickets\
Batch 2-112, 2-113.pdf	Injection Lot Data\2-112\Testing\
2-113 Ops Notes.xlsx	Injection Lot Data\2-113\
KSLA-0020 Empty (1).jpg	Injection Lot Data\2-113\Scale Tickets\
KSLA-0020 Full (1).jpg	Injection Lot Data\2-113\Scale Tickets\
KSLA-0021 Empty (1).jpg	Injection Lot Data\2-113\Scale Tickets\
KSLA-0021Full (2).jpg	Injection Lot Data\2-113\Scale Tickets\
Batch 2-112, 2-113.pdf	Injection Lot Data\2-113\Testing\
3-45 Charm Contents.xlsx	Injection Lot Data\3-45\
3-45 Ops Notes.xlsx	Injection Lot Data\3-45\
KSLA-006 Empty Weight (1).jpg	Injection Lot Data\3-45\Scale Tickets\
KSLA-006 LA Full Weight (2).jpg	Injection Lot Data\3-45\Scale Tickets\
KSLA-008 Empty Weight LA (2).png	Injection Lot Data\3-45\Scale Tickets\
KSLA-008 Full Weight LA (2).jpg	Injection Lot Data\3-45\Scale Tickets\
BATCH 5-05 3-45 (1).pdf	Injection Lot Data\3-45\Testing\
5-06 Charm Contents.xlsx	Injection Lot Data\5-06\
5-06 Ops Notes.xlsx	Injection Lot Data\5-06\

KSLA 0011 Empty WT (1).jpg	Injection Lot Data\5-06\Scale Tickets\
KSLA-0012LA empty (1).jpg	Injection Lot Data\5-06\Scale Tickets\
KSLA-0012LA FULL.jpg	Injection Lot Data\5-06\Scale Tickets\
KSLA-0023 Empty.jpg	Injection Lot Data\5-06\Scale Tickets\
KSLA-0023 Full (1).jpg	Injection Lot Data\5-06\Scale Tickets\
KSLA-0024 Empty (1).JPG	Injection Lot Data\5-06\Scale Tickets\
KSLA-0024 Full (1).jpg	Injection Lot Data\5-06\Scale Tickets\
KSLA0011 Full WT-70820 (1).jpg	Injection Lot Data\5-06\Scale Tickets\
AECN 3-46 AECN 3-47 AECN 3-48 BATCH 5-06.pdf	Injection Lot Data\5-06\Testing\
BOL 2245-T pickup 8.27 (1).pdf	Injection Lot Data\AECN BOLs\
BOL 2208-T pickup 7.24 (1).pdf	Injection Lot Data\AECN BOLs\
BOL 2209-T pickup 7.24 (1).pdf	Injection Lot Data\AECN BOLs\
BOL 2211-T pickup 7.29 (1).pdf	Injection Lot Data\AECN BOLs\
BOL 2212-T pickup 8.10 (1).pdf	Injection Lot Data\AECN BOLs\
BOL 2213-T pickup 8.12 (1).pdf	Injection Lot Data\AECN BOLs\
BOL 2216-T pickup 8.16 (1).pdf	Injection Lot Data\AECN BOLs\
BOL 2217-T pickup 8.17 (1).pdf	Injection Lot Data\AECN BOLs\
BOL 2219-T pickup 8.19 (1).pdf	Injection Lot Data\AECN BOLs\
BOL 2220-T pickup 8.20 (1).pdf	Injection Lot Data\AECN BOLs\
BOL 2221-T pickup 8.20 (1).pdf	Injection Lot Data\AECN BOLs\
BOL 2225-T pickup 8.21 (1).pdf	Injection Lot Data\AECN BOLs\
Site Emissions - Basco Injection & KS Pre Processing	
9_9_25-9_30_25 Diesel Consumption Calcs.xlsx	Site Emissions\Basco Injection\Diesel\
Basco Electricity Usage 9_9_25-9_30_25.xlsm	Site Emissions\Basco Injection\Electricity\
Basco 6 + KS Embodied Emissions Inventory (4).xlsx	Site Emissions\Basco Injection\Embodied Emissions\
9_9_25-9_30_25 Gasoline Tracker LA (1).xlsx	Site Emissions\Basco Injection\Gasoline\
9_10_25 (1).png	Site Emissions\Basco Injection\Gasoline\Receipts\
9_26_25 (1).pdf	Site Emissions\Basco Injection\Gasoline\Receipts\
INVOICE_9125.pdf	Site Emissions\Basco Injection\Methanol Flush\
Methanol Flush Impact (1).xlsx	Site Emissions\Basco Injection\Methanol Flush\
Methanol Invoice (2).pdf	Site Emissions\Basco Injection\Methanol Flush\
Basco Support Travel Calc Sheet 9_8-9_30 (2).xlsx	Site Emissions\Basco Injection\Support Travel\
Alexandria to B6 Distance.png	Site Emissions\Basco Injection\Support Travel\Measurements and Distances\
BTR to Alexandria Distance.png	Site Emissions\Basco Injection\Support Travel\Measurements and Distances\
BTR to Lafayette Distance.png	Site Emissions\Basco Injection\Support Travel\Measurements and Distances\
Denver to BTR Round Trip.png	Site Emissions\Basco Injection\Support Travel\Measurements and Distances\
Lafayette to Basco Well Site.png	Site Emissions\Basco Injection\Support Travel\Measurements and Distances\
SFO to BTR Round Trip.png	Site Emissions\Basco Injection\Support Travel\Measurements and Distances\

Wichita to BTR Round Trip.png	Site Emissions\Basco Injection\Support Travel\Measurements and Distances\
Sept Brine Flow (1).xlsx	Site Emissions\Basco Injection\Water-Brine\
9_9-9_30 Diesel Consumption Calcs.xlsx	Site Emissions\KS Pre Processing\Diesel\
Usage_Electricity_Charm_Industrial_INC_20251002_154328.xlsx	Site Emissions\KS Pre Processing\Electricity\
9_9-9_30 Gasoline Tracker KS.xlsx	Site Emissions\KS Pre Processing\Gasoline\
9_10_25.jpg	Site Emissions\KS Pre Processing\Gasoline\Receipts\
9_11_25.jpg	Site Emissions\KS Pre Processing\Gasoline\Receipts\
9_16_25.jpg	Site Emissions\KS Pre Processing\Gasoline\Receipts\
9_23_25.jpg	Site Emissions\KS Pre Processing\Gasoline\Receipts\
9_9-9_30 LCS Consumption Sheet.xlsx	Site Emissions\KS Pre Processing\LCS\
Isometric Certify Source Files	
ggs_1K7TCVRDH1S0XY5Z-sources.zip	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K36Y2T6A1S0MYR9_KS_Electricity_Calcs.png	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K36Y2YSX1S0J5NH_KS_Electricity_Calcs.png	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K36Z8JC91S099MT_GLEC_NA_Fuel_Energy.png	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K370M1Z51S076JY_GLEC_NA_Fuel_Energy.png	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K371H3W11S0BQ7G_LA_Grid_Emissions.png	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K37244EA1S0DESA_LA_Water_Transport_Emissions.png	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K3729JS71S07WKT_GLEC_NA_Fuel_Energy.png	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K39DSZWT1S0T93V_GLEC_NA_Road_Transport.png	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K39DWK2E1S0G69S_GLEC_NA_Road_Transport.png	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K39E29BY1S0W0NN_Truck_Embodied_Emissions.png	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K39E4ZYC1S07V1H_Truck_Embodied_Emissions.png	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J7C2WZ1S0MEZK_AECN_Process_Emissions_Calculation.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J7C5MZ1S0HNWV_AECN_Process_Emissions_Calculation.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J7C8Q71S0REVP_GLEC_NA_Road_Transport.png	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J7CB411S0NNRY_GLEC_NA_Road_Transport.png	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J7CCHV1S0497J_Screenshot_2025-09-12_at_11.30.31_AM.png	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J7CFVH1S01G4T_Truck_Embodied_Emissions.png	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J7CHRD1S0B26D_Truck_Embodied_Emissions.png	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J7CN281S0MM80_Screenshot_2025-09-12_at_11.31.48_AM.png	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J7CS011S0M3FH_Screenshot_2025-09-12_at_11.32.18_AM.png	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J7CTG51S07RB6_2-113_Ops_Notes.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J7CWVA1S0TWEC_Batch_2-112__2-113.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J7CXP71S0EHA1_2-113_Ops_Notes.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J7CY8N1S0265P_KSLA-0020_Full.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J7CZPB1S0NV1B_KSLA-0021_Empty.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J7D16J1S09FX0_KSLA-0021Full.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\

src_1K7J7D2E11S0X4RN_KSLA-0020_Empty.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J83AQY1S0EJNE_2-112_Ops_Notes.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J83DRX1S01PRM_KSLA-0019_Full.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J83FJZ1S0NBM9_Batch_2-112__2-113.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J83GEM1S090FY_2-112_Ops_Notes.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J83H8F1S0WNBK_KSLA-0019_Empty.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J87HZC1S0PEGM_2-111_Ops_Notes__1_.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J87MX41S09JKT_KSLA-0018_empty___1_.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J87P3N1S0X7FF_KSLA-0018_full__1_.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J87QDF1S0GWB4_2-111_Ops_Notes.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J87R2V1S04H6S_Batch_2-108__2-109__2-110__2-111__1_.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8ASEP1S0YABT_2-110_Ops_Notes.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8AW7Y1S0HEF0_KSLA-0017_empty.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8AXJC1S053AN_Batch_2-108__2-109__2-110__2-111.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8AYE91S0RR6A_KSLA-0017_full.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8AZSV1S0CD1Z_2-110_Ops_Notes.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8D7XB1S0DFYA_2-109_Ops_Notes.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8DAY01S00M1G_Batch_2-108__2-109__2-110__2-111.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8DBMN1S0M8X5_2-109_Ops_Notes.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8DC8H1S07XRT_KSLA-0016_Full.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8DE0J1S0VJMF_KSLA-0016_Empty.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8F5QT1S0WNGT_2-108_Ops_Notes.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8FA2M1S0FSM0_2-108_Ops_Notes.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8WZR81S0VS89_Batch_2-108__2-109__2-110__2-111.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8X0EQ1S0FE3Y_KSLA-0015_empty.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8YNTW1S0GH09_2-104_Ops_Notes__1_.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8YRDS1S03N3F_2-104_Ops_Notes.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8YS0G1S0Q9Z4_BATCH_2-104__1_.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8YSW31S0AYTS_KSLA-0010_Empty_Weight_LA__1_.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8YVB71S0YKPE_KSLA-0010_Full_Weight_LA__1_.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8YX8Q1S085R1_ks_electricity_calc.png	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8YYYF1S0PS6N_Usage_Electricity_Charm_Industrial_INC_20251002_154328.csv	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8Z26T1S0EYPW_DD8B42D3-C1F1-4C18-B38D-F99201572185.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8Z3GC1S02KJH_CCAD000A-EFD6-4296-BAB6-014B4E7D5D2F.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8Z5BG1S09X9V_5B08C946-FE58-4144-AE6F-25E1C1D52D08.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8Z70K1S0H715_13DD49A4-D08A-47E5-AD1A-03A84AFB9A27.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\

src_1K7J8Z8AX1S0RGRF_DD8B42D3-C1F1-4C18-B38D-F99201572185.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8ZDDQ1S0QF7H_src_1K3RPXAS01S0W0MG_LCS_Emissions_Calc_Sheet.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8ZG761S08B0E_Basco_6___KS_Embodied_Emissions_Inventory__2_.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8ZN391S0F3Z9_9_26_25.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8ZQ081S0PDPK_9_10_25.png	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8ZSGS1S0ZZR6_Basco_6_PDD_-_Electricity_Consumption_Model.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8ZTNJ1S0EK6T_Usage_210003486813__6_.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8ZWD01S0BT42_Water_Transport_Calc_Sheet.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J8ZXH51S0TDJP_Sept_Brine_Flow.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J903DQ1S03EVT_Basco_Support_Travel_Calc_Sheet_9_8-9_30.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J922441S06ZAV_2-107_Ops_Notes.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J925B11S0T3E1_2-107_Ops_Notes.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J9265R1S0DR9P_BATCH_2-105__2-106__2-107_AECN.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J927001S01D5B_KSLA-0014_Empty.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J9284D1S0N210_KSLA-0014_Full_weight.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J942XG1S0ZPYY_3-45_Ops_Notes.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J945Q71S0JV24_3-45_Ops_Notes.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J946BJ1S06FXS_KSLA-006_LA_Full_Weight.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J947XG1S0T4SE_KSLA-006_Empty_Weight.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J949CY1S0DSN3_KSLA-008_Full_Weight_LA.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J94AXJ1S0N3CD_KSLA-008_Empty_Weight_LA.png	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7J94CBE1S08R82_BATCH_5-05__3-45__1_.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PQYDW91S0M21C_Screenshot_2025-10-15_at_2.28.45_PM.png	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PQYZ1S1S08CXX_KSLA0011_Full_WT-70820__1_.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PQZ0NJ1S0W1SJ_5-06_Ops_Notes__3_.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PQZ1VE1S0FPN7_KSLA_0011_Empty_WT__1_.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PQZ3BQ1S03BGW_5-06_Ops_Notes__3_.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PQZ45S1S0Q0CH_KSLA-0012LA_FULL.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PQZ7EH1S07W5E_KSLA0011_Full_WT-70820.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PQZ90W1S0VH13_KSLA-0012LA_FULL.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PQZA9C1S0F5WR_KSLA_0011_Empty_WT.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PQZC4P1S02TRD_Testing_-_AECN_3-46_AECN_3-47_AECN_3-48_BATCH_5-06.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PQZCSS1S0PFM2_KSLA-0023_Empty.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PQZE001S0A4FQ_KSLA-0023_Full.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PQZF6X1S0XSBC_KSLA-0024_Empty.JPG	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PQZGAY1S0HE71_KSLA-0024_Full.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PQZHJJ1S0532P_5-06_Ops_Notes.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PQZJCE1S0RQYB_KSLA-0012LA_empty__1_.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\

src_1K7PRCM841S04QJM_BOL_2211-T_pickup_7.29_.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PRDPA11S0QG5R_3-45_Charm_Contents.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PRHBPM1S0KCCN_BOL_2212-T_pickup_8.10.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PRHD8D1S0718A_BOL_2213-T_pickup_8.12.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PRQ4C81S0BD0M_9_9_25-9_30_25_Gasoline_Tracker_LA.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PRQCBZ1S0EW48_Water_Transport_Calc_Sheet.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PRQK7K1S0Z74P_Methanol_Flush_Impact.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PRQM0M1S0JW0B_Methanol_Invoice__1_.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PRTAZJ1S021JV_BOL_2216-T_pickup_8.16.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PRV7371S0SVK0_KSLA-0015_Full_.png	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PRYNVA1S0XJ9P_BOL_2217-T_pickup_8.17.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PS2MFF1S0VBAT_BOL_2219-T_pickup_8.19.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PS78A11S0AGXA_BOL_2220-T_pickup_8.20.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PSAYEQ1S0A6RN_BOL_2221-T_pickup_8.20.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PSKJ361S097YH_KSLA-0012LA_empty__1_.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PSKKCZ1S0WWT6_KSLA-0023_Full__1_.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PSKMWC1S0GHNV_KSLA-0023_Empty.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PSKQCA1S0QVD5_KSLA-0024_Empty__1_.JPG	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7PSKRFM1S0BG8T_KSLA-0024_Full__1_.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7Q5Z1R11S0JD85_BOL_2208-T_pickup_7.24_.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7Q9A5S61S0KA90_Charm-A2-2024-10-24-63-1976.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7Q9DN051S097EY_Charm-A2-2024-10-24-63-1976.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7Q9F5MQ1S0JSGH_Charm-A2-2024-10-24-63-1976.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7Q9SA931S08PPF_Charm-A2-2024-10-24-64-1976.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7Q9WMFR1S0YKWD_Charm-A2-2024-10-24-64-1976.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7Q9XGYB1S0MH2B_Charm-A2-2024-10-24-64-1976.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7Q9XZ7X1S0AE89_LCS_Emissions_Calc_Sheet.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7Q9YBB51S00BE7_Charm-A2-2024-10-24-64-1976.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7QBXPT61S0VF9K_5-06_Charm_Contents__1_.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7QDSNW31S0EKCS_Charm-A2-2024-10-24-64-1976.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7QDV1WG1S04GJQ_Charm-A2-2024-10-24-64-1976.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7QDWD7M1S0TDRN_Charm-A2-2024-10-24-64-1976.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7QEC7BP1S0Q3XE_Mangrove___Certify_Lot_QC_Checklist_-_3-45_Transport_EE_Evidence.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7QEG8KF1S0XWW9_Mangrove___Certify_Lot_QC_Checklist_-_2-107_Transport_EE_Evidence__1_.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7QFFMJP1S0TBT5_BOL_2209-T_pickup_7.24.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7QFFMZX1S0E0NT_BOL_2208-T_pickup_7.24_.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\

src_1K7QFH66K1S08Z8S_BOL_2209-T_pickup_7.24.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7QFHTWZ1S0G903_BOL_2208-T_pickup_7.24_.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7QFHV4C1S03XVR_BOL_2209-T_pickup_7.24.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7QG3CKP1S0F7F5_Mangrove___Certify_Lot_QC_Checklist_-_2-104_Transport_EE_Evidence.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7QG64C91S0CECD_Mangrove___Certify_Lot_QC_Checklist_-_2-108_Transport_EE_Evidence.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7QG7B771S02BJB_Mangrove___Certify_Lot_QC_Checklist_-_2-109_Transport_EE_Evidence.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7QG8ARN1S0R8R9_Mangrove___Certify_Lot_QC_Checklist_-_2-110_Transport_EE_Evidence.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7QG9JMY1S094H6_Mangrove___Certify_Lot_QC_Checklist_-_2-111_Transport_EE_Evidence.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7QGAREW1S0Z1Q4_Mangrove___Certify_Lot_QC_Checklist_-_2-112_Transport_EE_Evidence.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7QGC0BX1S0MYX2_Mangrove___Certify_Lot_QC_Checklist_-_2-113_Transport_EE_Evidence.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7QMXG631S0BG5C_Kansas_Operations_Inventory__1___1_.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7QN01EH1S00BTC_9_9-9_30_Gasoline_Tracker_KS.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7QNSZCE1S0G34K_KSLA-0015_Full_.png	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7QNT04P1S03R08_KSLA-0015_empty.jpg	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7QP7MJ41S00D5S_BOL_2208-T_pickup_7.24_.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7QP7MS41S0M21E_BOL_2209-T_pickup_7.24.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7QPATZ61S0C7HN_3-45_Ops_Notes.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7QPDMTA1S0AN88_3-45_Ops_Notes.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7SCWXST1S0W2Y3_2-108_Ops_Notes.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7SDAVN51S0KQNV_2-108_Ops_Notes.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7SDBCJ41S09MVS_2-108_Ops_Notes.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7SW5XTT1S0PJ40_BOL__2245-T_pickup_8.27__1_.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7SW5Y5A1S0A6ZN_BOL_2225-T_pickup_8.21__1_.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7SW77T31S0BDS0_BOL_2225-T_pickup_8.21__1_.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7SW77TG1S0Z2MN_BOL__2245-T_pickup_8.27__1_.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7SW8ASJ1S0W9HX_BOL__2245-T_pickup_8.27__1_.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7SW8B3W1S0FYDJ_BOL_2225-T_pickup_8.21__1_.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7SW948D1S0J6QV_BOL__2245-T_pickup_8.27__1_.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7SW94JX1S05VKG_BOL_2225-T_pickup_8.21__1_.pdf	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7SXDNCP1S0AHGF_5-06_Charm_Contents__1_.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7SXE7PK1S0CSTR_5-06_Charm_Contents__1_.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7SXEQS11S0M3J2_5-06_Charm_Contents__1_.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\
src_1K7SXFB9J1S0VD9C_5-06_Charm_Contents__1_.xlsx	\ggs_1K7TCVRDH1S0XY5Z-sources\

APPENDIX 2: VERIFICATION AUDIT FINDINGS AND RESPONSES

ID No	Type	Finding / Issue	Supplier Response	Conclusion / Resolution
1	Clarification	The invoice for methanol has no units on it. The methanol injection spreadsheet indicates 1700 gallons of methanol was used. Can you provide invoices and calculations from invoice data to show this is the amount used?	An additional invoice for 1500 gal of Methanol has been added to the evidence package in Drive. We were advised by site management that an initial purchase of 100 gal had been made on a personal card and the purchaser did not receive a formal invoice, so an additional 100 gallons has been added to the total to ensure a complete accounting for consumables purchased by the project. We now have an account with the vendor so the issue with the initial 100 gallon purchase is not expected to recur	Complete. Additional information provided.
2	Clarification	The methanol emission factor was stated to be taken from GREET. However, our review of the emissions factors from GREET and EcoInvent indicates higher cradle to grave emissions factors for methanol. Can you clarify which factor was used (i.e. which pathway or feedstock) and provide documentation of the emission factor?	Yes -- The emission factor used is for "Methanol: Combined" in the MeOH_FTD tab of GREET. This shows 8138g GHGs associated with feedstock and 13321g GHGs associated with fuel per mmBtu in the "Energy Use, Water Consumption, and Total Emissions" table. In the spreadsheet calc, these values are summed and divided by 1000 to compute a kg CO2e/mmBtu factor, which is then converted to kg CO2e/gal based on the energy.gov mmBtu/gal constant.	Complete. Supporting information provided.
3	Omission	It does not appear that the BCU or RECs tracker sheets were properly updated for this reporting period. No data for this period is included on the REC GHG Statement tracer tab and the data entries after the last RP on the BCU GHG Statement tab has no dates and does not match the summary of BCU tCO2e that are in Certify (summed from all removals = 79.251 t CO2e for non-process diesel use). Please update the tracker sheets and review for any inconsistencies with Certify entries	The sheets have been updated to reflect this reporting period's use of BCUs and RECs. The sum of reductions in the reporting period as recorded on Certify is 79.161 -- I have added a list of the date and total reduction quantity for each removal in columns H and I of this sheet to confirm.	Complete

4	Omission - modified to FAR	Calibration certificate updates were provided for scales in use at Charm and at AECN. In addition to these, we request that the calibration certificates for the commercial scales used to provide the weigh tickets for deliveries are also provided. The commercial scale operator (CAT Scales) should be able to provide these certificates.	Each scale ticket provided notes that "This is to certify that the following described merchandise was weighed, counted, or measured by a public or deputy weighmaster, and when properly signed and sealed shall be prima facia evidence of the accuracy of the weight shown as prescribed by law". We have used these without issue so far, so have been operating under the understanding that this certification and signature of the weighmaster serves as sufficient evidence of the calibration and maintenance of the scale as required by law and satisfies the protocol requirement to provide calibration records for scales. If it is necessary to provide additional documentation, we are happy to discuss how to manage that, but in light of the above we had no reason to assume that this was in the scope of the original request. That said, we will be happy to reach out to CAT scales to understand the process for requesting and receiving these records.	Adequate justification provided for current and potentially future reporting periods. Additional inquiries to commercial weigh scale operators being completed over next reporting period regarding availability of additional documentation.
5	Clarification	The density used in the MRV Ops Notes spreadsheets doesn't reflect the density from the lab testing. For example, for Batch 5-06, the density shows 1.22 kg/L, where the results show 1.092 kg/L. This does not impact the calculations, since they are based on weigh tickets, but is confusing and inconsistent.	This is a placeholder from a prior data collection and calculations. It's not serving any purpose at this point and can be deleted	Complete
6	Clarification	Please confirm that RECs were not used for the electricity consumption for Basco injection electricity use (removal X7EG) lists only grid emissions in Certify for B6 Injection site electricity emissions (RECs applied) category	Correct. RECs were not used for the LA injection site during this period	Complete
7	FAR (prior)	Please plan to provide updated documentation on community engagement and stakeholder input activities by 12/31/2025	2025/26 community engagement plans and a log of grievances and responses are included in the “2025 Comm Eng Docs” subfolder in the “Additional Documentation” folder	Updated Community engagement information provided, including activity plan for 2026. Adequate for now, but will maintain as a forward action request to continue monitoring activity and development of additional community engagement documentation.
8	FAR (prior)	Please plan to provide updated documentation on grievance mechanism updates and any complaints/grievances received and responses (or confirmation of no issues) by 12/31/2025	.	Complete. Grievance mechanism and responses were provided. Will continue to monitor in future verifications

9	FAR (prior)	With injections no longer occurring at Vaulted, we would like to know how Charm will be notified of closure of the cavern where Charm oil was last injected, and to ensure that Charm will now be obtaining and submitting any post closure monitoring data to Isometric as part of the continued monitoring requirements. Please clarify that plans are in place for this and will be ongoing.	Charm has reached out to Vaulted on multiple occasions to get clarity regarding their future plans for the AR-09 injection well. The well still has considerable capacity and is the property of Vaulted, so it is up to them whether they plug and abandon the well or use it for their own emplacements. This decision on their part will affect the nature of the post-closure monitoring plan. We will continue to request clarity regarding these plans and, once received, we will define and submit a monitoring plan in light of the information we receive.	Modified to a FAR as ongoing discussions and post-closure monitoring plan requirements are evaluated with Isometric and Charm. Provide post-closure monitoring plan in near future as injections have now transitioned from Vaulted.
10	FAR (prior)	With injections no longer occurring at Vaulted, please provide updated contract for post-emplacement / post-closure management and monitoring and post-closure monitoring plan that documents how Charm will be notified of closure of the cavern where Charm oil was last injected, and to ensure that Charm will now be obtaining and submitting any post closure monitoring data to Isometric as part of the continued monitoring requirements or this storage location		Modified to a FAR as ongoing discussions and post-closure monitoring plan requirements are evaluated with Isometric and Charm. Provide evidence of contractual agreement with Vaulted regarding post-closure monitoring and responsibilities.

APPENDIX 3: VERIFIER QUALIFICATIONS

Supporting documentation, including verifier resumes, and verifier or corporate accreditations are also included in this appendix.

Verifier Qualifications	**Criteria Met?**	**Evidence / Notes** *(note how the criteria was met, specific documents - resume/CV, publications, certifications, etc.).*
Verifier has relevant technical knowledge of the type of technology being evaluated and carbon removal processes in general		
A) Does Verifier have:		
1. An in-depth technical knowledge of the technology type under verification;	☑	350Solutions is accredited to ISO/IEC 17020:2012 and ISO 14034 Environmental Technology Verification (ETV) as a Type A (third party) Inspection Body (ANAB Certificate Number: AI-2618). The technical scope of 350's accreditation includes verification of performance and environmental impact as it relates to design, materials, equipment, installation and operations of technologies in the categories of Energy, Clean Production and Process, and Air Pollution Monitoring and Abatement. As documented in 350Solutions' ETV Standard Operating Procedure (ETV QPM 350-223-03), and Quality Systems Procedures for verifier qualifications (QSP-350-005-02), 350Solutions conforms to the requirements of ISO 17020 Annex A with respect to verifier qualifications and procedures. These procedures and quality management programs are generally relevant to verification under the Isometric Standard. Note that verifications completed for Isometric are not equivalent to ISO 14034 verifications. 350 staff have participated in the evaluation and verification of novel technologies that sequester carbon via various methods, including biomass conversion to liquids, solids, and other products which are then permanantly stored in ways such as land application or geologic storage, conversion of captured CO2 into building materials and co-products, and the production of chemicals, fuels, and products via biomass pyrolysis and gasification. 350 also served as lead verifier for the Carbon XPrize competition and contributed to the development of procedures and processes for verification of relevant calculations, modeling, and statistical methods in order to assess team results and calculations of performance metrics and uncertainty. 350 has demonstrated knowledge of data quality and data validation approaches and execution in supporting verification of performance claims and results.
2. Knowledge of specific risk areas associated with performance of such technologies (i.e. common failure points, performance issues, barriers to scaleup);	☑	
3. Knowledge of the environmental implications related to the use of the technology from a life cycle perspective, such as impact of the technology on lifecycle CO2 emissions and carbon removal;	☑	
4. Knowledge of relevant applicable test methods and standards for evaluating performance or impact of the technology;	☑	
5. Knowledge of relevant calculation, modeling, and statistical methods in order to assess test results and calculations of performance metrics and uncertainty, as applicable;	☑	
6. Knowledge of data quality and data validation approaches, including QA/QC procedures, for example.	☑	
Verifier is a credible independent 3rd party		
B) Is Verifier:		
1. third-party body independent of the team registered for the Isometric Registry	☑	350Solutions is accredited to ISO/IEC 17020:2012 and ISO 14034 ETV as a Type A (third party) Inspection Body. As documented in 350Solutions ETV Policy Manual (ETV QPM 350-200-03), 350Solutions conforms to the requirements of ISO 17020 Annex A with respect to impartiality for Type A inspections, pursuant to ISO 14034 activities.
2. Not directly involved in the design, manufacture or construction, marketing, installation, use or maintenance of the specific technologies submitted to Isometric for verification, or represent the parties engaged in those activities.	☑	
3. Not part of a legal entity that is engaged in design, manufacture, supply, installation, purchase, ownership, use or maintenance of the items inspected.	☑	

Tim Hansen, P.E.
Founder and CEO, 350Solutions

EDUCATION:
B.S., Chemical Engineering, University of Virginia, 1993
M.S., Engineering Science, Thayer School of Engineering, Dartmouth College, 1995

EXPERIENCE SUMMARY:
Mr. Hansen has 26 years of experience in management of energy and environmental technology development and demonstration projects and programs, as well as multimedia environmental engineering efforts. The majority of his recent work has focused on the evaluation of innovative carbon capture, utilization, and removal technologies. Mr. Hansen has led the development and management of large technology evaluation programs in the advanced energy, transportation, and climate change areas.

RESEARCH AND PROFESSIONAL EXPERIENCE:
2019-Present Founder – CEO, 350Solutions, Inc.
Owns and operates a small cleantech engineering consulting business focused on the independent evaluation of new cleantech innovations and their impact on the environment and carbon emissions. Provides engineering consulting, testing and evaluation, techno-economic assessment, and other support to companies developing, using, or investing in new clean technology innovations. Manages administrative, business development, and project activities for 350Solutions.

2012-2019: Director - Energy and Environment, Southern Research
Manages scientific and technical staff performing research, development, and evaluation of innovative clean energy technologies. Projects range from $25,000 to $6million in size, and are funded by the US Department of Energy, Department of Defense, and commercial partners. Technical focus areas are conversion of biomass to fuels and chemicals, carbon capture and utilization, energy efficient building technologies and renewable energy generation.

2009-2012: Program Manager – Transportation & Climate Change Technology, Southern Research
2003-2009 Sr. Project Leader, Environmental Engineer, Southern Research
1996-2003 Environmental Engineer, Bensinger & Garrison Environmental

PROJECT EXPERIENCE:
Mr. Hansen has executed several independent technology performance verifications of emerging carbon, energy and transportation technologies, as CEO of 350Solutions, Director of Energy & Environment at Southern Research, and Director of the U.S. EPA's Greenhouse Gas Technology Center. Mr. Hansen has completed clean technology evaluations for the Department of Defense, state energy agencies, commercial clients, investors, and technology developers, involving evaluation of commercial feasibility, economic and environmental impacts, and technology performance. Mr. Hansen served as the Measurement and Verification Program Lead for the NRG COSIA Carbon XPrize – a $20M prize competition for technologies that capture and beneficially utilize CO_2. Mr. Hansen also served as U.S. Technical Expert for the development and implementation of ISO 14034 – Environmental Technology Verification, an international standard, issued in 2016

Guy Ingram-Hardwick
Carbon Removal Verification Engineer, 350Solutions

EDUCATION:
MEng Materials Science and Engineering, Loughborough University, UK - 2022

EXPERIENCE SUMMARY:
Guy Ingram-Hardwick is a Materials Engineer with experience in process engineering, MRV protocol development, experimental design and life cycle analysis (LCA). At 350 Solutions, Guys efforts center on validation and verification of varied carbon removal pathways. Guy began his experience in the carbon markets directly after graduating working to develop an LCA model for Brilliant Planet, a marine based carbon removal company growing, processing and burying microalgae for carbon sequestration. Once completing the LCA model, Guy managed the third-party verification and co-authored a paper currently awaiting publication documenting the findings. Guy also co-authored the MRV methodology for Brilliant Planet before managing its adoption with carbon market registries and developing the relevant PDD documentation. Guy's Master's thesis in degradation mechanisms for biodegradable polymers resulted in another publication but also provided him experience in experimental design and execution which lead to his experience at Brilliant Planet in conducting field trials for developing novel technologies associated to the processing and storage of the microalgae, displaying the long-term permanence of the carbon removal system. Prior to his experience at Brilliant Planet, Guy worked as a process engineer at Pirelli's rubber compound manufacturing plant in Burton-on-Trent with a focus on data analytics for driving continuous improvement.

RESEARCH AND PROFESSIONAL EXPERIENCE:
January 2025 – Present: Carbon Removal Verification Engineer, 350Solutions
Verify carbon dioxide removal technologies on behalf of registries and private companies ensuring high quality and meaningful climate impact.

Jul 2022 – Dec 2025: LCA and MRV Associate, Brilliant Planet
Quantified the carbon removal efficiency of the Brilliant Planet system across a variety of engineering designs using LCA. Developed the proprietary MRV methodology and PDD as well as setting up a novel experimental design to display the permanence of the stored carbon.

July 2019 – September 2020: Process engineer, Pirelli
Completed data analytics to drive continuous improvement for increasing efficiency, safety and rubber compound quality.