Isometric Standard Project Verification Report

For

Charm Industrial

Client	Isometric
Company / GHG Removal Supplier	Charm Industrial
Facility or Project Name	Charm Bio-oil Geologic Storage
Facility Address	**Bio-oil Production:** **AE Cote-Nord Canada Bioenergy Inc (AECN)** Port Cartier, Quebec, Canada **Charm Miniforge** Fort Lupton, CO, USA **Bio-oil Pre-Processing:** **Charm Industrial** El Dorado, KS, USA **Bio-oil Injection:** **Charm Industrial** Evangeline Parish, LA, USA
Greenhouse Gas Statement ID/Gas Statement Version ID	ggs_1K5W4N84Y1S0CNTX/ gss_1K6XRTJEW1S0N44F
Net Greenhouse Gas Removals	166.40 tonnes CO_{2e}
Removal Method	Bio-oil Geological Storage
Removal Period	August 16 – September 8, 2025
Verification Opinion	Positive (fully meets criteria)
Verifier/Validation and Verification Body	Tim Hansen Guy Hardwick 350Solutions, Inc.

ISSUED:

OCTOBER 9, 2025

CONTENTS

1. Key Project Data 3
1.1. Verification Summary 4
2. Verification & Storage Site Validation Details 6
2.1. Verification Objectives 6
2.2. Responsibilities 6
2.3. Level of Assurance & Materiality 6
2.4. Verification Team Details 6
2.5. Audit Process Followed 6
3. Technical Aspects 7
3.1. Project Details 7
3.2. Protocols and Modules Applied 8
3.3. Applicability of Applied Protocol and Modules 8
3.4. Project Boundary 8
3.5. Changes from Previous Verifications 9
3.6. Process & Data Irregularities During Reporting Period 9
4. Crediting Details 10
4.1. Project Reporting Period 10
4.2. Crediting Period 10
5. GHG Statement Verification & Storage Site Validation 10
5.1. Accuracy of the Statement 10
5.2. Verification Storage Site Validation Opinion 11
5.3. Verification & Storage Site Validation Results Summary 11
5.4. Verification & Storage Site Validation Findings 13
5.4.1. Critical Findings and Exceptions 13
5.4.2. Forward Action Requests & Recommendations 16
6. Revision History 17
Appendix 1: Documents Submitted for Review 19
Appendix 2: Verification Audit Findings and Responses 26
Appendix 3: Verifier Qualifications 30

ISOMETRIC STANDARD VERIFICATION REPORT		
Company: Charm Industrial	Company Contact: *Max Lavine	Validation and Verification Team: *Tim Hansen, PE Guy Hardwick
Removal Method: Bio-oil Geological Storage		
Report Date: October 9, 2025		
Document No: 350VR-Charm-ISO2504.07		
Rev: v1.2		

** Primary contact/lead author*

1. KEY PROJECT DATA

TABLE 1. VERIFICATION SUMMARY FOR CHARM INDUSTRIAL BIO-OIL STORAGE

Title	Charm Bio-Oil Geologic Storage
Location	Bio-oil Production: AE Cote-Nord Canada Bioenergy Inc (AECN) @ Produits Forestiers Arbec S.E.N.C., 175 Bd du Portage des Mousses Port-Cartier, QC G0W 1X0, Canada 50.025323, -66.818910 Charm Industrial Miniforge 2360 S Rollie Ave Fort Lupton, CO, USA 80621 40.076570, -104.804680 Bio-oil Pre-Processing: Charm Industrial 838 SW Purity Springs Rd El Dorado, KS 67042 37.813906, -96.914982 Bio-oil Injection & Storage: Charm Industrial Evangeline Parish, LA 30.916251, -92.297908
Reporting Period	August 16, 2025 – September 8, 2025
Greenhouse Gas Statement ID	Final Revised: ggs_1K5W4N84Y1S0CNTX (Version ID gss_1K6XRTJEW1S0N44F) (06OCT) Original Reviewed: ggs_1K5W4N84Y1S0CNTX (Version ID gss_1K5W4XQ0F1S0TRH2) (23SEP)
Project Proponents	CDR Supplier: Charm Industrial Feedstock Supplier: Produits Forestiers Arbec S.E.N.C (Quebec mill waste supplier); Altitude Forestry (CO forestry fire prevention waste supplier) Geologic Storage Management: Charm Industrial Salt Cavern Storage Management (Prior Injections): Vaulted Deep Regulatory Agency (Injections / Storage): Louisiana Department of Energy & Natural Resources; Kansas Department of Health & Environment (KDHE) (Prior Injections)

Legal Ownership of the Credits	Charm Industrial
Removals in Reporting Period	166.4 tonnes
Removal Method	Bio-oil Geological Storage
Verification Report Date	October 9, 2025
Verification Type & Criteria	Isometric Standard Verification for ongoing deliveries of carbon removal credits by Charm Industrial in accordance with the documents used during project validation: • Isometric Standard v1.7 • Bio-oil Geological Storage Protocol v1.1 • Biomass Feedstock Accounting Module v1.2 • Bio-oil Storage in Permeable Reservoirs v1.1 • Embodied Emissions Accounting v1.0 • Energy Use Accounting v1.2 • Transportation Emissions Accounting v1.1

1.1. VERIFICATION SUMMARY

350Solutions was contracted to perform a project verification of the greenhouse gas (GHG) statement of Charm Industrial's bio-oil geological storage process for the referenced reporting period. The validation report for the Charm Kansas Bio-oil Geologic Storage project was completed on June 25, 2024, by Futurepast, which focused on the use of third-party produced bio-oils and was issued by Isometric for the Crediting Period March 1, 2024 – February 28, 2029. An additional validation of the Charm Kansas Bio-oil Geologic Storage project for use of bio-oil produced by Charm was completed on October 18, 2024, for the same crediting period. These validations remain valid for this verification reporting period. Further details and findings can be found in the validation report (https://registry.isometric.com/project/prj_1HZSSWBQM1S08H83#project-documentation). A new injection and storage location in Evangeline Parish, Louisiana was utilized for all injections during this reporting period, and storage site validation is included in the report located here: https://storage.googleapis.com/isometric--production--eu--public-documents/spl_1H31MW3T81S0R67B/prj_1HZSSWBQM1S08H83/pjd_1K5XPX61T1S0TM0Z/verification_report.pdf.

350Solutions affirms that Charm has the appropriate equipment, procedures, and protocols in place and is documented to quantify GHG removal through the injection of bio-oil into permeable reservoirs via a permitted Class V well in accordance with the requirements of the applicable Isometric standards, protocols and modules.

The carbon removals for the reporting period are provided in Table 2. These values have been verified by 350Solutions.

TABLE 2. VERIFIED TOTAL REMOVALS BY CHARM INDUSTRIAL FOR REPORTING PERIOD ENDING SEPTEMBER 8, 2025

Removal ID	Date removal started	Date removal completed	Discounted CO_2e net removed, rounded (kg)
rmv_1K574HGHH1S0DA9A	2025-08-25	2025-08-25	3750
rmv_1K59ZW9561S0P18M	2025-08-19	2025-08-19	58580
rmv_1K5727HTZ1S0X5TV	2025-08-25	2025-08-25	3550

rmv_1K5791P761S0ATVM	2025-08-18	2025-08-18	3870
rmv_1K577TGYJ1S01JYP	2025-08-25	2025-08-25	4050
rmv_1K57QXPAK1S09XS2	2025-08-21	2025-08-21	3590
rmv_1K57221JE1S0J0BC	2025-09-05	2025-09-05	970
rmv_1K5AD2RC01S0PFFG	2025-08-20	2025-08-20	32070
rmv_1K57PEQ6S1S0V9Y9	2025-09-08	2025-09-08	1830
rmv_1K57SD2BG1S0EAGM	2025-08-16	2025-08-16	54140
TOTAL (kg CO_2e)			166400

The quantity of **166.40 tonnes** of net carbon removals has been verified with a reasonable level of assurance and are eligible for crediting under the referenced Isometric Standard and Protocol.

350Solutions Inc. declares that it is an impartial verification body, approved by Isometric for verifications in the required technical area, free from any conflicts of interest, capable, and qualified to complete this verification for the current reporting period according to the *Isometric Standard v1.7, Bio-oil Geological Storage Protocol v1.1, Biomass Feedstock Accounting Module v1.2.1*, *Bio-oil Storage in Permeable Reservoirs Module v1.1, Embodied Emissions Accounting v1.0, Transportation Emissions Accounting v1.1,* and *Energy Use Accounting v1.2*.

Verifier Information		
Verification Body	**Verifier**	**Verification ID No.**
350Solutions, Inc.	Tim Hansen	VR-Charm-ISO2504.07

Timothy A. Hansen Digitally signed by Timothy A. Hansen Date: 2025.10.09 13:13:32 -04'00'

Signed: Tim Hansen (Verifier)

Guy Hardwick Digitally signed by Guy Hardwick Date: 2025.10.09 18:36:26 +01'00'

Guy Hardwick (QA)

2. VERIFICATION & STORAGE SITE VALIDATION DETAILS

2.1. VERIFICATION OBJECTIVES

A series of verification activities was conducted by 350Solutions to independently verify the claimed removals of the GHG statement submitted by Charm Industrial for operations conducted at the Charm Bio-oil Geologic Storage facility for the referenced Reporting Period. The verification was conducted following the specifications of the standards and protocols cited in Table 1.

2.2. RESPONSIBILITIES

The verification is based on the provision and fair presentation of a complete and accurate GHG Statement submitted by Charm Industrial to the Isometric registry. It is Charm's responsibility to ensure a fair, accurate, and complete presentation of the GHG Statement and Project Design Document are provided. This is confirmed and verified independently by 350Solutions based on supporting evidence in accordance with the Isometric criteria (Table 1, Section 3.2).

2.3. LEVEL OF ASSURANCE & MATERIALITY

The verification was conducted with a reasonable level of assurance. Any discrepancies between the claimed removals of the project and the removals estimated by the verification process for the reporting period are less than the materiality threshold of 5%.

2.4. VERIFICATION TEAM DETAILS

350Solutions is an accredited inspection & verification body by ANAB under ISO 17020:2012 for completion of ISO 14034:2016 Technology Verifications. 350Solutions is headquartered in Raleigh, North Carolina, USA. 350Solutions Technical Lead for the Charm verification is Tim Hansen. Mr. Hansen is a registered Professional Engineer with over 25 years of experience in the evaluation and verification of novel cleantech and carbon technologies. Mr. Hansen has led verifications of carbon removal technologies for multiple registries, including Isometric, and has experience in the development and testing of biomass conversion technologies, including gasification and pyrolysis. The verification report was provided QA by Guy Hardwick, a Carbon Removal Verification Engineer, with experience developing and verifying carbon removal technologies, including biochar and biomass terrestrial storage.

2.5. AUDIT PROCESS FOLLOWED

The specific verification and storage site validation activities conducted are summarized in Table 3. The list of all files that were reviewed is provided in Appendix 1. The list of findings from the verification can be found in Appendix 2. Audit results are documented using 350's Compliance Checklist, which includes all requirements from the Isometric standard, Bio-oil Geologic Storage protocol, and referenced modules.

TABLE 3. VERIFICATION & STORAGE SITE VALIDATION ACTIVITIES

Date(s)	Verification Activity	Verification Tasks	Documents Reviewed
September 23 –	Review of reporting period	• Review of GHG Statement and report and guidance from Charm	Final V 1.10 Charm Industrial Bio-Oil Geologic Storage PDD.docx

Date(s)	Verification Activity	Verification Tasks	Documents Reviewed
October 7, 2025	modifications and changes		August_September Removals Isometric GHG Statement Report v1.6 August_September VVB Guidance.docx Final Revised: ggs_1K5W4N84Y1S0CNTX (Version ID gss_1K6XRTJEW1S0N44F) (06OCT) Original Reviewed: ggs_1K5W4N84Y1S0CNTX (Version ID gss_1K5W4XQ0F1S0TRH2) (23SEP)
September 23-October 7, 2025	Review of current Validation and GHG Statement Applicability	• Review of Validation Report • Review of prior Verification Report and findings • Identification of major and minor process steps, measurements, and calculations and changes in RP • Review of Standards/Protocols/Modules required for Verification • Generation of a checklist of verification issues and findings and opportunities for improvement	Validation_Report_for_Isometric_Charm_Industrial_Bio-Oil_Project_2024-06-25_r1 Isometric Standard Project Verification & Storage Site Validation Report For Charm Industrial (23Sep2025) Final V 1.10 Charm Industrial Bio Oil Geologic Storage PDD.docx August_September Removals Isometric GHG Statement Report v1.6 August_September VVB Guidance.docx Final Revised: ggs_1K5W4N84Y1S0CNTX (Version ID gss_1K6XRTJEW1S0N44F) (06OCT) Original Reviewed: ggs_1K5W4N84Y1S0CNTX (Version ID gss_1K5W4XQ0F1S0TRH2) (23SEP) Isometric Standard v1.7, Bio-oil Geological Storage Protocol v1.1, Biomass Feedstock Accounting Module v1.2, Bio-oil Storage in Permeable Reservoirs Module v1.1, Embodied Emissions Accounting v1.0, Transportation Emissions Accounting v1.1, and Energy Use Accounting v1.2
October 1-8, 2025	Verification of Removals	• Verify changes to the system • Review of measurements and calculations • Review of durability/permit requirement monitoring data • Review of GHG statement • Identification of initial findings and follow-up request for information • Write verification report	File List provided in Appendix 1. Initial Findings in Appendix 2.

3. TECHNICAL ASPECTS

3.1. PROJECT DETAILS

Charm obtained bio-oil from two sources during this reporting period. Charm obtains bio-oil from a producer in Quebec, Canada (AECN) who uses an Ensyn/Honeywell UOP pyrolysis system to generate bio-oil from waste wood produced at a neighboring mill. In addition, Charm produces bio-oil at its pyrolysis facility in Fort Lupton, CO. Production of bio-oil for sequestration and carbon removal credit generation began in August of 2024, with the initial installation of 4 pyrolyzers, with plans for up to 18 pyrolyzers total to be installed. Charm's pyrolyzers utilize wood chips, placed into a high temperature pressurized reactor in a low oxygen environment to reduce the wood chips into a combination of products, including syngas and light hydrocarbon gases, pyrolysis oils, biochar, and wood vinegar. All hot pyrolysis gases from the reactor are quenched with water to produce the oil and wood vinegar products. Excess gases are routed to a combustion device for emissions control, with the heat produced from the

combustion of excess gas utilized for drying the biomass from 40%-50% moisture content to 10% moisture content before introduction into the pyrolyzer.

Bio-oil from AECN and aqueous fraction product from Charm pyrolyzers are shipped by tanker truck, rail car, or tote tanks on flatbed to a Charm facility in El Dorado, Kansas. At this facility, Charm pretreats the bio-oil through the addition and sparging of liquid caustic soda (LCS) as needed to adjust the pH of the bio-oil and aqueous product to meet the requirements of the injection facility permit for storage in permeable reservoirs as specified by the Louisiana Department of Energy & Natural Resources (LDENR). Charm-produced bio-oil is not pretreated when injected at the Basco injection site in Louisiana.

Charm Bio-oil product and the treated AECN oil and Charm aqueous product are trucked to Charm's underground injection and storage facility located in Evangeline Parish, Louisiana for storage into a geologic reservoir. The bio-oil products are blended in on site storage tanks through recirculating pumps and injected as soon as practicable. Samples of the blended bio-oil are collected prior to injection and analyzed for bio-oil characteristics to ensure compliance with permit requirements. Charm also monitors all injection parameters as required by the Underground Injection Control (UIC) permit.

3.2. PROTOCOLS AND MODULES APPLIED

The verification was conducted following the specifications of the following standards, protocols, and modules:

- Isometric Standard v1.7 [1]
- Bio-oil Geological Storage Protocol v1.1 [2]
- Biomass Feedstock Accounting Module v1.2 [3]
- Bio-oil Storage in Permeable Reservoirs v1.1 [4]
- Embodied Emissions Accounting v1.0 [5]
- Energy Use Accounting v1.2 [6]
- Transportation Emissions Accounting v1.1 [7]

Charm utilizes Book and Claim Units (BCUs) to substitute for some, or all, or project diesel fuel usage and purchases Renewable Energy Certificates (RECs) for some or all its electricity consumption in accordance with the Energy Use and Transportation Modules.

3.3. APPLICABILITY OF APPLIED PROTOCOL AND MODULES

The Charm project takes mixed woody waste or forestry thinnings from wildfire prevention activities, converts it to bio-oil, which they pretreat and inject into geologic storage formations. The biomass feedstocks were assessed previously under the eligibility criteria of the Isometric Biomass Feedstock Module and were found to be eligible. As the biomass feedstocks have been deemed eligible biomass feedstocks, the storage of biomass conversion products (bio-oil) in a geologic formation makes both the Bio-oil Geological Storage Protocol and Bio-oil Storage in Permeable Reservoirs Module applicable to this project. All other modules for energy, transportation, and embodied emissions accounting are generally applicable to this project.

3.4. PROJECT BOUNDARY

The boundaries of the project include the supply of wood waste to the biomass processing sites (AECN and Charm Fort Lupton), the conversion of the biomass to bio-oil via AECN's pyrolysis process and Charm's pyrolysis process, transport of the bio-oil to Charm for preprocessing at its El Dorado, Kansas

facility, completion of pretreatment, shipment to the Charm Louisiana injection and storage site, and injection of the bio-oil in the geologic reservoir. Monitoring and required analysis of the bio-oil and the storage formation are also included in the project boundary.

3.5. CHANGES FROM PREVIOUS VERIFICATIONS

Compared to prior verification (Reporting Period 01AUG-15AUG2025), no significant modifications were made to the Charm Industrial processes, data collection, and calculation procedures which have been specified in the GHG statement and supporting documentation. The following minor modifications and notes have been provided for clarity. All were reviewed and deemed acceptable under the Isometric requirements:

- This Reporting Period includes all relevant process waste disposals which Charm has received disposal vendor documentation for during the period and details provided as applicable for carbon accounting
    - There was a significant quantity of bio-oil disposed from the Kansas Facility during this reporting period.
    - The bio-oil disposed was accumulated over a period of time. During the interim, all oil was stored in sealed IBC totes to prevent fugitive emissions.
    - Documentation of load mass and destination is provided in disposal vendor manifests which were delayed for some of the removal activity in July. Therefore, the disposal emissions in this Reporting Period include those disposals as well as all of those completed during the current Reporting Period.
- An additional Site Emission was added for Vaulted Embodied Emissions, which accounts for all outstanding Vaulted embodied emissions for prior injections and storage at the Vaulted facility
- All outstanding monitoring records for prior injections at the Vaulted facility have been submitted and reviewed.
- All site emissions related to bio-oil salting (salt delivery, tank salt residue cleanouts) are no longer included in reporting as bio-oil no longer needs to be salted due to the cessation of injections at the Vaulted facility.
- For AECN oil processed in KS, Charm has added an extra 355.4 kg of upstream production and transport emissions for each tanker truck of AECN that is used in a given batch to account for losses and measurement error.
- Note that Charm is continuing to transition additional parts of its reporting to the Isometric Certify platform. As this occurs, certain components may appear partially complete or incomplete in Certify. However, the data has been submitted separately from Certify and verified by 350 as compliant. For this reporting period, Monitoring and Feedstocks requirements are included in Certify, but entries appear incomplete. However, these items are fully addressed outside of Certify.

3.6. PROCESS & DATA IRREGULARITIES DURING REPORTING PERIOD

No significant data anomalies or irregularities occurred during the reporting period related to data collection and operations.

It should be noted that the ongoing monitoring required for prior injections at the salt cavern storage site in Kansas (Vaulted Deep) continues to be completed. However, the reporting schedule for such monitoring does not always align with the data submissions for current reporting periods. It is also not

relevant to the crediting associated with the current reporting period. As a result, some required monitoring report submittals for prior injections are delayed and will be reviewed in the next reporting period.

4. CREDITING DETAILS

4.1. PROJECT REPORTING PERIOD

This verification considers injections of bio-oil (oil and aqueous phases) by Charm during the period August 16, 2025 to September 8, 2025. The reporting period is based on the actual injection dates, with bio-oil production, transportation, monitoring, and related activities potentially occurring outside of this reporting period, but properly accounted for and allocated to the bio-oil injected within the reporting period.

4.2. CREDITING PERIOD

The 5-year crediting period for the Charm Kansas Bio-oil Geologic Sequestration Project began March 1, 2024, and continues for five years, ending February 28, 2029. All claimed removals in this reporting period fall within the current crediting period.

5. GHG STATEMENT VERIFICATION & STORAGE SITE VALIDATION

5.1. ACCURACY OF THE STATEMENT

The values represented in the GHG statement have been evaluated, cross-referenced with the presented evidence, and confirmed, noting:

- The initial GHG Statement contained an error in weights for transportation of one bio-oil injection batch, which was corrected, but had no material impact on the total GHG emissions.
- In addition, improper evidence was provided In Isometric's Certify platform for one removal (weigh scale tickets), however, the proper tickets were provided outside of Certify, and a revised GHG Statement was submitted and verified to correct the evidence in Certify.

Confirmation of the GHG statement has been based on the following efforts:

- Review and confirmation of calculations of total bio-oil and CO_2 equivalent injected and all process, operational, and embodied emissions, as well as all supporting evidence for the following removals:

Removal ID	Date Removal Started
rmv_1K59ZW9561S0P18M	2025-08-19
rmv_1K57221JE1S0J0BC	2025-09-05
rmv_1K57SD2BG1S0EAGM	2025-08-16

- This includes for these removals:
  - Calculation of mass of bio-oil delivered and injected including tracing to raw data (weigh scale tickets, carbon content, addition of consumables)
  - Confirmation of transportation distances for tanker and rail car deliveries from AECN to El Dorado, KS and to Basco site, LA
  - Confirmation of weigh scale raw data for deliveries of bio-oil and injectate
  - Confirmation of raw data for fuel usage at Charm pre-treatment and injection facilities
  - Confirmation of electricity usage at Charm pretreatment and injection facilities
  - Confirmation of proper use and accounting of BCUs and RECs to offset diesel and electricity usage emissions, respectively
  - Review of Charm pyrolysis process emissions, supporting evidence, and calculations
- Review of monitoring data as required for Basco site injection and post injection monitoring to ensure compliance with Class V permit as well as Vaulted prior injections.

5.2. VERIFICATION STORAGE SITE VALIDATION OPINION

350Solutions has reviewed the documentation of the technology, the instrumentation, the procedures, performance and collected data and has found that the data presented in the greenhouse gas removal statement indicates that the claims fall within the 5% materiality threshold for greenhouse gas emissions and removals as required by the Isometric Standard:

☒ ***Meets the requirements of the Isometric Standard v1.7, Biomass Geological Storage Protocol v1.1, Biomass Feedstock Accounting Module v1.2, and Bio-oil Storage in Permeable Reservoirs Module v1.1 for Verification***

☐ ***Meets the requirements with minor revisions of Isometric Standard v1.7, Biomass Geological Storage Protocol v1.1, Biomass Feedstock Accounting Module v1.2, and Biomass or Bio-oil Storage in Salt Caverns Module v1.1 for Verification***

☐ ***Does Not Meet the requirements of the Isometric Standard v1.7, Biomass Geological Storage Protocol v1.1, Biomass Feedstock Accounting Module v1.2, and Biomass or Bio-oil Storage in Salt Caverns Module v1.1 for Verification***

5.3. VERIFICATION & STORAGE SITE VALIDATION RESULTS SUMMARY

A summary of verification results and compliance with relevant requirements of the *Isometric Standard, Biomass Geological Storage Protocol, Biomass Feedstock Accounting Module*, and *Bio-oil Storage in Permeable Reservoirs Module* are summarized below.

TABLE 4. VERIFICATION RESULTS SUMMARY

Isometric Standard Section Ref.	Verification Topic	Changed since Project Validation? (Y/N)	Final Findings
2.1.	*Validated against approved Protocols*	N	Acceptable – No additional changes since validation
2.5.1	*Boundaries*	N	Acceptable – No additional changes since validation
2.5.2	*Baseline*	N	Acceptable – No change since validation

Isometric Standard Section Ref.	Verification Topic	Changed since Project Validation? (Y/N)	Final Findings
2.5.3	*Additionality - Financial*	N	Acceptable – No change since validation
2.5.3	*Additionality – Environmental*	N	Acceptable – No change since validation
2.5.3	*Additionality – Regulatory*	N	Acceptable – No change since validation
2.5.4	*Leakage*	N	Acceptable – No change since validation and prior verification.
2.5.5	*Default Emission Factors, Proxies, and Models*	N	Acceptable – No additional significant changes were made since prior verifications. See Section 3.5 for summary of modifications to any calculation methods, all of which are acceptable.
2.5.11	*Life Cycle Assessment (LCA) Policies*	N	
2.5.6	*Common Calculation Factors*	N	
2.5.7	*Uncertainty*	N	
2.5.8	*Durability and Monitoring*	Y	All updated durability evidence and storage monitoring requirements validated to meet protocol requirements. Note reports for prior injections at Kansas salt caverns were not submitted until after data was submitted for this reporting period and will be reviewed in next reporting period.
2.5.9	*Risk of Reversal*	N	Acceptable – No additional changes since validation
2.5.10 3.7	*Environmental and Socioeconomic Impacts*	N	Acceptable – No additional changes since validation.
3.1	*Ownership*	N	Acceptable – No change since validation
3.2	*Documentation*	Y	Acceptable – No additional changes since prior verification. All documentation properly updated for reporting period
3.3	*Eligibility*	Y (GHG Statement Updated)	Acceptable – Project registered with Isometric and reporting period GHG Statement properly submitted to Isometric dMRV Certify platform.
3.4	*Project Crediting*	Y (GHG Statement Updated)	Acceptable – New reporting period GHG Statement is complete, and all removals have been verified. Reporting period is within current validation crediting period.
3.5	*Stakeholder Input Process*	N	Acceptable – No change since validation.
3.6	*Regulatory Compliance*	Y (Required Monitoring Updated)	Required monitoring and reporting completed during reporting period. No additional compliance issues identified. Note reports for prior injections at Kansas salt caverns were not submitted until after data was submitted for this reporting period and will be reviewed in next reporting period.
Biomass Feedstock Accounting Module			
2.1	*Eligibility Criteria for Market Leakage*	N	Acceptable – No change since prior feedstock validations
2.2	*Counterfactual Storage Eligibility*	N	Acceptable – No change since prior feedstock validations
2.3	*Dedicated Energy Feedstock Eligibility*	N	Acceptable – No change since prior feedstock validations
3.0	*Counterfactual Definition*	N	Acceptable – No change since prior feedstock validations
3.1	*Counterfactual Energy Definition*	N	Acceptable – No change since prior feedstock validations

Isometric Standard Section Ref.	Verification Topic	Changed since Project Validation? (Y/N)	Final Findings
3.2	*Counterfactual Replacement Definition*	N	Acceptable – No change since prior feedstock validations

TABLE 5. BASCO STORAGE SITE VERIFICATION SUMMARY

Isometric Standard Section Ref.	Verification Topic	Changed since Project Validation? (Y/N)	Final Findings
Bio-oil Storage in Permeable Reservoirs Module			
1.0	*Storage System Eligibility*	N	Acceptable – No change since validation
2.1	*Storage Reservoir – Permitting*	N	Acceptable – No change since validation
2.2	*Storage Reservoir – Capacity*	N	Acceptable – No change since validation
2.2	*Storage Reservoir – Integrity*	N	Acceptable – No change since validation
2.2	*Storage Reservoir – Integrity: Characterization*	N	Acceptable – No change since validation
2.2	*Storage Reservoir Characterization – Temperature, pH, conductivity, density*	N	Acceptable – No change since validation
2.2	*Storage Reservoir Characterization – $d^{13}C$ analysis (where applicable)*	NA	Acceptable – Not required
2.3	*Storage Reservoir Integrity – Well Construction*	N	Acceptable – No change since validation
3.1.1	*Storage Reservoir Integrity – Injection operations*	N	Acceptable – No change since validation. Updated monitoring data provided indicating no exceedances of permit limits
3.1.1	*Storage Reservoir Integrity – Injection operations – Sampling & Analysis*	N	Acceptable – No change since validation. Updated sampling and analytical data provided indicating no exceedances of permit limits
1.0, 3.2	*Well Closure and Post Closure Requirements*	N	Acceptable – No change since validation
3.1.3	*Injection Pressure*	N	Acceptable – Pressure is continuously monitored and reported quarterly (monitoring reports indicate full compliance)
3.1.2	*Mechanical Integrity*	N	Acceptable – No change since validation
3.1.3	*Volatile Gas Monitoring*	N	Acceptable – No change since validation
3.1.3	*Reversal Risk & Monitoring*	N	Acceptable – No change since validation
3.3.1	*Attribution of Reversals*	N	Acceptable – No change since validation

5.4. VERIFICATION & STORAGE SITE VALIDATION FINDINGS

5.4.1. CRITICAL FINDINGS AND EXCEPTIONS

Assessment of the greenhouse gas removal statement identified several initial findings (Appendix 2). All findings, primarily associated with missing supporting evidence, have been addressed and closed. Findings of note include the following:

Table 6. Critical Findings

ID	Type+	Finding	Required Action	Supplier Response	Conclusion/ Resolution
1	NC	Weigh Scale ticket 'Scale Ticket 1 Empty' for batch 3-41 on certify (rmv_1K57SD2BG1S0EAGM) is incorrect and does not match trailer ID. MRV Ops Notes for 3-41 also shows a different value than on weigh ticket. Note that batch 3-41 injection data provided by Charm provides a correct ticket and (matches trailer ID) and matches value in MRV Ops Notes. So, appears only that the correct ticket needs to be in certify - no calculation updates needed.	Update certify with correct ticket	Evidence in Certify has been updated to reflect the correct scale ticket	Complete
4	NC	For Batch 3-43 (rmv_1K59ZW9561S0P18M) on certify, the injection / Sequestration evidence is for Batch 3-42, so does not match the values in Certify. Data is provided in Google Drive that matches the 3-43 data and what is reported in Certify, so no incorrect values are attributed, but evidence must be updated in Certify	Update certify with correct information	Thank you for the catch, the document has been updated in Certify	Complete
11	NC	Despite injections no longer occurring at Vaulted, the storage of the bio-oil in the Vaulted salt caverns is still the ultimate responsibility of Charm. With that, the requirements to continue post-emplacement and post-well-closure monitoring continue and must be submitted as part of the Charm Bio-oil storage project	Please submit the required Vaulted Salt Cavern monitoring records	In progress	Complete. Noting that Vaulted monitoring reports are submitted to KDHE 30-60 days after month or quarter end so may not be available during the reporting period as part of GHG statement data submission.
12	NC	Although the reports are not required to be submitted to LA any more than quarterly, we request that monitoring data for the injection site be provided with each Reporting Period to prove that Charm is completing the monitoring required. Please provide: - Bio-oil TAN, pH, density, O2 (if	Please provide monitoring records listed	-Bio-oil TAN, density, and viscosity are included in the third party testing documents in each injection batch folder. -pH is provided in a separate document entitled “Batch pH values 8/15-9/8” that has been added to the Injection Lot	Complete

		available), and viscosity results - formation fluid density and conductivity (monthly) - formation fluid salinity (continuous) - injection pressure and injection rate (continuous)		Data folder. -Injection pressure and injection rate data averages and maximums are provided in the reporting submitted to LDENR. This has been added to a folder in the Reporting Package titled "Injection MRV" subfolder "LDENR Reporting" -Appendix 7 of the PDD addresses the availability of formation fluid for analysis after the start of bio-oil injection operations: While the Protocol accommodates the presence of a monitoring well, the Basco 6 EW project consists only of a single Well for injection. As a result, formation fluid analytes (i.e., pH, density, anions/cations, etc.) will not be available after bio-oil injection operations commence, as doing so would jeopardize previously sequestered bio-oil. This variance was reviewed and approved by Isometric prior to inclusion in the PDD.	
3	NC	Related to the weigh scale ticket issue in item 1, the incorrect weigh scale ticket is also used in Certify in calcs for transport emissions for batch 3-41, resulting in an incorrect mass transported (21028.53 kg mass load vs 19168.79 kg). Impact on emission calculation is 1.62 ton vs 1.48 tons (non-material, but noted for accuracy)	We recommend updating for accuracy, but not required (non material)	Updated the emission and the reductions quantity on 3-41. Revised GHG Statement Report has been submitted	Complete
8	RI	It was noted in last reporting period that, with the new storage process, the protocol requires a 5% buffer pool. The registry listing for the Aug1-Aug15 2025 removals cites the correct removal total, but only uses the	Work with Isometric to adjust buffer pool value to 5% and modify for this and prior reporting periods	Completed - updated buffer pool for subsequent issuances	Complete

		previous 2% buffer pool that was set for the salt cavern storage			
10	RI	The PDD Version posted on the Isometric Registry is v1.9. The current version which was significantly updated last reporting period is now v1.10	Work with Isometric to get the updated PDD posted	https://storage.googleapis.com/isometric--production--eu--public-documents/spl_1H31MW3T81S0R67B/prj_1HZSSWBQM1S08H83/pjd_1K6ZPRB591S0QBVN/pdd.pdf	Complete

+NC = Nonconformity; RI = Registry Issue

5.4.2. FORWARD ACTION REQUESTS & RECOMMENDATIONS

Forward action requests (FAR) and recommendations are also provided in Appendix 2 for consideration for improvement of future operations and GHG Removal Credit calculations and to ensure tracking of potential issues to be monitored by verifiers in future verifications. Open FARs and opportunities for improvement are summarized below for future verification reference:

TABLE 7. FORWARD ACTION REQUESTS AND RECOMMENDATIONS

ID No	Type	Finding / Issue	Resolution
5	FAR (prior)	Please plan to provide updated documentation on community engagement and stakeholder input activities by 12/31/2025	Review for future verifications
6	FAR (prior)	Please plan to provide updated documentation on grievance mechanism updates and any complaints/grievances received and responses (or confirmation of no issues) by 12/31/2025	Review for future verifications
7	FAR (prior)	Please ensure all waste disposal related emissions for future disposal of wastes which has been produced during this period are accounted for in future reporting periods as required. Note: Charm has properly accounted for all disposals so far and has all systems in place to do so going forward.	Complete for current Reporting Period. Review for future verifications
13	FAR	With injections no longer occurring at Vaulted, please provide updated contract for post-emplacement / post-closure management and monitoring and post-closure monitoring plan that documents how Charm will be notified of closure of the cavern where Charm oil was last injected, and to ensure that Charm will now be obtaining and submitting any post closure monitoring data to Isometric as part of the continued monitoring requirements or this storage location	Review for next reporting periods

6. REVISION HISTORY

Original date of issue: October 8, 2025

Version	Date Issued	Noted Changes
v1.0 (Draft – Internal)	October 8, 2025	N/A Initial Version
v1.1 (Draft – External)	October 8, 2025	Minor edits from QA
v1.2 (FINAL)	October 9, 2025	Final Version – Minor Edits from Isometric and Charm; Closure of Findings List

References

[1] Isometric, “Isometric Standard v1.2.0.” Accessed: Feb. 19, 2025. [Online]. Available: https://registry.isometric.com/standard/1.2.0

[2] Isometric, “Bio-oil Geological Storage .1.1.” Accessed: Feb. 19, 2025. [Online]. Available: https://registry.isometric.com/protocol/bio-oil-geological-storage/1.1

[3] Isometric, “Biomass Feedstock Accounting .1.” Accessed: Feb. 19, 2025. [Online]. Available: https://registry.isometric.com/protocol/biomass-feedstock-accounting/1.1

[4] Isometric, “Biomass or Bio-oil Storage in Salt Caverns .0.4.” Accessed: Feb. 19, 2025. [Online]. Available: https://registry.isometric.com/protocol/salt-cavern-storage/1.0

[5] Isometric, “Embodied Emissions Accounting v1.0.3.” Accessed: Nov. 20, 2024. [Online]. Available: https://registry.isometric.com/protocol/embodied-emissions/1.0

[6] Isometric, “Energy Use Accounting v1.1.” Accessed: Nov. 20, 2024. [Online]. Available: https://registry.isometric.com/protocol/energy-use-accounting/1.1

[7] Isometric, “Transportation Emissions Accounting v1.1.” Accessed: Nov. 20, 2024. [Online]. Available: https://registry.isometric.com/protocol/transportation

See Appendix 1 and Table 3 for list of specific files reviewed during the verification.

APPENDIX 1: DOCUMENTS SUBMITTED FOR REVIEW

Source Data

Name	Extension	Folder Path
Injection MRV		
Aug_Sept LDENR Injection Reporting .xlsx	.xlsx	Injection MRV-20251008T002948Z-1-001\Injection MRV\LDENR Reporting\
Aug Receipt Response.png	.png	Injection MRV-20251008T002948Z-1-001\Injection MRV\LDENR Reporting\Comms\
Aug Receipt.png	.png	Injection MRV-20251008T002948Z-1-001\Injection MRV\LDENR Reporting\Comms\
Aug Submission.png	.png	Injection MRV-20251008T002948Z-1-001\Injection MRV\LDENR Reporting\Comms\
Sept Submission.png	.png	Injection MRV-20251008T002948Z-1-001\Injection MRV\LDENR Reporting\Comms\
Injection Lot Data		
Batch pH Values 8_15-9_8.xlsx	.xlsx	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\
RP Summary August_September.xlsx	.xlsx	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\
2-105 Ops Notes.xlsx	.xlsx	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\2-105\
KSLA-002 Empty.jpg	.jpg	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\2-105\Scale Tickets\
KSLA-002 Full.jpg	.jpg	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\2-105\Scale Tickets\
KSLA-004 Empty.jpg	.jpg	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\2-105\Scale Tickets\
KSLA-004 Full.jpg	.jpg	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\2-105\Scale Tickets\
CHARM INDUSTRIAL - BATCH 2-105 AECN.pdf	.pdf	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\2-105\Testing\
2-106 Ops Notes.xlsx	.xlsx	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\2-106\
KSLA-0013 Empty.PNG	.PNG	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\2-106\Scale Tickets\
KSLA-0013 full.jpg	.jpg	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\2-106\Scale Tickets\
BATCH 2-105, 2-106, 2-107 AECN.pdf	.pdf	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\2-106\Testing\
3-41 Charm Contents.xlsx	.xlsx	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\3-41\
3-41 Ops Notes.xlsx	.xlsx	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\3-41\
Scale Ticket 1 Empty.jpg	.jpg	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\3-41\Scale Tickets\
Scale Ticket 1 Full.jpg	.jpg	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\3-41\Scale Tickets\
Scale Ticket 2 Empty.jpg	.jpg	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\3-41\Scale Tickets\
Scale Ticket 2 Full.png	.png	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\3-41\Scale Tickets\
Batch 3-40, 3-41, 3-42.PDF	.PDF	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\3-41\Testing\
3-43 Charm Contents.xlsx	.xlsx	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\3-43\
3-43 Ops Notes.xlsx	.xlsx	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\3-43\
Empty Scale Ticket Truck 1.jpg	.jpg	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\3-43\Scale Tickets\
Scale Ticket Full 1.png	.png	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\3-43\Scale Tickets\
Truck 2 Empty Scale Ticket.jpg	.jpg	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\3-43\Scale Tickets\
Truck 2 Full Scale Ticket.jpg	.jpg	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\3-43\Scale Tickets\
BATCH 3-43 & 5-02 (1).pdf	.pdf	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\3-43\Testing\
3-44 Charm Contents.xlsx	.xlsx	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\3-44\
3-44 Ops Notes.xlsx	.xlsx	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\3-44\
Scale Ticket 1 Empty.jpg	.jpg	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\3-44\Scale Tickets\
Scale Ticket 1 Full.jpg	.jpg	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\3-44\Scale Tickets\

Batch 3-44 5-03.PDF	.PDF	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\3-44\Testing\
4-04 Charm Contents.xlsx	.xlsx	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\4-04\
4-04 Ops Notes.xlsx	.xlsx	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\4-04\
KSLA-005 Empty Weight.jpg	.jpg	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\4-04\Scale Tickets\
KSLA-005 Full Weight.jpg	.jpg	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\4-04\Scale Tickets\
BATCH 4-04 Final Salted (TAN, density, viscosity).pdf	.pdf	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\4-04\Testing\
BATCH 4-04 Post LCS & Sparged (CHN & H2O).pdf	.pdf	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\4-04\Testing\
5-02 Charm Contents.xlsx	.xlsx	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\5-02\
5-02 Ops Notes.xlsx	.xlsx	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\5-02\
5-02 Empty Weight.jpg	.jpg	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\5-02\Scale Tickets\
5-02 Full Weight.png	.png	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\5-02\Scale Tickets\
BATCH 3-43 & 5-02.pdf	.pdf	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\5-02\Testing\
5-03 Charm Contents.xlsx	.xlsx	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\5-03\
5-03 Ops Notes.xlsx	.xlsx	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\5-03\
5-03 Empty Weight.jpg	.jpg	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\5-03\Scale Tickets\
5-03 Full Weight.jpg	.jpg	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\5-03\Scale Tickets\
Batch 3-44 5-03.PDF	.PDF	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\5-03\Testing\
5-04 Charm Contents.xlsx	.xlsx	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\5-04\
5-04 Ops Notes.xlsx	.xlsx	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\5-04\
KSLA007 emty wt.jpg	.jpg	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\5-04\Scale Tickets\
KSLA007-LA full weight.jpg	.jpg	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\5-04\Scale Tickets\
Batch 5-04.PDF	.PDF	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\5-04\Testing\
5-05 Charm Contents.xlsx	.xlsx	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\5-05\
5-05 Ops Notes.xlsx	.xlsx	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\5-05\
KSLA-009 Empty Weight LA.jpg	.jpg	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\5-05\Scale Tickets\
KSLA-009 Full Weight LA.jpg	.jpg	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\5-05\Scale Tickets\
BATCH 5-05 3-45.pdf	.pdf	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\5-05\Testing\
BOL 2203-T pickup 7.18.pdf	.pdf	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\AECN BOLs\
BOL 2199-T pickup 7.14.pdf	.pdf	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\AECN BOLs\
BOL 2200-T pickup 7.15 (1).pdf	.pdf	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\AECN BOLs\
BOL 2201-T pickup 7.15 (1).pdf	.pdf	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\AECN BOLs\
BOL 2202-T pickup 7.16 (1).pdf	.pdf	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\AECN BOLs\
BOL 2204-T pickup 7.21 .pdf	.pdf	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\AECN BOLs\
BOL 2205-T pickup 7.23.pdf	.pdf	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\AECN BOLs\
BOL 2206-T pickup 7.22 .pdf	.pdf	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\AECN BOLs\
BOL 2207-T pickup 7.24.pdf	.pdf	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\AECN BOLs\
BOL 2208-T pickup 7.24 .pdf	.pdf	Injection Lot Data-20251008T002950Z-1-001\Injection Lot Data\AECN BOLs\
Charm Bio-oil MRV		
Charm BO Deliveries August.xlsx	.xlsx	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm BO Deliveries\
August 2025 Production Period Summary.xlsx	.xlsx	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\
August 2025 PP (8_1-8_31) Biomass Throughput.xlsx	.xlsx	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Biomass Throughput\

Miniforge Biomass Transport Allocation -- Updated (August).xlsx	.xlsx	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Biomass Transport\
Diesel Consumption Calc 8_1_25-8_31_25.xlsx	.xlsx	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Diesel\
8_12_25.PDF	.PDF	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Diesel\Receipts\
8_17_25.PDF	.PDF	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Diesel\Receipts\
8_21_25.PDF	.PDF	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Diesel\Receipts\
8_4_25.PDF	.PDF	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Diesel\Receipts\
8_6_25.PDF	.PDF	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Diesel\Receipts\
8_1_25-8_31_25.xlsx	.xlsx	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Electricity\
August 2025 Miniforge Electricity Consumption Calculator.xlsx	.xlsx	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Electricity\
August 2025.csv	.csv	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Electricity\
Cap Ex MRV August.xlsx	.xlsx	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Embodied Emissions\
SP&C August.xlsx	.xlsx	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Embodied Emissions\
August 2025 PP Gasoline Consumption Calculator.xlsx	.xlsx	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Gasoline\
8_21_25.jpg	.jpg	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Gasoline\Gasoline Receipts\
8_5_25.jpg	.jpg	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Gasoline\Gasoline Receipts\
August 2025 Production Period Output Summary.xlsx	.xlsx	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Output\
Copy of 20250909 CAR-400.pdf	.pdf	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Output\Testing\
Copy of C Content WODO+QOWV .pdf	.pdf	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Output\Testing\
Propane Consumption Calculator 8_1_25-8_31_25.xlsx	.xlsx	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Propane\
8_11_25.PDF	.PDF	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Propane\Reciepts\Bulk\
8_14_25.PDF	.PDF	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Propane\Reciepts\Bulk\
8_18_25.PDF	.PDF	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Propane\Reciepts\Bulk\
8_19_25.PDF	.PDF	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Propane\Reciepts\Bulk\
8_26_25.PDF	.PDF	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Propane\Reciepts\Bulk\
8_5_25.PDF	.PDF	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Propane\Reciepts\Bulk\
Copy of 8_14_25.pdf	.pdf	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Propane\Reciepts\Cylinders\
Copy of 8_27_25.pdf	.pdf	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Propane\Reciepts\Cylinders\
Copy of 8_6_25.pdf	.pdf	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Propane\Reciepts\Cylinders\
8_1_25-8_31_25.png	.png	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Pyrolysis Up-Time\
Miniforge Pyrolysis Up-Time Reporting.xlsx	.xlsx	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Pyrolysis Up-Time\
August 2025 PP (8_1-8_31) Vendor Delivery Emissions Calc Sheet.xlsx	.xlsx	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Vendor Delivery Emissions Folder\
August 2025 PP Water Usage Log.xlsx	.xlsx	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\August 2025 Production Period\Water\

Production Period 8 Summary.xlsx	.xlsx	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\
PP8 (7_1-7_31) Biomass Throughput.xlsx	.xlsx	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Biomass Throughput\
Miniforge Biomass Transport Allocation -- Updated.xlsx	.xlsx	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Biomass Transport\
PP8 (7_1-7_31) Vendor Delivery Emissions Calc Sheet.xlsx	.xlsx	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Consumables Delivery\
Agfinity to Miniforge.png	.png	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Consumables Delivery\Vendor Distance Measurements\
Airgas to Miniforge.png	.png	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Consumables Delivery\Vendor Distance Measurements\
Miniforge to Ace.png	.png	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Consumables Delivery\Vendor Distance Measurements\
Miniforge to Buckeye.png	.png	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Consumables Delivery\Vendor Distance Measurements\
7_1_25-7_31_25 - 7_1_25-7_31_25.pdf	.pdf	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Electricity\
7_1_25-7_31_25.csv	.csv	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Electricity\
Date Range Screenshot.png	.png	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Electricity\
PP8 Miniforge Electricity Consumption Calculator.xlsx	.xlsx	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Electricity\
Cap Ex MRV July.xlsx	.xlsx	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Embodied Emissions\
SP&C July.xlsx	.xlsx	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Embodied Emissions\
PP8 Gasoline Consumption Calculator.xlsx	.xlsx	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Gasoline\
Gasoline Receipt.jpg	.jpg	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Gasoline\Gasoline Receipts\
Production Period 8 Output Summary.xlsx	.xlsx	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Output Data\
Biochar C Content Testing.pdf	.pdf	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Output Data\Testing\
WODO and Aqueous C Content.pdf	.pdf	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Output Data\Testing\
Propane Consumption Calculator 7_1_25-7_31_25.xlsx	.xlsx	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Propane\
7_14_25.PDF	.PDF	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Propane\Transaction Docs\Bulk\
7_18_25.PDF	.PDF	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Propane\Transaction Docs\Bulk\
7_1_25.PDF	.PDF	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Propane\Transaction Docs\Bulk\
7_23_25.PDF	.PDF	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Propane\Transaction Docs\Bulk\
7_28_25.PDF	.PDF	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Propane\Transaction Docs\Bulk\
7_31_25.PDF	.PDF	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Propane\Transaction Docs\Bulk\
7_7_25.PDF	.PDF	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Propane\Transaction Docs\Bulk\
7_16_25.pdf	.pdf	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Propane\Transaction Docs\Cylinders\
7_23_25.pdf	.pdf	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Propane\Transaction Docs\Cylinders\
7_2_25.pdf	.pdf	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Propane\Transaction Docs\Cylinders\
7_30_25.pdf	.pdf	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Propane\Transaction Docs\Cylinders\
7_9_25.pdf	.pdf	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Propane\Transaction Docs\Cylinders\

7_1_25-7_31_25.png	.png	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Up-Time Data\
Miniforge Pyrolysis Up-Time Reporting.xlsx	.xlsx	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Up-Time Data\
PP8 Water Usage Log.xlsx	.xlsx	Charm BO MRV-20251008T002952Z-1-001\Charm BO MRV\Charm Production Docs\Production Period 8\Water\
Additional Guidance / GHG Statement		
August_September Removals Isometric GHG Statement Report v1.6.docx	.docx	Additional Documentation-20251008T002956Z-1-001\Additional Documentation\
August_September VVB Guidance.docx	.docx	Additional Documentation-20251008T002956Z-1-001\Additional Documentation\
G+A Headcount 24-25.xlsx	.xlsx	Additional Documentation-20251008T002956Z-1-001\Additional Documentation\
August_September Removals Isometric GHG Statement Report v1.6.docx	.docx	Additional Documentation-20251008T002956Z-1-001\Additional Documentation\Deprecated\
2025 2nd Quarter Monitoring Well Report.pdf	.pdf	Additional Documentation-20251008T002956Z-1-001\Additional Documentation\Outstanding Vaulted Reporting\
ACS 2025 Second Quarter Report - AR-09.pdf	.pdf	Additional Documentation-20251008T002956Z-1-001\Additional Documentation\Outstanding Vaulted Reporting\
AR-09 KOLAR July 2025.pdf	.pdf	Additional Documentation-20251008T002956Z-1-001\Additional Documentation\Outstanding Vaulted Reporting\
Site Production Emissions		
8_15_25-9_8_25 Diesel Consumption Calcs.xlsx	.xlsx	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Diesel\
8_18_25.jpg	.jpg	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Diesel\Receipts\
8_19_25.jpg	.jpg	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Diesel\Receipts\
8_20_2025.jpg	.jpg	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Diesel\Receipts\
8_20_25.jpg	.jpg	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Diesel\Receipts\
8_26_25.pdf	.pdf	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Diesel\Receipts\
8_27_25.jpg	.jpg	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Diesel\Receipts\
8_31_25.jpg	.jpg	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Diesel\Receipts\
9_2_25.jpg	.jpg	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Diesel\Receipts\
9_4_25.jpg	.jpg	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Diesel\Receipts\
Basco Diesel (8_15-9_8) Vendor Delivery Emissions Calc Sheet.xlsx	.xlsx	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Diesel\Vendor Delivery Docs\
Basco to Moffitt .png	.png	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Diesel\Vendor Delivery Docs\
Basco Electricity Usage 8_15-9_8.xlsx	.xlsx	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Electricity\
8_16-9_8 Basco 6 + KS Embodied Emissions Inventory.xlsx	.xlsx	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Embodied Emissions\
8_15_25-9_8_25 Gasoline Tracker LA.xlsx	.xlsx	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Gasoline\
8_20_25.jpg	.jpg	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Gasoline\Receipts\
8_25_25.png	.png	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Gasoline\Receipts\
8_27_25.jpg	.jpg	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Gasoline\Receipts\
8_30_25.jpg	.jpg	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Gasoline\Receipts\
9_3_25.jpg	.jpg	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Gasoline\Receipts\
Basco Support Travel Calc Sheet.xlsx	.xlsx	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Support Travel\

Alexandria to B6 Distance.png	.png	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Support Travel\Measurements and Distances\
BTR to Alexandria Distance.png	.png	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Support Travel\Measurements and Distances\
BTR to Lafayette Distance.png	.png	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Support Travel\Measurements and Distances\
Denver to BTR Round Trip.png	.png	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Support Travel\Measurements and Distances\
Lafayette to Basco Well Site.png	.png	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Support Travel\Measurements and Distances\
SFO to BTR Round Trip.png	.png	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Support Travel\Measurements and Distances\
Wichita to BTR Round Trip.png	.png	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Support Travel\Measurements and Distances\
8_15_25-9_8_25 Brine Usage.xlsx	.xlsx	Site Emissions-20251008T002947Z-1-001\Site Emissions\Basco Injection\Water-Brine\
8_15-9_8 Diesel Consumption Calcs.xlsx	.xlsx	Site Emissions-20251008T002947Z-1-001\Site Emissions\KS Pre Processing\Diesel\
8_15_25-9_8_25 Electricity Use KS.xlsx	.xlsx	Site Emissions-20251008T002947Z-1-001\Site Emissions\KS Pre Processing\Electricity\
8_15-9_8 Gasoline Tracker KS.xlsx	.xlsx	Site Emissions-20251008T002947Z-1-001\Site Emissions\KS Pre Processing\Gasoline\
8_19_25.jpg	.jpg	Site Emissions-20251008T002947Z-1-001\Site Emissions\KS Pre Processing\Gasoline\Receipts\
9_2_25.jpg	.jpg	Site Emissions-20251008T002947Z-1-001\Site Emissions\KS Pre Processing\Gasoline\Receipts\
9_3_25.jpg	.jpg	Site Emissions-20251008T002947Z-1-001\Site Emissions\KS Pre Processing\Gasoline\Receipts\
9_4_25.jpg	.jpg	Site Emissions-20251008T002947Z-1-001\Site Emissions\KS Pre Processing\Gasoline\Receipts\
8_15-9_8 LCS Consumption Sheet.xlsx	.xlsx	Site Emissions-20251008T002947Z-1-001\Site Emissions\KS Pre Processing\LCS\
8_21_25.PDF	.PDF	Site Emissions-20251008T002947Z-1-001\Site Emissions\KS Pre Processing\LCS\
Waste Disposal Emissions Calc Sheet - KS.xlsx	.xlsx	Site Emissions-20251008T002947Z-1-001\Site Emissions\KS Pre Processing\Waste Disposal\
202507CI00001-10.pdf	.pdf	Site Emissions-20251008T002947Z-1-001\Site Emissions\KS Pre Processing\Waste Disposal\Manifests and Shipping Orders\
202507CI00001-11 (1).pdf	.pdf	Site Emissions-20251008T002947Z-1-001\Site Emissions\KS Pre Processing\Waste Disposal\Manifests and Shipping Orders\
202507CI00001-11.pdf	.pdf	Site Emissions-20251008T002947Z-1-001\Site Emissions\KS Pre Processing\Waste Disposal\Manifests and Shipping Orders\
202507CI00001-12.pdf	.pdf	Site Emissions-20251008T002947Z-1-001\Site Emissions\KS Pre Processing\Waste Disposal\Manifests and Shipping Orders\
202507CI00001-13.pdf	.pdf	Site Emissions-20251008T002947Z-1-001\Site Emissions\KS Pre Processing\Waste Disposal\Manifests and Shipping Orders\
202507CI00001-14.pdf	.pdf	Site Emissions-20251008T002947Z-1-001\Site Emissions\KS Pre Processing\Waste Disposal\Manifests and Shipping Orders\
202507CI00001-15.pdf	.pdf	Site Emissions-20251008T002947Z-1-001\Site Emissions\KS Pre Processing\Waste Disposal\Manifests and Shipping Orders\
202507CI00001-16.pdf	.pdf	Site Emissions-20251008T002947Z-1-001\Site Emissions\KS Pre Processing\Waste Disposal\Manifests and Shipping Orders\
202507CI00001-17.pdf	.pdf	Site Emissions-20251008T002947Z-1-001\Site Emissions\KS Pre Processing\Waste Disposal\Manifests and Shipping Orders\
202507CI00001-18.pdf	.pdf	Site Emissions-20251008T002947Z-1-001\Site Emissions\KS Pre Processing\Waste Disposal\Manifests and Shipping Orders\
202507CI00001-19.pdf	.pdf	Site Emissions-20251008T002947Z-1-001\Site Emissions\KS Pre Processing\Waste Disposal\Manifests and Shipping Orders\
202507CI00001-5.pdf	.pdf	Site Emissions-20251008T002947Z-1-001\Site Emissions\KS Pre Processing\Waste Disposal\Manifests and Shipping Orders\
202507CI00001-7.pdf	.pdf	Site Emissions-20251008T002947Z-1-001\Site Emissions\KS Pre Processing\Waste Disposal\Manifests and Shipping Orders\
202507CI00001-8.pdf	.pdf	Site Emissions-20251008T002947Z-1-001\Site Emissions\KS Pre Processing\Waste Disposal\Manifests and Shipping Orders\
202507CI00001-9.pdf	.pdf	Site Emissions-20251008T002947Z-1-001\Site Emissions\KS Pre Processing\Waste Disposal\Manifests and Shipping Orders\

3-30 Charm Contents.xlsx	.xlsx	Site Emissions-20251008T002947Z-1-001\Site Emissions\KS Pre Processing\Waste Disposal\Manifests and Shipping Orders\

APPENDIX 2: VERIFICATION AUDIT FINDINGS AND RESPONSES

ID No	Type	Finding / Issue	Audit Evidence	Protocol Reference	Required Action	Supplier Response	Conclusion / Resolution
1	Nonconformity	Weigh Scale ticket 'Scale Ticket 1 Empty' for batch 3-41 on certify (rmv_1K57SD2BG1S0EAGM) is incorrect and does not match trailer ID. MRV Ops Notes for 3-41 also shows a different value than on weigh ticket. Note that batch 3-41 injection data provided by Charm provides a correct ticket and (matches trailer ID) and matches value in MRV Ops Notes. So, appears only that the correct ticket needs to be in certify - no calculation updates needed.	Scale Ticket 1 Empty.jpg		Update certify with correct ticket	Evidence in Certify has been updated to reflect the correct scale ticket	Complete
2	Clarification	BOL 2199-T (shipment from AECN to KS) indicates only 1.32 tonnes, when the BOL shows 10 tonnes and typically these shipments are 19-20 tonnes. Please clarify that this is correct.			Clarify / confirm	2199-T was mostly allocated to 3-42 at the end of the previous Reporting Period (rmv_1K3PJJBN31S0KDER) so the 1.32 MT is just the remainder that was not allocated during the previous period.	Complete
3	Nonconformity (non-material error)	Related to the weigh scale ticket issue in item 1, the incorrect weigh scale ticket is also used in Certify in calcs for transport emissions for batch 3-41, resulting in an incorrect mass transported (21028.53 kg mass load vs 19168.79 kg). Impact on emission calculation is 1.62 ton vs 1.48 tons (non-material, but noted for accuracy)			We recommend updating for accuracy, but not required (non material)	Updated the emission and the reductions quantity on 3-41. Revised GHG Statement Report has been submitted	Complete
4	Nonconformity	For Batch 3-43 (rmv_1K59ZW9561S0P18M) on certify, the injection / Sequestration evidence is for Batch 3-42, so does not match the values in Certify. Data is provided in Google Drive that matches the 3-43 data and what is reported in Certify, so no incorrect values are attributed, but evidence must be updated in Certify			Update certify with correct information	Thank you for the catch, the document has been updated in Certify	Complete
5	FAR (prior)	Please plan to provide updated documentation on community engagement and stakeholder input activities by 12/31/2025				Will do -- Working with our Community Engagement Manager on this item	Review for future verifications
6	FAR (prior)	Please plan to provide updated documentation on grievance mechanism updates and any complaints/grievances received and responses (or confirmation of no issues) by 12/31/2025				Will do -- Working with our Community Engagement Manager on this item	Review for future verifications

7	FAR (prior)	Please ensure all waste disposal related emissions for future disposal of wastes which have been produced during this period are accounted for in future reporting periods as required. Note: Charm has properly accounted for all disposals so far and has all systems in place to do so going forward.				Absolutely -- We will continue to account for completed disposals as soon as they are completed and, if applicable, documentation is provided to quantify mass, confirm disposal method, etc.	Complete. Disposal emissions properly acounted for in this reporting period. Please continue to track and include as necessary.
8	Registry Issue	It was noted in last reporting period that, with the new storage process, the protocol requires a 5% buffer pool. The registry listing for the Aug1-Aug15 2025 removals cites the correct removal total, but only uses the previous 2% buffer pool that was set for the salt cavern storage	https://registry.isometric.com/issuance/iss_1K5XPYRDZ1S01XR9	https://registry.isometric.com/module/bio-oil-storage-in-permeable-reservoirs/1.1#risk-of-reversal	Work with Isometric to adjust buffer pool value to 5% and modify for this and prior reporting periods	Completed - updated buffer pool for subsequent issuances	Complete
9	Clarification	With injections no longer occurring at Vaulted, we would like to know how Charm will be notified of closure of the cavern where Charm oil was last injected, and to ensure that Charm will now be obtaining and submitting any post closure monitoring data to Isometric as part of the continued monitoring requirements. Please clarify that plans are in place for this and will be ongoing.	NA	Refer to 3.2, 3.3, 3.5 of : https://registry.isometric.com/module/salt-cavern-storage/1.1#closure-requirements		Charm has reached out to Vaulted on multiple occasions to get clarity regarding their future plans for the AR-09 injection well. The well still has considerable capacity and is the property of Vaulted, so it is up to them whether they plug and abandon the well or use it for their own emplacements. This decision on their part will affect the nature of the post-closure monitoring plan. We will continue to request clarity regarding these plans and, once received, we will define and submit a monitoring plan in light of the information we receive.	Complete. Noting that Vaulted monitoring reports are submitted to KDHE 30-60 days after month or quarter end so may not be available during the reporting period as part of GHG statement data submission. And, adding forward action request to provide post-closure monitoring plan as injections have now transitioned from Vaulted.
10	Registry Issue	The PDD Version posted on the Isometric Registry is v1.9. The current version which was significantly updated last reporting period is now v1.10	https://storage.googleapis.com/isometric--production--eu--public-documents/spl_1H31MW3T81S0R67B/prj_1HZS		Work with Isometric to get the updated PDD posted	https://storage.googleapis.com/isometric--production--eu--public-documents/spl_1H31MW3T81S0R67B/prj_1HZSSWBQM1S08H83/pjd_1K6ZPRB591S0QBVN/pdd.pdf	Completed

			SWBQM1S08H83/pjd_1JX2A6CPG1S0H8GA/pdd.pdf				
11	Nonconformity	Despite injections no longer occurring at Vaulted, the storage of the bio-oil in the Vaulted salt caverns is still the ultimate responsibility of Charm. With that, the requirements to continue post-emplacement and post-well-closure monitoring continue and must be submitted as part of the Charm Bio-oil storage project			Please submit the required Vaulted Salt Cavern monitoring records, including at a minimum: - monthly pressure monitoring reports - biannual temperature monitoring - quarterly report to KDHC - quarterly groundwater monitoring report - corrosion monitoring (permit schedule) - well integrity testing and inspection (permit schedule) - sonar survey (at full capacity and every 5 years)	ACS 2025 Second Quarter Report - AR-09 AR-09 KOLAR July 2025.pdf AR-09 KOLAR August 2025.pdf 2025 2nd Quarter Monitoring Well Report Well Report	Complete. Noting that Vaulted monitoring reports are submitted to KDHE 30-60 days after month or quarter end so may not be available during the reporting period as part of GHG statement data submission.

12	Nonconformity	Although the reports are not required to be submitted to LA any more than quarterly, we request that monitoring data for the injection site be provided with each Reporting Period to prove that Charm is completing the monitoring required. Please provide: - Bio-oil TAN, pH, density, O2 (if available), and viscosity results - formation fluid density and conductivity (monthly) - formation fluid salinity (continuous) - injection pressure and injection rate (continuous)	https://registry.isometric.com/module/bio-oil-storage-in-permeable-reservoirs/1.1#appendix-1-monitoring-plan-requirements		Please provide monitoring records listed	-Bio-oil TAN, density, and viscosity are included in the third party testing documents in each injection batch folder. -pH is provided in a separate document entitled "Batch pH values 8/15-9/8" that has been added to the Injection Lot Data folder. -Injection pressure and injection rate data averages and maximums are provided in the reporting submitted to LDENR. This has been added to a folder in the Reporting Package titled "Injection MRV" subfolder "LDENR Reporting" -Appendix 7 of the PDD addresses the availability of formation fluid for analysis after the start of bio-oil injection operations: While the Protocol accommodates the presence of a monitoring well, the Basco 6 EW project consists only of a single Well for injection. As a result, formation fluid analytes (i.e., pH, density, anions/cations, etc.) will not be available after bio-oil injection operations commence, as doing so would jeopardize previously sequestered bio-oil. This variance was reviewed and approved by Isometric prior to inclusion in the PDD.	Complete
13	FAR	With injections no longer occurring at Vaulted, please provide updated contract for post-emplacement / post-closure management and monitoring and post-closure monitoring plan that documents how Charm will be notified of closure of the cavern where Charm oil was last injected, and to ensure that Charm will now be obtaining and submitting any post closure monitoring data to Isometric as part of the continued monitoring requirements or this storage location			Please provide Post-Closure Monitoring Plan and copy of modified contract with storage partner regarding post-closure activities and responsibilities		Review for next reporting periods

APPENDIX 3: VERIFIER QUALIFICATIONS

Supporting documentation, including verifier resumes, and verifier or corporate accreditations are also included in this appendix.

Verifier Qualifications	Criteria Met?	Evidence / Notes *(note how the criteria was met, specific documents - resume/CV, publications, certifications, etc.).*
Verifier has relevant technical knowledge of the type of technology being evaluated and carbon removal processes in general		
A) Does Verifier have:		
1. An in-depth technical knowledge of the technology type under verification;	☑	350Solutions is accredited to ISO/IEC 17020:2012 and ISO 14034 Environmental Technology Verification (ETV) as a Type A (third party) Inspection Body (ANAB Certificate Number: AI-2618). The technical scope of 350's accreditation includes verification of performance and environmental impact as it relates to design, materials, equipment, installation and operations of technologies in the categories of Energy, Clean Production and Process, and Air Pollution Monitoring and Abatement. As documented in 350Solutions' ETV Standard Operating Procedure (ETV QPM 350-223-03), and Quality Systems Procedures for verifier qualifications (QSP-350-005-02), 350Solutions conforms to the requirements of ISO 17020 Annex A with respect to verifier qualifications and procedures. These procedures and quality management programs are generally relevant to verification under the Isometric Standard. Note that verifications completed for Isometric are not equivalent to ISO 14034 verifications. 350 staff have participated in the evaluation and verification of novel technologies that sequester carbon via various methods, including biomass conversion to liquids, solids, and other products which are then permanantly stored in ways such as land application or geologic storage, conversion of captured CO2 into building materials and co-products, and the production of chemicals, fuels, and products via biomass pyrolysis and gasification. 350 also served as lead verifier for the Carbon XPrize competition and contributed to the development of procedures and processes for verification of relevant calculations, modeling, and statistical methods in order to assess team results and calculations of performance metrics and uncertainty. 350 has demonstrated knowledge of data quality and data validation approaches and execution in supporting verification of performance claims and results.
2. Knowledge of specific risk areas associated with performance of such technologies (i.e. common failure points, performance issues, barriers to scaleup);	☑	
3. Knowledge of the environmental implications related to the use of the technology from a life cycle perspective, such as impact of the technology on lifecycle CO2 emissions and carbon removal;	☑	
4. Knowledge of relevant applicable test methods and standards for evaluating performance or impact of the technology;	☑	
5. Knowledge of relevant calculation, modeling, and statistical methods in order to assess test results and calculations of performance metrics and uncertainty, as applicable;	☑	
6. Knowledge of data quality and data validation approaches, including QA/QC procedures, for example.	☑	
Verifier is a credible independent 3rd party		
B) Is Verifier:		
1. third-party body independent of the team registered for the Isometric Registry	☑	350Solutions is accredited to ISO/IEC 17020:2012 and ISO 14034 ETV as a Type A (third party) Inspection Body. As documented in 350Solutions ETV Policy Manual (ETV QPM 350-200-03), 350Solutions conforms to the requirements of ISO 17020 Annex A with respect to impartiality for Type A inspections, pursuant to ISO 14034 activities.
2. Not directly involved in the design, manufacture or construction, marketing, installation, use or maintenance of the specific technologies submitted to Isometric for verification, or represent the parties engaged in those activities.	☑	
3. Not part of a legal entity that is engaged in design, manufacture, supply, installation, purchase, ownership, use or maintenance of the items inspected.	☑	

Tim Hansen, P.E.
Founder and CEO, 350Solutions

EDUCATION:
B.S., Chemical Engineering, University of Virginia, 1993
M.S., Engineering Science, Thayer School of Engineering, Dartmouth College, 1995

EXPERIENCE SUMMARY:
Mr. Hansen has 26 years of experience in management of energy and environmental technology development and demonstration projects and programs, as well as multimedia environmental engineering efforts. The majority of his recent work has focused on the evaluation of innovative carbon capture, utilization, and removal technologies. Mr. Hansen has led the development and management of large technology evaluation programs in the advanced energy, transportation, and climate change areas.

RESEARCH AND PROFESSIONAL EXPERIENCE:
2019-Present Founder – CEO, 350Solutions, Inc.
Owns and operates a small cleantech engineering consulting business focused on the independent evaluation of new cleantech innovations and their impact on the environment and carbon emissions. Provides engineering consulting, testing and evaluation, techno-economic assessment, and other support to companies developing, using, or investing in new clean technology innovations. Manages administrative, business development, and project activities for 350Solutions.

2012-2019: Director - Energy and Environment, Southern Research
Manages scientific and technical staff performing research, development, and evaluation of innovative clean energy technologies. Projects range from $25,000 to $6million in size, and are funded by the US Department of Energy, Department of Defense, and commercial partners. Technical focus areas are conversion of biomass to fuels and chemicals, carbon capture and utilization, energy efficient building technologies and renewable energy generation.

2009-2012: Program Manager – Transportation & Climate Change Technology, Southern Research
2003-2009 Sr. Project Leader, Environmental Engineer, Southern Research
1996-2003 Environmental Engineer, Bensinger & Garrison Environmental

PROJECT EXPERIENCE:
Mr. Hansen has executed several independent technology performance verifications of emerging carbon, energy and transportation technologies, as CEO of 350Solutions, Director of Energy & Environment at Southern Research, and Director of the U.S. EPA's Greenhouse Gas Technology Center. Mr. Hansen has completed clean technology evaluations for the Department of Defense, state energy agencies, commercial clients, investors, and technology developers, involving evaluation of commercial feasibility, economic and environmental impacts, and technology performance. Mr. Hansen served as the Measurement and Verification Program Lead for the NRG COSIA Carbon XPrize – a $20M prize competition for technologies that capture and beneficially utilize CO_2. Mr. Hansen also served as U.S. Technical Expert for the development and implementation of ISO 14034 – Environmental Technology Verification, an international standard, issued in 2016

Guy Ingram-Hardwick
Carbon Removal Verification Engineer, 350Solutions

EDUCATION:
MEng Materials Science and Engineering, Loughborough University, UK - 2022

EXPERIENCE SUMMARY:
Guy Ingram-Hardwick is a Materials Engineer with experience in process engineering, MRV protocol development, experimental design and life cycle analysis (LCA). At 350 Solutions, Guys efforts center on validation and verification of varied carbon removal pathways. Guy began his experience in the carbon markets directly after graduating working to develop an LCA model for Brilliant Planet, a marine based carbon removal company growing, processing and burying microalgae for carbon sequestration. Once completing the LCA model, Guy managed the third-party verification and co-authored a paper currently awaiting publication documenting the findings. Guy also co-authored the MRV methodology for Brilliant Planet before managing its adoption with carbon market registries and developing the relevant PDD documentation. Guy's Master's thesis in degradation mechanisms for biodegradable polymers resulted in another publication but also provided him experience in experimental design and execution which lead to his experience at Brilliant Planet in conducting field trials for developing novel technologies associated to the processing and storage of the microalgae, displaying the long-term permanence of the carbon removal system. Prior to his experience at Brilliant Planet, Guy worked as a process engineer at Pirelli's rubber compound manufacturing plant in Burton-on-Trent with a focus on data analytics for driving continuous improvement.

RESEARCH AND PROFESSIONAL EXPERIENCE:
January 2025 – Present: Carbon Removal Verification Engineer, 350Solutions
Verify carbon dioxide removal technologies on behalf of registries and private companies ensuring high quality and meaningful climate impact.

Jul 2022 – Dec 2025: LCA and MRV Associate, Brilliant Planet
Quantified the carbon removal efficiency of the Brilliant Planet system across a variety of engineering designs using LCA. Developed the proprietary MRV methodology and PDD as well as setting up a novel experimental design to display the permanence of the stored carbon.

July 2019 – September 2020: Process engineer, Pirelli
Completed data analytics to drive continuous improvement for increasing efficiency, safety and rubber compound quality.